GANITA PRAKASH

TEXTBOOK OF MATHEMATICS

GRADE
8
Part-I

© NCERT not to be republished

0874

विद्यया ऽमृतमश्नुते

एन सी ई आर टी
NCERT

राष्ट्रीय शैक्षिक अनुसंधान और प्रशिक्षण परिषद्
NATIONAL COUNCIL OF EDUCATIONAL RESEARCH AND TRAINING

Reprint 2026-27

0874 – Ganita Prakash
Textbook of Mathematics for Grade 8 (Part-I)

ISBN 978-93-5729-642-7

First Edition
July 2025 Ashadha 1947

Reprinted
January 2026 Magha 1947

PD 680T BS

©National Council of Educational Research and Training, 2025

₹ 65.00

Printed on 80 GSM paper with NCERT watermark

Published at the Publication Division by the Secretary, National Council of Educational Research and Training, Sri Aurobindo Marg, New Delhi 110 016 and printed at Kalyan Enterprises, D-20, Sector B-3, Trans Delhi Signature City (Tronica City) Industrial Area, Loni, Ghaziabad (U.P.) 201101

ALL RIGHTS RESERVED

- No part of this publication may be reproduced, stored in a retrieval system or transmitted, in any form or by any means, electronic, mechanical, photocopying, recording or otherwise without the prior permission of the publisher.
- This book is sold subject to the condition that it shall not, by way of trade, be lent, re-sold, hired out or otherwise disposed of without the publisher's consent, in any form of binding or cover other than that in which it is published.
- The correct price of this publication is the price printed on this page, Any revised price indicated by a rubber stamp or by a sticker or by any other means is incorrect and should be unacceptable.

OFFICES OF THE PUBLICATION DIVISION, NCERT

NCERT Campus
Sri Aurobindo Marg
New Delhi 110 016 **Phone : 011-26562708**

108, 100 Feet Road
Hosdakere Halli Extension
Banashankari III Stage
Bengaluru 560 085 **Phone : 080-26725740**

Navjivan Trust Building
P.O.Navjivan
Ahmedabad 380 014 **Phone : 079-27541446**

CWC Campus
Opp. Dhankal Bus Stop
Panihati
Kolkata 700 114 **Phone : 033-25530454**

CWC Complex
Maligaon
Guwahati 781 021 **Phone : 0361-2674869**

Publication Team

Head, Publication Division : *M.V. Srinivasan*

Chief Editor : *Bijnan Sutar*

Chief Business Manager : *Amitabh Kumar*

Chief Production Officer (In charge) : *Deepak Jaiswal*

Assistant Production Officer : *Prakash Veer Singh*

Cover and Layout
Creative Art Studio

Illustrations
Chetan Sharma and Madhushree Basu

© NCERT not to be republished

FOREWORD

The National Education Policy (NEP) 2020 envisages a system of education in the country that is rooted in an Indian ethos and its civilisational accomplishments in all fields of knowledge and human endeavour. At the same time, it aims to prepare students to engage constructively with the opportunities and challenges of the twenty-first century. The basis for this aspirational vision has been well laid out by the National Curriculum Framework for School Education (NCF-SE) 2023 across curricular areas at all stages. By nurturing students' inherent abilities across all five planes of human existence (*pañchakośhas*), the Foundational and Preparatory Stages set the Stage for further learning at the Middle Stage. Spanning Grades 6 to 8, the Middle Stage serves as a critical three-year bridge between the Preparatory and Secondary Stages.

The NCF-SE 2023, at the Middle Stage, aims to equip students with the skills that are needed to grow, as they advance in their lives. It aims to enhance their analytical, descriptive, and narrative capabilities, and to prepare them for the challenges and opportunities that await them. A diverse curriculum, covering nine subjects ranging from three languages—including at least two languages native to India—to Science, Mathematics, Social Sciences, Art Education, Physical Education and Well-being, and Vocational Education promotes their holistic development.

Such a transformative learning culture requires certain essential conditions. One of them is to have appropriate textbooks in different curricular areas, as these textbooks are intended to play a central role in mediating between content and pedagogy's role that helps strike a judicious balance between direct instruction and opportunities for exploration and inquiry. Among the other conditions, classroom arrangement and teacher preparation are crucial to establish conceptual connections both within and across curricular areas.

The National Council of Educational Research and Training (NCERT), on its part, is committed to providing students with such high-quality textbooks. Various Curricular Area Groups (CAGs), which have been constituted for this purpose, comprising notable subject-experts, pedagogues, and practising teachers as their members, have made all possible efforts to develop such textbooks. *Ganita Prakash*, the textbook of mathematics for Grade 8 (Part 1) is designed to make learning fun, engaging, and meaningful. Aligned with NEP 2020 and NCF-SE 2023, the textbook continues to foster the spirit of experiential and inquiry-based learning, a spirit already introduced in the mathematics textbooks for Grades 6 and 7. It encourages students to ask questions, think critically, and understand concepts of mathematics through real-world contexts.

© NCERT not to be republished

The textbook makes efforts to encourage the students to observe and explore patterns around them and discover mathematical concepts on their own. The content is structured in a way that supports a joyful and progressive understanding of increasingly complex concepts, easing students into more advanced learning. The content attempts to integrate mathematics with other subject areas, such as Science, Social Science with cross-cutting themes like environmental education, value education, inclusive education, and Indian Knowledge Systems (IKS). At most of the places the concept begins with either a story or a puzzle that not only makes students think but also feels the importance of the concept.

However, in addition to this textbook, students at this stage should also be encouraged to explore various other learning resources. School libraries play a crucial role in making such resources available. Besides, the role of parents and teachers will also be invaluable in guiding and encouraging students to do so.

With this, I express my gratitude to all those who have been involved in the development of this textbook, and hope that it will meet the expectations of all stakeholders. At the same time, I also invite suggestions and feedback from all its users for further improvement in the coming years.

Dinesh Prasad Saklani
Director
National Council of Educational
Research and Training

New Delhi
June 2025

© NCERT not to be republished

Reprint 2026-27

ABOUT THE BOOK

Mathematics helps students develop not only basic arithmetic skills, but also the crucial capacities of logical reasoning, creative problem-solving, and clear and precise communication (both oral and written). Mathematical knowledge also plays a crucial role in understanding concepts in other school subjects, such as Science and Social Science, and even Arts, Physical Education, and Vocational Education. Learning Mathematics contributes to the development of capacities to make informed choices and decisions. Understanding numbers and quantitative arguments is necessary for effective and meaningful democratic and economic participation. Mathematics thus plays an important role in achieving the overall aims of school education.

Mathematics at the Middle Stage is a major challenge and performs the dual role of being both close to the experience and environment of a learner and being abstract. It performs the role of developing intuition, while also maintaining and emphasising rigour. It is enhancing critical and logical thinking, while also developing artistry and creativity, and a sense of elegance and aesthetics. Mathematics provides students with plenty of opportunities to explore and discover concepts on their own while also teaching the best-known methods in the global repertoire of mathematics.

This textbook attempts to address the goals and challenges of learning mathematics. The writers have aimed to strike a judicious balance between informal and formal definitions and methods in helping students to develop both intuition and rigour. The textbook also provides numerous opportunities for student-student and student–teacher interaction in the classroom to promote active and experiential learning. A number of questions, puzzles, and interactive exercises are posed throughout the textbook to encourage constant exploration. Many of the questions are open-ended to stimulate classroom discussion.

The Chapter 1: 'A Square and A Cube' is an introduction to the special types of numbers called squares and cubes through engaging explorations, and contexts. Chapter 2: 'Power Play' considers short and logical ways of expressing very large numbers, and discusses how they can be written and read without ambiguity. Chapter 3: 'A Story of Numbers' reveals how the idea of number and number representation evolved over the course of time, across different places in the world, to finally reach its modern efficient form. Chapter 4: 'Quadrilaterals' discusses some interesting types of four-sided figures and problems based on them. Chapter 5: 'Number Play' shows different properties of numbers studied by the students with a balance of engaging activities

© NCERT not to be republished

through visualisation and rigorous mathematical reasoning. Chapter 6: 'We Distribute, Yet Things Multiply' covers aspects related to Algebra, and in particular, the distributive law. Chapter 7: 'Proportional Reasoning' explores a new way to compare two quantities using daily life situations. In all the chapters, an attempt has been made to emphasise connections with other subjects including Art, History and Science.

By weaving storytelling and hands-on activities together, as done in Grades 6 and 7, we hope that an immersive learning experience will be created that ignites curiosity and fosters a love for mathematics. It is hoped that teachers would give students the opportunity to discuss, play, engage with each other and provide logical arguments for different ideas, and find loopholes in arguments presented. This is necessary for the learners to eventually develop the ability to understand what it means to prove something and also become confident about the underlying concepts. The mathematics classroom should not expect a blind application of algorithms but should rather encourage students to find many different ways to solve problems.

As per the National Education Policy (NEP) 2020, computational thinking has also been gently introduced through puzzles, games, and interactive exercises that encourage students on these aspects. Indian rootedness has also been kept in mind while giving contexts for different concepts. The contributions of Indian mathematicians have also been given as part of a problem-solving approach to make students aware of India's rich mathematical heritage and its global contributions to mathematics.

The concepts and problems in this textbook are related to daily life situations. An attempt has been made to use contexts and materials that students are familiar with. Learning material sheets have been given at the back of the book that may be photocopied and used in the classroom. Exercises or activities are often given to encourage peer group efforts and discussions. However, this textbook intends to address the learning needs of a diverse group of students in the classroom.

We have tried to link concepts learnt in initial chapters with ideas in subsequent chapters, to show the connectedness and unity of mathematics. We hope that teachers can revise these concepts in a spiralling way so that students are able to appreciate the entire conceptual structure of mathematics. We hope that teachers may focus more on the ideas of squares and cubes, exponents, evolution of numbers and other notions that are new to the students, and are foundational for further learning.

Finally, this textbook aims to be more than just a textbook—it is a passport to a world of mathematical discovery and exploration. Whether used in the classroom or at home, we hope that it inspires

Reprint 2026-27

students to embark on their own mathematical adventures, empowering them to see the beauty and relevance of Mathematics in everything. With its engaging approach and comprehensive coverage of Grade 8 mathematics concepts, this textbook aims to captivate young minds and set them on a lifelong journey of mathematical discovery.

I once again thank all the writers of and contributors of this textbook for their valuable contribution and service to the nation's mathematics teachers, learners and enthusiasts.

We look forward to your comments and suggestions regarding the textbook and hope that you will send interesting exercises, activities and tasks that you may develop while teaching and learning for future editions.

Ashutosh Wazalwar
Professor and *Academic Convener*
Department of Education in
Science and Mathematics
National Council of Educational
Research and Training

© NCERT not to be republished

Reprint 2026-27

NATIONAL SYLLABUS AND TEACHING LEARNING MATERIAL COMMITTEE (NSTC)

1. M.C. Pant, *Chancellor*, National Institute of Educational Planning and Administration (NIEPA) **(Chairperson)**
2. Manjul Bhargava, *Professor*, Princeton University **(Co-Chairperson)**
3. Sudha Murty, Acclaimed *Writer* and *Educationist*
4. Bibek Debroy, *Chairperson*, Economic Advisory Council to the Prime Minister (EAC–PM)
5. Shekhar Mande, Former *Director General*, CSIR, Distinguished Professor, Savitribai Phule Pune University, Pune
6. Sujatha Ramdorai, *Professor*, University of British Columbia, Canada
7. Shankar Mahadevan, Music Maestro, Mumbai
8. U. Vimal Kumar, *Director*, Prakash Padukone Badminton Academy, Bengaluru
9. Michel Danino, Visiting Professor, IIT–Gandhinagar
10. Surina Rajan, *IAS* (Retd.), Haryana, Former *Director General*, HIPA
11. Chamu Krishna Shastri, *Chairperson*, Bharatiya Bhasha Samiti, Ministry of Education
12. Sanjeev Sanyal, Member, Economic Advisory Council to the Prime Minister (EAC–PM)
13. M.D. Srinivas, *Chairperson*, Centre for Policy Studies, Chennai
14. Gajanan Londhe, *Head*, Programme Office
15. Rabin Chhetri, *Director*, SCERT, Sikkim
16. Pratyusa Kumar Mandal, *Professor*, Department of Education in Social Sciences, NCERT, New Delhi
17. Dinesh Kumar, *Professor*, Department of Education in Science and Mathematics, NCERT, New Delhi
18. Kirti Kapur, *Professor*, Department of Education in Languages, NCERT, New Delhi
19. Ranjana Arora, *Professor* and *Head*, Department of Curriculum Studies and Development, NCERT **(Member-Secretary)**

© NCERT not to be republished

TEXTBOOK DEVELOPMENT TEAM

Contributors

Amartya Kumar Dutta, *Professor*, Stat-math Unit, Indian Statistical Institute (ISI), Kolkata

Anjali Gupte, *Principal* (Retd.), Vidya Bhavan Public School, Udaipur

Ashutosh Kedarnath Wazalwar, *Professor*, Department of Education in Science and Mathematics, NCERT, New Delhi—CAG (Mathematics) **(Member Coordinator)**

H. S. Sharada, *Assistant Mistress*, Government High School, M. C. Thalalu, H. D. Kote Taluk, Mysore, Karnataka

Madhavan Mukund, *Director*, Chennai Mathematical Institute, Chennai—CAG *Chairperson* (Mathematics)

Madhu B., *Assistant Professor*, Regional Institute of Education (RIE), Mysuru

Manjul Bhargava, *Professor*, Princeton University, and *Co-Chairperson*, NSTC

Padmapriya Shirali, Former *Principal*, Sahyadri School KFI, Pune

Patanjali Sharma, *Assistant Professor*, Regional Institute of Education, (RIE), Ajmer

Ramchandar Krishnamurthy, *Principal*, Azim Premji School, Bengaluru

Shivkumar K. M., *Senior Consultant*, Programme Office, NSTC,

Shravan S. K., *Senior Consultant*, Programme Office, NSTC

Reviewers

Aaloka Kanhere, *Project Scientific Officer*, Homi Bhabha Centre for Science Education, Mumbai

Aparna Lalingakar, *Director*, Aksharbrahma Consultancy, Pune—(Team Leader)

Rakhi Bannerjee, *Associate Professor*, Azim Premji University, Bengaluru

Sujatha Ramdorai, *Professor*, University of British Columbia, Canada, Member NSTC

Vijayan K., *Professor*, Department of Curriculum Studies and Development, NCERT, New Delhi

© NCERT not to be republished

ACKNOWLEDGEMENTS

The National Council of Educational Research and Training (NCERT) acknowledges the guidance and support of the esteemed Chairperson and members of the Curricular Area Group (CAG): Mathematics, and other concerned CAGs for their guidelines on cross-cutting themes in developing this textbook. During the development of this textbook, various workshops were organised and subject experts from different Institutions were invited. The NCERT acknowledges the valuable views and inputs given by subject experts—Sreelatha Iyengar, *TGT* Mathematics, Bengaluru; Jaspal Kaur, TGT (Maths), School of Excellence, Delhi; Sunita Sharma, *TGT* Mathematics, The Heritage School, Delhi; Sangeeta Solanki, *TGT* Mathematics, The Heritage School, Delhi; Rishikesh Kumar, *Assistant Professor*, DESM, NCERT, New Delhi.

The Council acknowledges the efforts of Nidhi M. Shastri and Tarun Choubisa from the Programme Office; and Sneha Titus, *Cheif Editor*, At Right Angles, Azim Premji University, Bengaluru, Ramu MS *Philatelist*, for providing the pictures of the stamps of some endangered species; Shweta Rao, Banyan Tree, New Delhi for providing Infographic; and Arkaprovo Das for making world maps.

Acknowledgements are due for the academic and administrative support of Sunita Farkya, *Professor* and *Head*, DESM, NCERT, New Delhi.

The Council appreciates the contributions of Sushmita Joshi, *Senior Research Associate*, Department of Education in Science and Mathematics, NCERT for providing support in the development of the textbook. The NCERT gratefully acknowledges the contributions of Kishore Singhal, Ayaz Ahmad Ansari, DTP Operators (contractual), Publication Division, and Abhilash Kumar, DTP Operator of DESM NCERT for all their efforts.

The Council acknowledges the efforts of Ilma Nasir, *Editor* (contractual); Adiba Tasneem, Ariba Usman, Jatinder Kumar, Praveen Kumar and Talha Faisal Khan, *Proofreaders* (contractual), Publication Division, NCERT. The Council also appreciates the efforts of Pawan Kumar Barriar, *In charge*, DTP Cell; Mohan Singh, Vivek Mandal and Anita Kumari *DTP Operators* (contractual), Publication Division, NCERT, for finalising this textbook.

© NCERT not to be republished

NOTE TO THE TEACHER

We hope that this book, *Ganita Prakash*, will serve as a strong support and guide to you in achieving the exciting task that you have before you: that of passing on the joy of learning the beautiful subject of Mathematics to the next generation.

This task calls for providing a fertile environment that allows for the flowering of mathematical thinking in the minds of students. Classrooms, where students just listen and write down whatever is being told to them or written on the board, are deficient in the conditions required for learning mathematics. Instead, classrooms need to be places where students are engaged in playing with mathematical concepts, finding and discussing patterns, and developing creative strategies together to solve problems. Students should also be posing problems to each other and discussing possible solutions with each other. In fact, these are the very conditions that have led to the development of the entire field of mathematics so far, and so one cannot expect students to pick up mathematical thinking and understanding without these conditions.

Fortunately, it is not difficult to create such conditions in the classroom. It just requires an interesting question, problem, pattern, or challenge to be thrown open to the students on a regular basis, and sufficient time to be given to them to play with, discuss, and work on it as a class or in pairs or groups.

Along with it, an environment that accepts mistakes and acknowledges their importance in learning needs to be nurtured.

While creating the spark for initiating mathematical thinking in classrooms is not difficult, sustaining it may be challenging and may involve efforts from your side. Nevertheless, even if just the first part of throwing open a question, problem, pattern, or challenge is done at least once or twice a week, accompanied by sufficient waiting time from your side for students to play, discuss, and work on it, it can have a great positive impact on how the students view and approach mathematics.

It should be noted that this positive impact will not happen overnight. That takes time and depends on various factors such as the number of opportunities you give for problem solving, your patience, and the encouragement you give to the students.

To support you in posing problems, all the problems or questions in this book are marked using the icons ? and ?. These icons are indicators of potential opportunities to start off a process of problem-solving and exploration in the classroom. You will find some of the problems labelled '

'. Such questions can especially be made as topics for classroom discussion.

© NCERT not to be republished

An owl mascot appears at various points in the textbook to highlight important mathematical processes, ways of thinking, and problem-solving approaches. These can be brought out during classroom discussions, both where the owl is present and also in other similar situations.

In this grade, justification/proofs of mathematical statements find an increased presence. Students should be gently encouraged to deduce properties and not be forced to do it. Whenever students face challenges in doing it, encourage them to experiment and observe, and use their intuition in figuring out properties. Providing justification/ proof is a skill that takes time to develop.

To develop students' mathematical thinking and understanding of concepts, a sufficient number of problems are given. Trying to 'cover' all of them must not happen at the cost of students not getting to spend quality time on playing with and discussing them.

It is important to understand that the exploratory problems are not only for promoting problem solving skills; they also serve in strengthening procedural fluency when children start engaging in exploration.

Efforts must be made in making students independent learners. One essential aspect required for this is an ability to read and understand mathematical text. To promote this skill, students should be encouraged to read the book by themselves and in groups. Give opportunities to them to interpret what they read and express it to others. This will also address the big problem that students face in speaking mathematics and interpreting word problems.

This textbook contains a number of open-ended problems. It also contains new treatments of certain concepts. If you are not able to solve them or follow some of them immediately, it is perfectly okay! Not everyone knows everything. Along with trying to understand and reflect upon such content,it will be very useful to take it to the classroom and open it up for discussion. After the discussion, things that are clear and those that are not yet clear can be clearly summarised. This process itself can throw a lot of light on the content.

In these discussions, you can participate as a fellow seeker, and when students see a teacher seek and think to understand something, it sets a wonderful example for them.

It is hoped that you and your students will have a great and fruitful time using this textbook!

© NCERT not to be republished

Summary of Key Points

Time for Exploration

1. It is important to routinely pose new problems, questions, patterns, or challenges to the students and give them sufficient time to play with, discuss, and work on them, individually and in groups.
2. During this time, an environment that accepts mistakes and acknowledges their importance in learning needs to be nurtured.
3. There should be a culture where students pose problems to each other and discuss with each other various ways to approach the problems.

About the Problems in the Book

1. The exploratory problems in the book not only promote problem solving; they also aim to strengthen procedural fluency when students start engaging in exploration.
2. Trying to 'cover' all the problems in the book must not happen at the cost of students not getting to spend quality time on playing with, discussing, and solving them.

Reading

1. Encourage students to read the book by themselves and in groups.
2. Give opportunities to them to interpret what they read and to express it to others.

Right of Not Knowing!

1. It is perfectly okay if some of the content is not understood immediately. Along with trying to understand and reflect upon such content, it can also be taken to the classroom and opened up for discussion. After the discussion, things that are clear and those that are not yet clear can be clearly summarised. In these discussions, you can participate as a fellow seeker, and when students see a teacher seek and think to understand something, it sets a wonderful example for them!
2. Learning is a continual process. Indeed, there is so much in mathematics that is still not known and requires further exploration!

© NCERT not to be republished

Reprint 2026-27

A NOTE TO STUDENTS!

To be able to appreciate the art of mathematics, it is not enough to just be a passive spectator. You need to immerse yourself in its process like a detective getting into action to solve a mystery.

This is especially required when you see a new question or when a question arises from your own sense of wonder, or when you come across a new beautiful pattern. When you encounter these, pause your reading, and use your creativity to work out the question or understand and appreciate the pattern.

You will find that some questions are accompanied by their answers. Even if this is the case, it is worthwhile to work on the problems by yourself or in a group before you see the answer.

This will enrich your experience of going through the book!

Whenever there are questions coming up, you will see the icon ? and ?. This indicates that it is time for figuring things out! ? indicates a main question and ? indicates a sub-question.

The icons for owls and suggest some important processes in the learning of mathematics.

Sometimes you will find many questions collected together in a single place under the title '**Figure it Out**'.

Some questions are marked

. These questions are meant to be discussed and worked out with your peers.

Finally, there are questions marked

. These questions demand more creativity to be answered, and therefore will also often be more fun to answer as a result!

© NCERT not to be republished

CONTENTS

Foreword *iii*
About the Book *v*
Note to the Teacher *xi*
A Note to Students *xiv*

Chapter 1
A Square and A Cube 1

Chapter 2
Power Play 19

Chapter 3
A Story of Numbers 48

Chapter 4
Quadrilaterals 82

Chapter 5
Number Play 112

Chapter 6
We Distribute, Yet Things Multiply 136

Chapter 7
Proportional Reasoning-1 159

© NCERT not to be republished

THE CONSTITUTION OF INDIA

PREAMBLE

WE, THE PEOPLE OF INDIA, having solemnly resolved to constitute India into a [1]**[SOVEREIGN SOCIALIST SECULAR DEMOCRATIC REPUBLIC]** and to secure to all its citizens :

JUSTICE, social, economic and political;

LIBERTY of thought, expression, belief, faith and worship;

EQUALITY of status and of opportunity; and to promote among them all

FRATERNITY assuring the dignity of the individual and the [2][unity and integrity of the Nation];

IN OUR CONSTITUENT ASSEMBLY this twenty-sixth day of November, 1949 do **HEREBY ADOPT, ENACT AND GIVE TO OURSELVES THIS CONSTITUTION.**

---

1. Subs. by the Constitution (Forty-second Amendment) Act, 1976, Sec.2, for "Sovereign Democratic Republic" (w.e.f. 3.1.1977)
2. Subs. by the Constitution (Forty-second Amendment) Act, 1976, Sec.2, for "Unity of the Nation" (w.e.f. 3.1.1977)

1 A SQUARE AND A CUBE

0874CH01

Queen Ratnamanjuri had a will written that described her fortune of *ratnas* (precious stones) and also included a puzzle. Her son Khoisnam and their 99 relatives were invited to the reading of her will. She wanted to leave all of her *ratnas* to her son, but she knew that if she did so, all their relatives would pester Khoisnam forever. She hoped that she had taught him everything he needed to know about solving puzzles. She left the following note in her will—

"I have created a puzzle. If all 100 of you answer it at the same time, you will share the *ratnas* equally. However, if you are the first one to solve the problem, you will get to keep the entire inheritance to yourself. Good luck."

The minister took Khoisnam and his 99 relatives to a secret room in the mansion containing 100 lockers.

The minister explained— "Each person is assigned a number from 1 to 100.

- Person 1 opens every locker.
- Person 2 toggles every 2nd locker (i.e., closes it if it is open, opens it if it is closed).
- Person 3 toggles every 3rd locker (3rd, 6th, 9th, ... and so on).
- Person 4 toggles every 4th locker (4th, 8th, 12th, ... and so on).

This continues until all 100 get their turn.

In the end, only some lockers remain open. The open lockers reveal the code to the fortune in the safe."

? Before the process begins, Khoisnam realises that he already knows which lockers will be open at the end. How did he figure out the answer?

Hint: Find out how many times each locker is toggled.



© NCERT not to be republished

If a locker is toggled an odd number of times, it will be open. Otherwise, it will be closed. The number of times a locker is toggled is the same as the number of factors of the locker number. For example, for locker #6, Person 1 opens it, Person 2 closes it, Person 3 opens it and Person 6 closes it. The numbers 1, 2, 3, and 6 are factors of 6. If the number of factors is even, the locker will be toggled by an even number of people and it will eventually be closed.

Note that each factor of a number has a 'partner factor' so that the product of the pair of factors yields the given number. Here, 1 and 6 form a pair of partner factors of 6, and 2 and 3 form another pair.

6:
1 × 6
2 × 3
Factors are
1, 2, 3 and 6.

? Does every number have an even number of factors?

1:
1 × 1
The only factor is 1.

4:
1 × 4
2 × 2
Factors are
1, 2 and 4.

9:
1 × 9
3 × 3
Factors are
1, 3 and 9.

We see in some cases, like 2 × 2, that the numbers in the pair are the same.

? Can you use this insight to find more numbers with an odd number of factors?

For instance, 36 has a factor pair 6 × 6 where both numbers are 6. Does this number have an odd number of factors? If every factor of 36 other than 6 has a different factor as its partner, then we can be sure that 36 has an odd number of factors. Check if this is true.

Hence all the following numbers have an odd number of factors —

$$1 \times 1, 2 \times 2, 3 \times 3, 4 \times 4, \ldots$$

A number that can be expressed as the product of a number with itself is called a **square number,** or simply a **square**. The only numbers that have an odd number of factors are the squares, because they each have one factor which, when multiplied by itself, equals the number. Therefore, every locker whose number is a square will remain open.

© NCERT not to be republished

? Write the locker numbers that remain open.

Khoisnam immediately collects word clues from these 10 lockers and reads, "The passcode consists of the first five locker numbers that were touched exactly twice."

? Which are these five lockers?

The lockers that are toggled twice are the prime numbers, since each prime number has 1 and the number itself as factors. So, the code is 2-3-5-7-11.

1.1 Square Numbers

Why are the numbers, 1, 4, 9, 16, ..., called squares? We know that the number of unit squares in a square (the area of a square) is the product of its sides. The table below gives the areas of squares with different sides.

Sidelength (in units)	Area (in sq units)
1	1 × 1 = 1 sq. unit
2	2 × 2 = 4 sq. units
3	3 × 3 = 9 sq. units
4	4 × 4 = 16 sq. units
5	5 × 5 = 25 sq. units
10	10 × 10 = 100 sq. units



We use the following notation for squares.

$1 \times 1 = 1^2 = 1$
$2 \times 2 = 2^2 = 4$
$3 \times 3 = 3^2 = 9,$
$4 \times 4 = 4^2 = 16$
$5 \times 5 = 5^2 = 25.$
⋮

In general, for any number n, we write $n \times n = n^2$, which is read as 'n squared'.

Can we have a square of sidelength $\frac{3}{5}$ or 2.5 units?

Yes, there area in square units are $(\frac{3}{5})^2 = (\frac{3}{5}) \times (\frac{3}{5}) = (\frac{9}{25})$,

and $(2.5)^2 = (2.5) \times (2.5) = 6.25$.

© NCERT not to be republished

The squares of natural numbers are called **perfect squares.** For example, 1, 4, 9, 16, 25, ... are all perfect squares.

Patterns and Properties of Perfect Squares

Find the squares of the first 30 natural numbers and fill in the table below.

$1^2 = 1$	$11^2 = 121$	$21^2 = 441$
$2^2 = 4$	$12^2 =$	$22^2 =$
$3^2 = 9$	$13^2 =$	
$4^2 = 16$	$14^2 =$	
$5^2 = 25$	$15^2 =$	
$6^2 =$	$16^2 =$	
$7^2 =$	$17^2 =$	
$8^2 =$	$18^2 =$	
$9^2 =$	$19^2 =$	
$10^2 =$	$20^2 =$	

? What patterns do you notice? Share your observations and make conjectures.

Math Talk

Study the squares in the table above. What are the digits in the units places of these numbers? All these numbers end with 0, 1, 4, 5, 6 or 9. None of them end with 2, 3, 7 or 8.

? If a number ends in 0, 1, 4, 5, 6 or 9, is it always a square?

Math Talk

The numbers 16 and 36 are both squares with 6 in the units place. However, 26, whose units digit is also 6, is not a square. Therefore, we cannot determine if a number is a square just by looking at the digit in the units place. But, the units digit can tell us when a number is not a square. If a number ends with 2, 3, 7, or 8, then we can definitely say that it is not a square.

? Write 5 numbers such that you can determine by looking at their units digit that they are not squares.

The squares, 1^2, 9^2, 11^2, 19^2, 21^2, and 29^2, all have 1 in their units place. Write the next two squares. Notice that if a number has 1 or 9 in the units place, then its square ends in 1.

? Let us consider square numbers ending in 6: $16 = 4^2$, $36 = 6^2$, $196 = 14^2$, $256 = 16^2$, $576 = 24^2$, and $676 = 26^2$.

© NCERT not to be republished

Which of the following numbers have the digit 6 in the units place?

(i) 38^2 (ii) 34^2 (iii) 46^2 (iv) 56^2 (v) 74^2 (vi) 82^2

? Find more such patterns by observing the numbers and their squares from the table you filled earlier.

Consider the following numbers and their squares.



? If a number contains 3 zeros at the end, how many zeros will its square have at the end?

? What do you notice about the number of zeros at the end of a number and the number of zeros at the end of its square? Will this always happen? Can we say that squares can only have an even number of zeros at the end?

? What can you say about the parity of a number and its square?

Perfect Squares and Odd Numbers

Let us explore the differences between consecutive squares. What do you notice?

$4 - 1 = \mathbf{3}$ $9 - 4 = \mathbf{5}$ $16 - 9 = \mathbf{7}$ $25 - 16 = \mathbf{9}$

See if this pattern continues for the next few square numbers.

From this we observe that adding consecutive odd numbers starting from 1 gives consecutive square numbers, as shown below.

$1 = \mathbf{1}$
$1 + 3 = \mathbf{4}$
$1 + 3 + 5 = \mathbf{9}$
$1 + 3 + 5 + 7 = \mathbf{16}$
$1 + 3 + 5 + 7 + 9 = \mathbf{25}$
$1 + 3 + 5 + 7 + 9 + 11 = \mathbf{36}.$



© NCERT not to be republished

Do you remember this pattern from Grade 6?
The picture below explains why each subsequent inverted L gives the next odd number:



1 + 3 1 + 3 + (3 + 2) 1 + 3 + 5 1 + 3 + 5 + (5 + 2) 1 + 3 + 5 + 7

We see that the sum of the first n odd numbers is n^2. Alternatively, every square is a sum of successive odd numbers starting from 1.

In mathematics, sometimes arguments and reasoning can be presented without any words. Visual proofs can be complete by themselves.

Also, we can find out whether a number is a perfect square by successively subtracting odd numbers. Consider the number 25, successively subtract 1, 3, 5, ... until you get or cross over 0,

25 – 1 = 24 24 – 3 = 21 21 – 5 = 16 16 – 7 = 9 9 – 9 = 0

This means 25 = 1 + 3 + 5 + 7 + 9 and is thus a perfect square. Since we subtracted the first five odd numbers, $25 = 5^2$.

? Using the pattern above, find 36^2, given that $35^2 = 1225$.

From the question we know that 1225 is the sum of the first 35 odd numbers. To find 36^2, we need to add the 36th odd number to 1225.

? How do we find the 36th odd number?

The 1st odd number is 1, 2nd odd number is 3, 3rd number is 5, ..., 6th odd number is 11 and so on.

? What is the n^{th} odd number?

The n^{th} odd number is $2n–1$.
Therefore, the 36th odd number is 71.
By adding 71 to 1225, we get 1296, which is 36^2.

Consider a number such as 38 that is not a square and subtract consecutive odd numbers starting from 1.

38 – 1 = 37 37 – 3 = 34 34 – 5 = 29 29 – 7 = 22 22 – 9 = 13

13 – 11 = 2 2 – 13 = – 11

This shows that 38 cannot be expressed as a sum of consecutive odd numbers starting with 1.

© NCERT not to be republished

Thus, we can say that a natural number is not a perfect square if it cannot be expressed as a sum of successive odd natural numbers starting from 1. We can use this result to find out whether a natural number is a perfect square.

? Find how many numbers lie between two consecutive perfect squares. Do you notice a pattern?

? How many square numbers are there between 1 and 100? How many are between 101 and 200? Using the table of squares you filled earlier, enter the values below, tabulating the number of squares in each block of 100. What is the largest square less than 1000?

1 –100	101 – 200	201 – 300	301 – 400	401 – 500
____	____	____	____	____
501 – 600	601 – 700	701 – 800	801 – 900	901 – 1000
____	____	____	____	____

Perfect Squares and Triangular Numbers

Do you remember triangular numbers?



? Can you see any relation between triangular numbers and square numbers? Extend the pattern shown and draw the next term.



$1 + 3 = 4 = 2^2$ $3 + 6 = 9 = 3^2$ $6 + 10 = 16 = 4^2$

Square Roots

? The area of a square is 49 sq. cm. What is the length of its side?

We know that $7 \times 7 = 49$, or $7^2 = 49$.

© NCERT not to be republished

So, the length of the side of a square with an area of 49 sq. cm is 7 cm. We call 7 the **square root** of 49.
In general, if $y = x^2$ then x is the **square root** of y.

? What is the square root of 64?

We know that 8 × 8 is 64. So, 8 is the square root of 64. What about – 8 × – 8 ? That is 64 too!

$$8^2 = 64, \text{ and } (-8)^2 = 64.$$

So, the square roots of 64 are + 8 and – 8.

Every perfect square has two integer square roots. One is positive and the other is negative. The square root of a number is denoted by $\sqrt{\ }$

Thus, $\sqrt{64} = \pm 8$ and $\sqrt{100} = \pm 10$.

Note that $\sqrt{8^2} = \pm 8$ and $\sqrt{10^2} = \pm 10$. In general, $\sqrt{n^2} = \pm n$.
In this chapter, we shall only consider the positive square root.

? Given a number, such as 576 or 327, how do we find out if it is a perfect square? If it is a perfect square, how can we find its square root?

Math Talk

We know that perfect squares end in 1, 4, 9, 6, 5, or an even number of zeros. But, it is not certain that a number that satisfies this condition is a square.

We can clearly say that 327 is not a perfect square. However, we cannot be sure that 576 is a perfect square.

1. We can list all the square numbers in sequence and find out whether 576 occurs among them. We know that 202 = 400, we can find squares of 21, 22, 23, ... and so on until we get 576 or a number greater than 576.

   $20^2 = 400$ $21^2 = 441$ $22^2 = 484$ $23^2 = 529$ $24^2 = 576$

   However, this process becomes inefficient for larger numbers.

2. Recall that every square can be expressed as a sum of consecutive odd numbers starting from 1.

   Consider $\sqrt{81}$.

   81 – 1 = 80 80 – 3 = 77 77 – 5 = 72 72 – 7 = 65 65 – 9 = 56

   56 – 11 = 45 45 – 13 = 32 32 – 15 = 17 17 – 17 = 0

   From 81, we successively subtracted consecutive odd numbers starting from 1 until we obtained 0 at the 9th step. Therefore $\sqrt{81}$ = 9.

   Can we find the square root of 729 using this method? Yes, but it will be time-consuming.

© NCERT not to be republished

3. We know that a perfect square is obtained by multiplying an integer by itself. Will looking at a number's prime factorisation help in determining whether it is a perfect square?

Yes, if we can divide the prime factors of a number into two equal groups, then the product of the prime factors in either group combine to form the square root.

? Is 324 a perfect square?

$$324 = 2 \times 2 \times 3 \times 3 \times 3 \times 3.$$

These can be grouped as

$$324 = (2 \times 3 \times 3) \times (2 \times 3 \times 3).$$

$$= (2 \times 3 \times 3)^2 = 18^2.$$

We can also write the prime factors in pairs. That is,

$$324 = (2 \times 2) \times (3 \times 3) \times (3 \times 3),$$

which shows that 324 is a perfect square. Thus,

$$324 = (2 \times 3 \times 3)^2 = 18^2.$$

Therefore, $\sqrt{324} = 18$.

? Is 156 a perfect square?

The prime factorisation of 156 is $2 \times 2 \times 3 \times 13$.
We cannot pair up these factors.
Therefore, 156 is not a perfect square.

? Find whether 1156 and 2800 are perfect squares using prime factorisation.

We can estimate the square root of larger perfect squares by looking at the closest perfect squares we are familiar with and then narrowing down the interval to search.

For example, to find $\sqrt{1936}$, we can reason as follows:

(i) 1936 is between 1600 (40^2) and 2500 (50^2), so $40 < \sqrt{1936} < 50$.

(ii) The last digit of 1936 is 6. So, the last digit of the square root must either be 4 or 6. It can be 44 or 46.

(iii) If we calculate 45^2, we can compare it with 1936 to halve the interval to search from 40–50 to either 40–45 or 45–50. We can write 45^2 as $(40 + 5)\ (40 + 5) = 40^2 + 2 \times 40 \times 5 + 5^2 = 1600 + 400 + 25 = 2025$.

(iv) $2025 > 1936$. So, $40 < \sqrt{1936} < 45$

(v) From the observation in point b we can guess and then verify that $\sqrt{1936}$ is 44.

Consider the following situations —

Aribam and Bijou play a game. One says a number and the other replies with its square root. Aribam starts. He says 25, and Bijou quickly

© NCERT not to be republished

responds with 5. Then Bijou says 81, and Aribam answers 9. The game goes on till Aribam says 250. Bijou is not able to answer because 250 is not a perfect square. Aribam asks Bijou if he can at least provide a number that is close to the square root of 250.

For this, Bijou needs to estimate the square root of 250.
We know that $100 < 250 < 400$ and $\sqrt{100} = 10$ and $\sqrt{400} = 20$.
So, $10 < \sqrt{250} < 20$.

But, we are still not very close to the number whose square is 250.
We know that $15^2 = 225$ and $16^2 = 256$.

Therefore, $15 < \sqrt{250} < 16$. Since 256 is much closer to 250 than 225, $\sqrt{250}$ is approximately 16. We also know it is less than 16.

Here is another problem that requires estimating square roots.

Akhil has a square piece of cloth of area 125 cm^2. He wants to know if he can cut out a square handkerchief of side 15 cm. If not, he wants to know the maximum size handkerchief that can be cut out from this piece of cloth with an integer side length.

125 is not a perfect square. The nearest perfect squares are $11^2 = 121$ and $12^2 = 144$. So the largest square handkerchief with integer side length that can be cut out from this piece of cloth has side length 11 cm.

Figure it Out

1. Which of the following numbers are not perfect squares?
   (i) 2032 (ii) 2048 (iii) 1027 (iv) 1089
2. Which one among 64^2, 108^2, 292^2, 36^2 has last digit 4?
3. Given $125^2 = 15625$, what is the value of 126^2?
   (i) 15625 + 126 (ii) 15625 + 26^2 (iii) 15625 + 253
   (iv) 15625 + 251 (v) 15625 + 51^2
4. Find the length of the side of a square whose area is 441 m^2.
5. Find the smallest square number that is divisible by each of the following numbers: 4, 9, and 10.
6. Find the smallest number by which 9408 must be multiplied so that the product is a perfect square. Find the square root of the product.
7. How many numbers lie between the squares of the following numbers?
   (i) 16 and 17 (ii) 99 and 100
8. In the following pattern, fill in the missing numbers:

© NCERT not to be republished

$1^2 + 2^2 + 2^2 = 3^2$

$2^2 + 3^2 + 6^2 = 7^2$

$3^2 + 4^2 + 12^2 = 13^2$

$4^2 + 5^2 + 20^2 = (___)^2$

$9^2 + 10^2 + (___)^2 = (___)^2$

9. How many tiny squares are there in the following picture? Write the prime factorisation of the number of tiny squares.



1.2 Cubic Numbers

You know the word **cube** from geometry. A cube is a solid figure all of whose all sides meet at right angles and are equal. How many cubes of side 1 cm make a cube of side 2 cm?



? How many cubes of side 1 cm will make a cube of side 3 cm?

© NCERT not to be republished

Consider the numbers 1, 8, 27, ...

These numbers are called **perfect cubes.** Can you see why they are named so?

Each of them is obtained by multiplying a number by itself three times. We note that

$$1 = 1 \times 1 \times 1$$
$$8 = 2 \times 2 \times 2$$
$$27 = 3 \times 3 \times 3$$



? Is 9 a cube?

We see that $2 \times 2 \times 2 = 8$ and $3 \times 3 \times 3 = 27$. This shows that 9 is not a perfect cube. Nor is any number from 10 to 26.

? Can you estimate the number of unit cubes in a cube with an edge length of 4 units?



It has 64 unit cubes! If you notice carefully, each layer of this cube has 4×4 unit cubes. Each square layer has 16 unit cubes (4×4), and there are 4 such layers, so the total number of unit cubes is $4 \times 4 \times 4 = 64$.
Since $5^3 = 5 \times 5 \times 5 = 125$, 125 is a cube.
In general, for any number *n*, we write the cube $n \times n \times n$ as n^3.

? Complete the table below.

$1^3 = 1$	$11^3 = 1331$
$2^3 = 8$	$12^3 =$
$3^3 = 27$	$13^3 = 2197$
$4^3 = 64$	$14^3 = 2744$
$5^3 = 125$	$15^3 =$
$6^3 =$	$16^3 =$
$7^3 =$	$17^3 = 4913$
$8^3 =$	$18^3 = 5832$
$9^3 =$	$19^3 = 6859$
$10^3 =$	$20^3 =$

? What patterns do you notice in the table above?

Math Talk

? We know that 0, 1, 4, 5, 6, 9 are the only last digits possible for

© NCERT not to be republished

squares. What are the possible last digits of cubes?

? Similar to squares, can you find the number of cubes with 1 digit, 2 digits, and 3 digits? What do you observe?

? Can a cube end with exactly two zeroes (00)? Explain.

Just as we can take squares of fractions/decimals — $(\frac{4}{6})^2$, $(13.08)^2$, and $(-6)^2$ — we also can compute cubes of such numbers — $(\frac{4}{6})^3$, $(13.08)^3$, and $(-6)^3$.

$$(\frac{4}{6})^3 = (\frac{4}{6}) \times (\frac{4}{6}) \times (\frac{4}{6}) = (\frac{64}{216})$$

$$(13.08)^3 = 13.08 \times 13.08 \times 13.08 = 2237.810112$$

$$(-6)^3 = -6 \times -6 \times -6 = -216.$$

Taxicab Numbers

Once when Srinivasa Ramanujan was working with G. H. Hardy at the University of Cambridge, Hardy had come to visit Ramanujan at a hospital when he was ill. Hardy had ridden in a taxicab numbered 1729 and he remarked that 1729 was 'rather a dull number,' adding that he hoped that this was not a bad sign. Ramanujan immediately replied, "No, Hardy, it is a very interesting number. It is the smallest number that can be expressed as the sum of two cubes in two different ways".

$$1729 = 1^3 + 12^3$$

$$= 9^3 + 10^3.$$

Because of this story, 1729 has since been known as the **Hardy–Ramanujan** Number. And numbers that can be expressed as the sum of two cubes in two different ways are called **taxicab numbers.**

? The next two taxicab numbers after 1729 are 4104 and 13832. Find the two ways in which each of these can be expressed as the sum of two positive cubes.

Try This

How did Ramanujan know this? Well, he loved numbers. All through his life, he tinkered with numbers. During Ramanujan's time in Cambridge, his colleagues often marveled at his ability to see deep patterns in numbers that seemed arbitrary to others. His colleague, John Littlewood, once said, "Every positive integer was one of his [Ramanujan's] personal friends".

© NCERT not to be republished

Perfect Cubes and Consecutive Odd Numbers

Consecutive odd numbers have a role to play with cubes too. Look at the following pattern:

$$1 = 1 = 1^3$$

$$3 + 5 = 8 = 2^3$$

$$7 + 9 + 11 = 27 = 3^3$$

$$13 + 15 + 17 + 19 = 64 = 4^3$$

$$21 + 23 + 25 + 27 + 29 = 125 = 5^3$$

$$31 + 33 + 35 + 37 + 39 + 41 = 216 = 6^3.$$

Later in this series, we get the following set of consecutive numbers:

$$91 + 93 + 95 + 97 + 99 + 101 + 103 + 105 + 107 + 109.$$

? Can you tell what this sum is without doing the calculation?

Cube Roots

We know that $8 = 2^3$.

We call 2 the cube root of 8 and denote this by $2 = \sqrt[3]{8}$.

More generally, if $y = x^3$, then x is the cube root of y. This is denoted by $x = \sqrt[3]{y}$. So, $\sqrt[3]{8} = \sqrt[3]{2^3} = 2$.

Similarly, $\sqrt[3]{27} = \sqrt[3]{3^3} = 3$ and $\sqrt[3]{1000} = \sqrt[3]{10^3} = 3$. In general, $\sqrt[3]{n^3} = n$.

How do we find out if a number is a cube? Taking inspiration from the case of squares, let us see if we can use prime factorisations.

? Let us check if 3375 is a perfect cube.

$$3375 = 3 \times 3 \times 3 \times 5 \times 5 \times 5.$$

Can the factors be split into three identical groups? For 3375, we can form three groups of (3×5). So,

$$3375 = (3 \times 5) \times (3 \times 5) \times (3 \times 5)$$
$$= (3 \times 5)^3 = 15^3.$$

Another way is to check if the factors can be grouped into triplet(s):
$3375 = (3 \times 3 \times 3) \times (5 \times 5 \times 5) = 3^3 \times 5^3$.
This means $\sqrt[3]{3375} = 15$.

? Is 500 a perfect cube?

$500 = 2 \times 2 \times 5 \times 5 \times 5$. We see that the factors cannot be split into three identical groups. Therefore, 500 is not a perfect cube.

© NCERT not to be republished

Prime Factorisation of a Number	Prime Factorisation of its Cube
$4 = 2 \times 2$	$4^3 = 64 = 2 \times 2 \times 2 \times 2 \times 2 \times 2 = 2^3 \times 2^3$
$6 = 2 \times 3$	$6^3 = 216 = 2 \times 2 \times 2 \times 3 \times 3 \times 3 = 2^3 \times 3^3$
$15 = 3 \times 5$	$15^3 = 3375 = 3 \times 3 \times 3 \times 5 \times 5 \times 5 = 3^3 \times 5^3$
$12 = 2 \times 2 \times 3$	$12^3 = 1728 = 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 3 \times 3 \times 3 = 2^3 \times 2^3 \times 3^3$

Observe that each prime factor of a number appears three times in the prime factorisation of its cube.

? Find the cube roots of these numbers:

(i) $\sqrt[3]{64}$ = (ii) $\sqrt[3]{512}$ = (iii) $\sqrt[3]{729}$ =

Successive Differences

We know that the differences between consecutive perfect squares gives the sequence of odd numbers. Observe the figure below where the differences are computed successively for perfect squares. After two levels, all the differences are the same.

Perfect Squares



? Compute successive differences over levels for perfect cubes until all the differences at a level are the same. What do you notice?

Perfect Cubes

1.3 A Pinch of History

The first known list of perfect squares and perfect cubes was compiled by the Babylonians as far back as 1700 BCE. These lists, found on clay tablets, were used to quickly find square roots and cube

© NCERT not to be republished

roots in problems involving land measurement, architectural design, and other areas where geometric calculations were necessary.

In ancient Sanskrit works the term *varga* was used both for the square figure or its area, as well as the square power, and the term *ghana* was used both for the solid cube as well as the product of a number with itself three times. The fourth power was called *varga-varga* . These terms were used in India at least from the third century BCE.

Aryabhata (499 CE) states

"A square figure of four equal sides and the number representing its area are called *varga*. The product of two equal quantities is also called *varga*."

Thus, the term *varga* for square power has its origin in the graphical representation of a square figure.

Why is the word 'root' (the root of a plant) used for the mathematical operation √ (square root, cube root, etc.)?

It is because, in ancient India, the Sanskrit word *mula*, meaning root of a plant, basis, cause, origin, etc., was used for the mathematical operations of taking roots.

In Sanskrit, *varga-mula* (the basis, cause, origin of the square) was used for square-root and *ghana-mula* was used for cube-root. This use of *mula* for the mathematical concept of root was subsequently emulated in Arabic and Latin through their corresponding words for the root of a plant — *jidhr* and *radix* respectively. The term *mula* for root has been used in India at least from the first century BCE. Another term used was *pada* (foot, basis, cause, origin). Brahmagupta (628 CE) explains, 'The *pada* (root) of a *krti* (square) is that of which it is a square.'

Figure it Out

1. Find the cube roots of 27000 and 10648.
2. What number will you multiply by 1323 to make it a cube number?
3. State true or false. Explain your reasoning.
   - (i) The cube of any odd number is even.
   - (ii) There is no perfect cube that ends with 8.
   - (iii) The cube of a 2-digit number may be a 3-digit number.
   - (iv) The cube of a 2-digit number may have seven or more digits.
   - (v) Cube numbers have an odd number of factors.
4. You are told that 1331 is a perfect cube. Can you guess without factorisation what its cube root is? Similarly, guess the cube roots of 4913, 12167, and 32768.

© NCERT not to be republished

5. Which of the following is the greatest? Explain your reasoning.
   (i) $67^3 - 66^3$ (ii) $43^3 - 42^3$ (iii) $67^2 - 66^2$ (iv) $43^2 - 42^2$

SUMMARY

- A number obtained by multiplying a number by itself is called a **square number**. Squares of natural numbers are called **perfect squares**.
- All perfect squares end with 0, 1, 4, 5, 6 or 9. Squares can only have an even number of zeros at the end.
- **Square root** is the inverse operation of square. Every perfect square has two integral square roots. The positive square root of a number is denoted by the symbol $\sqrt{}$. For example, $\sqrt{9} = 3$.
- A **number** obtained by multiplying a number by itself three times is called a **cube**. For example 1, 8, 27, ... ,etc., are cubes.
- A number is a perfect square if its prime factors can be split into two identical groups.
- A number is a perfect cube if its prime factors can be split into three identical groups
- The symbol $\sqrt[3]{}$ denotes cube root. For example, $\sqrt[3]{27} = 3$.

© NCERT not to be republished



Square Pairs!

Look at the following numbers: 3 6 10 15 1
They are arranged such that each pair of adjacent numbers adds up to a square.

$$3 + 6 = 9,\ 6 + 10 = 16,\ 10 + 15 = 25,\ 15 + 1 = 16.$$

Try arranging the numbers 1 to 17 (without repetition) in a row in a similar way — the sum of every adjacent pair of numbers should be a square.

Can you arrange them in more than one way? If not, can you explain why?

Can you do the same with numbers from 1 to 32 (again, without repetition), but this time arranging all the numbers in a circle?



© NCERT not to be republished

2 POWER PLAY

0874CH02

2.1 Experiencing the Power Play ...

An Impossible Venture!

Take a sheet of paper, as large a sheet as you can find. Fold it once. Fold it again, and again.

? How many times can you fold it over and over?

Estu says "I heard that a sheet of paper can't be folded more than 7 times".

Roxie replies "What if we use a thinner paper, like a newspaper or a tissue paper?"

Try it with different types of paper and see what happens.



? Say you can fold a sheet of paper as many times as you wish. What would its thickness be after 30 folds? Make a guess.

Let us find out how thick a sheet of paper will be after 46 folds. Assume that the thickness of the sheet is 0.001 cm.

© NCERT not to be republished

? The following table lists the thickness after each fold. Observe that the thickness doubles after each fold.

Fold	Thickness	Fold	Thickness	Fold	Thickness
1	0.002 cm	7	0.128 cm	13	8.192 cm
2	0.004 cm	8	0.256 cm	14	16.384 cm
3	0.008 cm	9	0.512 cm	15	32.768 cm
4	0.016 cm	10	1.024 cm	16	65.536 cm
5	0.032 cm	11	2.048 cm	17	≈ 131 cm
6	0.064 cm	12	4.096 cm		

(We use the sign '≈' to indicate 'approximately equal to'.)
After 10 folds, the thickness is just above 1 cm (1.024 cm).
After 17 folds, the thickness is about 131 cm (a little more than 4 feet).

? Now, what do you think the thickness would be after 30 folds? 45 folds? Make a guess.

Math Talk

? Fill the table below.

Fold	Thickness	Fold	Thickness	Fold	Thickness
18	≈ 262 cm	21		24	
19	≈ 524 cm	22		25	
20	≈ 10.4 m	23		26	

After 26 folds, the thickness is approximately 670 m. Burj Khalifa in Dubai, the tallest building in the world, is 830 m tall.

Fold	Thickness	Fold	Thickness
27	≈ 1.3 km	29	
28		30	

After 30 folds, the thickness of the paper is about 10.7 km, the typical height at which planes fly. The deepest point discovered in the oceans is the Mariana Trench, with a depth of 11 km.

Fold	Thickness	Fold	Thickness	Fold	Thickness
31		36		41	
32		37		42	
33		38		43	
34		39		44	
35		40		45	

© NCERT not to be republished

It might be hard to digest the fact that after just 46 folds, the thickness is more than 7,00,000 km. This is the power of **multiplicative growth,** also called **exponential growth.** Let us analyse the growth.
We have seen that the thickness doubles after every fold.

Fold 4	0.016 cm
Fold 5	0.032 cm

Fold 9	0.512 cm
Fold 10	1.024 cm

Notice the change in thickness after two folds. By how much does it increase?

Fold 4	0.016 cm
Fold 6	0.064 cm

After any 3 folds, the thickness increases 8 times (= 2 × 2 × 2). Check if that is true. Similarly, from any point, the thickness after 10 folds increases by 1024 times (= 2 multiplied by itself 10 times), as shown in the table below.

Fold	Thickness	Times increased by
0 to 10	1.024 cm – 0.001 cm = 1.023 cm	1.024 ÷ 0.001 = 1024
10 to 20	10.485 m – 1.024 cm ≈ 10.474 m	10.485 m ÷ 1.024 cm = 1024
20 to 30	10.737 km – 10.485 m ≈ 10.726 km	10.737 km ÷ 10.485 m = 1024
30 to 40	10995 km – 10.737 km ≈ 10984.2 km	10995 km ÷ 10.737 km = 1024

2.2 Exponential Notation and Operations

The initial thickness of the paper was 0.001 cm.
Upon folding once, its thickness became 0.001 cm × 2 = 0.002 cm.

Folding it twice, its thickness became —
0.001 cm × 2 × 2 = 0.004 cm, or 0.001 cm × 2^2 = 0.004 cm (in shorthand).

Upon folding it thrice, its thickness became —
0.001 cm × 2 × 2 × 2, or 0.001 cm × 2^3 = 0.008 cm.

When folded four times, its thickness became —
0.001 cm × 2 × 2 × 2 × 2, or 0.001 cm × 2^4 = 0.016 cm.

Similarly, the expression for the thickness of the paper when folded 7 times will be 0.001 cm × 2 × 2 × 2 × 2 × 2 × 2 × 2, or 0.001 cm × 2^7 = 0.128 cm.

We have seen that square numbers can be expressed as n^2 and cube numbers as n^3.
$n \times n = n^2$ (read as 'n squared' or 'n raised to the power 2')

© NCERT not to be republished

$n \times n \times n = n^3$ (read as 'n cubed' or 'n raised to the power 3')
$n \times n \times n \times n = n^4$ (read as 'n raised to the power 4' or 'the 4th power of n')
$n \times n \times n \times n \times n \times n \times n = n^7$ (read as 'n raised to the power 7' or 'the 7th power of n') and so on.

In general, we write n^a to denote n multiplied by itself a times.

$$5^4 = 5 \times 5 \times 5 \times 5 = 625.$$

5^4 is the exponential form of 625. Here, 4 is the **exponent/power,** and 5 is the **base.** Exponents of the form 5^n are called powers of 5: 5^1, 5^2, 5^3, 5^4, etc. $2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 = 2^{10} = 1024$. Remember the 1024 from earlier? There, it meant that after every 10 folds, the thickness increased 1024 times.

5^4 is read as
'5 raised to the power 4' or
'5 to the power 4' or
'5 power 4' or
'4th power of 5'

? Which expression describes the thickness of a sheet of paper after it is folded 10 times? The initial thickness is represented by the letter-number v.

(i) $10v$ (ii) $10 + v$ (iii) $2 \times 10 \times v$
(iv) 2^{10} (v) $2^{10}v$ (vi) 10^2v

Some more examples of exponential notation:
$4 \times 4 \times 4 = 4^3 = 64$.
$(-4) \times (-4) \times (-4) = (-4)^3 = -64$.
Similarly,
$a \times a \times a \times b \times b$ can be expressed as a^3b^2 (read as a cubed b squared).
$a \times a \times b \times b \times b \times b$ can be expressed as a^2b^4 (read as a squared b raised to the power 4).
Remember that $4 + 4 + 4 = 3 \times 4 = 12$, whereas $4 \times 4 \times 4 = 4^3 = 64$.

? Express the number 32400 as a product of its prime factors and represent the prime factors in their exponential form.

$$32400 = 2 \times 2 \times 2 \times 2 \times 5 \times 5 \times 3 \times 3 \times 3 \times 3.$$

In exponential form, this would be

$$32400 = 2^4 \times 5^2 \times 3^4.$$

2	32400
2	16200
2	8100
2	4050
5	2025
5	405
3	81
3	27
3	9
3	3
	1

? What is $(-1)^5$? Is it positive or negative? What about $(-1)^{56}$?

? Is $(-2)^4 = 16$? Verify.

What is 0^2, 0^5?
What is 0^n?

? Figure it Out

1. Express the following in exponential form:

(i) $6 \times 6 \times 6 \times 6$ (ii) $y \times y$
(iii) $b \times b \times b \times b$ (iv) $5 \times 5 \times 7 \times 7 \times 7$
(v) $2 \times 2 \times a \times a$ (vi) $a \times a \times a \times c \times c \times c \times c \times d$

© NCERT not to be republished

2. Express each of the following as a product of powers of their prime factors in exponential form.

   (i) 648 (ii) 405 (iii) 540 (iv) 3600

3. Write the numerical value of each of the following:

   (i) 2×10^3 (ii) $7^2 \times 2^3$ (iii) 3×4^4
   (iv) $(-3)^2 \times (-5)^2$ (v) $3^2 \times 10^4$ (vi) $(-2)^5 \times (-10)^6$

The Stones that Shine ...

Three daughters with curious eyes,
Each got three baskets—a kingly prize.
Each basket had three silver keys,
Each opens three big rooms with ease.
Each room had tables—one, two, three,
With three bright necklaces on each, you see.
Each necklace had three diamonds so fine...
Can you count these stones that shine?

Hint: Find out the number of baskets and rooms.

How many rooms were there altogether?

The information given can be visualised as shown below.



From the diagram, the number of rooms is 3^4. This can be computed by repeatedly multiplying 3 by itself,

$3 \times 3 = 9.$
$9 \times 3 = 27.$
$27 \times 3 = 81.$
$81 \times 3 = 243.$

How many diamonds were there in total? Can we find out by just one multiplication using the products above?

The number of diamonds is $3 \times 3 \times 3 \times 3 \times 3 \times 3 \times 3 = 3^7$.

© NCERT not to be republished

Reprint 2026-27

We can write

$$3^7 = (3 \times 3 \times 3 \times 3) \times (3 \times 3 \times 3)$$

We had computed till 3^4. To find 3^7, we can just multiply 3^4 (= 81) with 3^3 (= 27).

$$= 3^4 \times 3^3$$
$$= 81 \times 27 = 2187$$

$$\underbrace{3 \times 3 \times 3 \times 3}_{3^4} \times \underbrace{3 \times 3 \times 3}_{3^3}$$

? 3^7 can also be written as $3^2 \times 3^5$. Can you reason out why?

This can be easily extended to products where exponents are the same letter-numbers.

? Write the product $p^4 \times p^6$ in exponential form.

$$p^4 \times p^6 = (p \times p \times p \times p) \times (p \times p \times p \times p \times p \times p) = p^{10}.$$

We can generalise this to —

$n^a \times n^b = n^{a+b}$, where a and b are counting numbers.

? Use this observation to compute the following.

(i) 2^9 (ii) 5^7 (iii) 4^6

Math Talk

4^6 can be evaluated in these two ways,

$(4 \times 4 \times 4) \times (4 \times 4 \times 4) = 4^3 \times 4^3$ $= 64 \times 64$ $= 4096.$ $4^3 \times 4^3$ is the square of 4^3, i.e., $4^3 \times 4^3$ can also be written as $(4^3)^2$.	$(4 \times 4) \times (4 \times 4) \times (4 \times 4) = 4^2 \times 4^2 \times 4^2$ $= 16 \times 16 \times 16$ $= 4096.$ $4^2 \times 4^2 \times 4^2$ is the cube of 4^2, i.e., $4^2 \times 4^2 \times 4^2$ can also be written as $(4^2)^3$.

Similarly, $7^4 = (7 \times 7) \times (7 \times 7) = 7^2 \times 7^2 = (7^2)^2$, and

$2^{10} = (2 \times 2) \times (2 \times 2) \times (2 \times 2) \times (2 \times 2) \times (2 \times 2)$
$= (2^2) \times (2^2) \times (2^2) \times (2^2) \times (2^2)$
$= (2^2)^5$.

? Is 2^{10} also equal to $(2^5)^2$? Write it as a product.

$2^{10} = (2 \times 2 \times 2 \times 2 \times 2) \times (2 \times 2 \times 2 \times 2 \times 2)$
$= (2^5) \times (2^5)$
$= (2^5)^2$.

In general,

$(n^a)^b = (n^b)^a = n^{a \times b} = n^{ab}$, where a and b are counting numbers.

? Write the following expressions as a power of a power in at least two different ways:

(i) 8^6 (ii) 7^{15} (iii) 9^{14} (iv) 5^8

© NCERT not to be republished

Magical Pond

In the middle of a beautiful, magical pond lies a bright pink lotus. The number of lotuses doubles every day in this pond. After 30 days, the pond is completely covered with lotuses. On which day was the pond half full?

If the pond is completely covered by lotuses on the 30th day, how much of it is covered by lotuses on the 29th day?

Since the number of lotuses doubles every day, the pond should be half covered on the 29th day.

Write the number of lotuses (in exponential form) when the pond was —

(i) fully covered (ii) half covered

There is another pond in which the number of lotuses triples every day. When both the ponds had no flowers, Damayanti placed a lotus in the doubling pond. After 4 days, she took all the lotuses from there and put them in the tripling pond. How many lotuses will be in the tripling pond after 4 more days?

After the first 4 days, the number of lotuses is $1 \times 2 \times 2 \times 2 \times 2 = 2^4$.
After the next 4 days, the number of lotuses is $2^4 \times 3 \times 3 \times 3 \times 3 = 2^4 \times 3^4$.

What if Damayanti had changed the order in which she placed the flowers in the lakes? How many lotuses would be there?

$$1 \times 3^4 \times 2^4 = (3 \times 3 \times 3 \times 3) \times (2 \times 2 \times 2 \times 2).$$

Can this product be expressed as an exponent m^n, where m and n are some counting numbers?

By regrouping the numbers,

$$= (3 \times 2) \times (3 \times 2) \times (3 \times 2) \times (3 \times 2)$$
$$= (3 \times 2)^4 = 6^4.$$

In general form,

$m^a \times n^a = (mn)^a$, where a is a counting number.

Use this observation to compute the value of $2^5 \times 5^5$.

Simplify $\frac{10^4}{5^4}$ and write it in exponential form.

In general, we can show that $\frac{m^a}{n^a} = \left(\frac{m}{n}\right)^a$.

© NCERT not to be republished

How Many Combinations

? Estu has 4 dresses and 3 caps. How many different ways can Estu combine the dresses and caps?

For each cap, he can choose any of the 4 dresses, so for 3 caps, 4 + 4 + 4 = 4 × 3 = 12 combinations are possible. We can also look at it as—for each dress, Estu can choose any of the 3 caps, so for 4 outfits, 3 + 3 + 3 + 3 = 3 × 4 = 12 combinations are possible.



? Roxie has 7 dresses, 2 hats, and 3 pairs of shoes. How many different ways can Roxie dress up?

Hint: Try drawing a diagram like the one above.

? Estu and Roxie came across a safe containing old stamps and coins that their great-grandfather had collected. It was secured with a 5-digit password. Since nobody knew the password, they had no option except to try every password until it opened. They were unlucky and the lock only opened with the last password, after they had tried all possible combinations. How many passwords did they end up checking?



If you can't solve a problem, try to find a simpler version of the problem that you can solve. This technique can come in handy many times.

Instead of a 5-digit lock, let us assume we have a 2-digit lock and try to find out how many passwords are possible.

There are 10 options for the first digit (0 to 9). For each of these, there are 10 options for the second digit (If 0 is the first digit then 00, 01, 02, 03, ..., 09 are possible). Therefore the total number of combinations for a 2-digit lock is 10 × 10 = 100.

Now, suppose we have a 3-digit lock. For each of the earlier 100 (2-digit) passwords there are 10 choices for the third digit. So, there are 100 × 10 = 1000 combinations for a 3-digit lock. You can list them all: 000, 001, 002, ..., 997, 997, 999.

© NCERT not to be republished

How many 5-digit passwords are possible?

Each digit has 10 choices, so a 5-digit lock will have:

$10 \times 10 \times 10 \times 10 \times 10 = 10^5$ = 1,00,000 passwords. This is the same as writing numbers till 99,999 with all 5 digits, i.e., 00000, 00001, 00002, ...00010, 00011, ..., 00100, 00101, ..., 00999, ..., 30456, ..., 99998, 99999.

Estu says, "Next time, I will buy a lock that has 6 slots with the letters A to Z. I feel it is safer."



? How many passwords are possible with such a lock?

Try This

? Think about how many combinations are possible in different contexts. Some examples are—

(i) Pincodes of places in India—The Pincode of Vidisha in Madhya Pradesh is 464001. The Pincode of Zemabawk in Mizoram is 796017.

(ii) Mobile numbers.

(iii) Vehicle registration numbers.

Try to find out how these numbers or codes are allotted/generated.

2.3 The Other Side of Powers

Imagine a line of length 16 units. Erasing half of it would result in

$$2^4 \div 2 = \frac{2 \times 2 \times 2 \times 2}{2} = 2 \times 2 \times 2 = 2^3 = 8 \text{ units.}$$

Erasing half one more time would result in,

$$(2^4 \div 2) \div 2 = 2^4 \div 2^2 = \frac{2 \times 2 \times 2 \times 2}{2 \times 2} = 2 \times 2 = 2^2 = 4 \text{ units.}$$

Halving 16 cm three times may be written as,

$$2^4 \div 2^3 = \frac{2 \times 2 \times 2 \times 2}{2 \times 2 \times 2} = 2 = 2^1 = 2 \text{ units.}$$

From this we can see that

$$2^4 \div 2^3 = 2^{4-3} = 2^1.$$

? What is $2^{100} \div 2^{25}$ in powers of 2?

In a generalised form,

$$n^a \div n^b = n^{a-b},$$

where $n \neq 0$ and a and b are counting numbers and $a > b$.

© NCERT not to be republished

Why can't n be 0?

Math Talk

We have not covered the case when the exponent is 0; for example, what is 2^0?

Let us define 2^0 in a way that the generalised form above holds true.

$$2^0 = 2^{4-4} = 2^4 \div 2^4 = \frac{2 \times 2 \times 2 \times 2}{2 \times 2 \times 2 \times 2} = 1.$$

In fact for any letter number a

$$2^0 = 2^{a-a} = 2^a \div 2^a = 1.$$

In general,

$$x^a \div x^a = x^{a-a} = x^0, \text{ and so}$$

$$1 = x^0,$$

where $x \neq 0$ and a is a counting number.

When Zero is in Power!



When a line of length 2^4 units is halved 5 times,

$$2^4 \div 2^5 = \frac{2 \times 2 \times 2 \times 2}{2 \times 2 \times 2 \times 2 \times 2} = \frac{1}{2} \text{ units.}$$

Using the generalised form, we get $2^4 \div 2^5 = 2^{(4-5)} = 2^{-1}$.

So, $2^{-1} = \frac{1}{2}$.

When a line of length 2^4 units is halved 10 times,
we get $2^4 \div 2^{10} = 2^{(4-10)} = 2^{-6}$ units.

When expanded, $2^4 \div 2^{10} = \frac{2 \times 2 \times 2 \times 2}{2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2} = \frac{1}{2^6} = \frac{1}{64}$,
which is also written as 2^{-6}.

© NCERT not to be republished

Similarly, $10^{-3} = \frac{1}{10^3}$, $7^{-2} = \frac{1}{7^2}$, etc.

? Can we write $10^3 = \frac{1}{10^{-3}}$?

We can write,

$$\frac{1}{10^{-3}} = \frac{1}{1/10^3} = 1 \div \frac{1}{10^3} = 1 \times 10^3 = 10^3.$$

Similarly, $7^2 = \frac{1}{7^{-2}}$ and $4^a = \frac{1}{4^{-a}}$.

In a generalised form,

$$n^{-a} = \frac{1}{n^a} \text{ and } n^a = \frac{1}{n^{-a}}, \text{ where } n \neq 0.$$

Math Talk

Consider the following general forms we have identified.

$n^a \times n^b = n^{a+b}$	$(n^a)^b = (n^b)^a = n^{a \times b}$	$n^a \div n^b = n^{a-b}$

? We had required a and b to be counting numbers. Can a and b be any integers? Will the generalised forms still hold true?

? Write equivalent forms of the following.

(i) 2^{-4} (ii) 10^{-5} (iii) $(-7)^{-2}$

(iv) $(-5)^{-3}$ (v) 10^{-100}

? Simplify and write the answers in exponential form.

(i) $2^{-4} \times 2^7$ (ii) $3^2 \times 3^{-5} \times 3^6$ (iii) $p^3 \times p^{-10}$

(iv) $2^4 \times (-4)^{-2}$ (v) $8^p \times 8^q$

Power Lines

Let us arrange the powers of 4 along a line.



© NCERT not to be republished

? Can we say that 16384 (4^7) is 16 (4^2) times larger than 1,024 (4^5)?
Yes, since $4^7 \div 4^5 = 4^2$.

? How many times larger than 4^{-2} is 4^2?

? Use the power line for 7 to answer the following questions.

7^7	823543	$2{,}401 \times 49 =$
7^6	117649	$49^3 =$
7^5	16807	$343 \times 2{,}401 =$
7^4	2401	$\frac{16{,}807}{49} =$
7^3	343	$\frac{7}{343} =$
7^2	49	$\frac{16{,}807}{8{,}23{,}543} =$
7^1	7	$1{,}17{,}649 \times \frac{1}{343} =$
7^0	1	$\frac{1}{343} \times \frac{1}{343} =$
7^{-1}	$\frac{1}{7}$	
7^{-2}	$\frac{1}{49}$	
7^{-3}	$\frac{1}{343}$	
7^{-4}	$\frac{1}{2401}$	

2.4 Powers of 10

We have used numbers like 10, 100, 1000, and so on when writing Indian numerals in an expanded form. For example,

$$47561 = (4 \times 10000) + (7 \times 1000) + (5 \times 100) + (6 \times 10) + 1.$$

This can be written using powers of 10 as

$$(4 \times 10^4) + (7 \times 10^3) + (5 \times 10^2) + (6 \times 10^1) + (1 \times 10^0).$$

? Write these numbers in the same way: (i) 172, (ii) 5642, (iii) 6374.

? How can we write 561.903?

$$561.903 = (5 \times 100) + (6 \times 10) + 1 + (9 \times \tfrac{1}{10}) + (0 \times \tfrac{1}{100}) + (3 \times \tfrac{1}{1000}).$$

Writing it using powers of 10, we have

$$561.903 = (5 \times 10^2) + (6 \times 10^1) + (1 \times 10^0) + (9 \times 10^{-1}) + (0 \times 10^{-2}) + (3 \times 10^{-3}).$$

© NCERT not to be republished

Scientific Notation

Let's look at some facts involving large numbers—

(i) The Sun is located 30,00,00,00,00,00,00,00,000 m from the centre of our Milky Way galaxy.

(ii) The number of stars in our galaxy is 1,00,00,00,00,000.

(iii) The mass of the Earth is 59,76,00,00,00,00,00,00,00,00,00,000 kg.

As the number of digits increases, it becomes difficult to read the numbers correctly. We may miscount the number of zeroes or place commas incorrectly. We will then read the wrong value. It is like getting ₹5,000 when you were supposed to get ₹50,000. The number of zeroes is more important than the initial digits in several cases.

Can we use the exponential notation to simplify and read these very large numbers correctly?

For example, the number 5900 can be expressed as—

$$5900 = 590 \times 10 = 590 \times 10^1$$
$$= 59 \times 100 = 59 \times 10^2$$
$$= 5.9 \times 1000 = 5.9 \times 10^3$$
$$= 0.59 \times 10000 = 0.59 \times 10^4.$$

Any number can be written as the product of a number between 1 and 10 and a power of 10. For example,

$5900 = 5.9 \times 10^3$ $\quad$ $20800 = 2.08 \times 10^4$ $\quad$ $80,00,000 = 8 \times 10^6$

? Write the large-number facts we read just before in this form.

In **scientific notation or scientific form** (also called **standard form)**, we write numbers as $x \times 10^y$, where $x \geq 1$ and $x < 10$ is the coefficient and y, the exponent, is any integer. Often, the exponent y is more important than the coefficient x. When we write the 2 crore population of Mumbai as 2×10^7, the 7 is more important than the 2. Indeed, if the 2 is changed to 3, the population increases by one-half, i.e., 2 crore to 3 crore, whereas if the 7 is changed to 8, the change in population is 10 times, i.e., 2 crores to 20 crores. Therefore, the standard form explicitly mentions the exponent, which indicates the number of digits.

If we say that the population of Kohima is 1,42,395, then it gives the impression that we are quite sure about this number up to the units place. When we use large numbers, in most cases, we are more concerned about how big a quantity or measure is, rather than the exact value. If we are only sure that the population is around 1 lakh 42 thousand, we can write it as 1.42×10^5. If we can only be certain that it is around 1 lakh 40 thousand, we write it as 1.4×10^5. The number of digits in the coefficient reflects how well we know the number. The most important part of any

© NCERT not to be republished

number written in scientific form is the exponent, and then the first digit of the coefficient. The digits following the coefficient are small corrections to the first digit.



These values are rounded-off estimates, averages, or approximations; most of the time, they serve the purpose at hand.

The distance between the Sun and Saturn is 14,33,50,00,00,000 m = 1.4335×10^{12} m.

The distance between Saturn and Uranus is 14,39,00,00,00,000 m = 1.439×10^{12} m. The distance between the Sun and Earth is 1,49,60,00,00,000 m = 1.496×10^{11} m.

? Can you say which of the three distances is the smallest?



? The number line below shows the distance between the Sun and Saturn (1.4335×10^{12} m). On the number line below, mark the relative position of the Earth. The distance between the Sun and the Earth is 1.496×10^{11} m.



? Express the following numbers in standard form.

(i) 59,853 (ii) 65,950

(iii) 34,30,000 (iv) 70,04,00,00,000

© NCERT not to be republished

2.5 Did You Ever Wonder?

Last year, we looked at interesting thought experiments in the chapter on Large Numbers. Let us continue this journey.

Nanjundappa wants to donate jaggery equal to Roxie's weight and wheat equal to Estu's weight. He is wondering how much it would cost.

? What would be the worth (in rupees) of the donated jaggery? What would be the worth (in rupees) of the donated wheat?

In order to find out, let us first describe the relationships among the quantities present.

Worth of jaggery (in rupees) = Roxie's weight in kg × cost of 1 kg jaggery.

Worth of wheat (in rupees) = Estu's weight in kg × cost of 1 kg wheat.

? Make necessary and reasonable assumptions for the unknowns and find the answers. Remember, Roxie is 13 years old and Estu is 11 years old.

Assuming Roxie's weight to be 45 kg and the cost of 1 kg of jaggery to be ₹70, the worth of donated jaggery is 45 × 70 = ₹3150. Assuming Estu's weight to be 50 kg and the cost of 1 kg of wheat to be ₹50, the worth of donated wheat is 50 × 50 = ₹2500.

The practice of offering goods equal to the weight of a person, called Tulābhāra or Tulābhāram, is quite old and is still followed in many places in Southern India. It is a symbol of bhakti (surrendering oneself), a token of gratitude; it also supports the community.

? Roxie wonders, "Instead of jaggery if we use 1-rupee coins, how many coins are needed to equal my weight?". How can we find out?

For questions like these, you can consider following the steps suggested below.

1. Guessing: Make an instinctive (quick) guess of what the answer could be, without any calculations.

© NCERT not to be republished

2. Calculating using estimation and approximation —
   (i) Describe the relationships among the quantities that are needed to find the answer.
   (ii) Make reasonable assumptions and approximations if the required information is not available.
   (iii) Compute and find the answer (and check how close your guess was).

? Would the number of coins be in hundreds, thousands, lakhs, crores, or even more? Make an instinctive guess.

? Find the answer by making necessary and reasonable assumptions and approximations for the unknowns. Remember, we are not looking for an exact answer but a reasonably close estimate.

How about measuring to find out the weight of a 1-rupee coin?

Initially, your guesses may be very far off from the answer and it is perfectly fine! You will get better at it like as you do it often and in different situations. Guessing and estimating can build intuition about numbers and various quantities.

Estu asks, "What if we use 5-rupee coins or 10-rupee notes instead? How much money could it be?"

? Make an instinctive guess first. Then find out (make necessary and reasonable assumptions about the unknown details and find the answers).

Estu says, "When I become an adult, I would like to donate notebooks worth my weight every year". Roxie says, "When I grow up, I would like to do *annadāna* (offering grains or meals) worth my weight every year".

? How many people might benefit from each of these offerings in a year? Again, guess first before finding out.

Math Talk

Roxie and Estu overheard someone saying—"We did *pādayātra* for about 400 km to reach this place! We arrived early this morning."

? How long ago would they have started their journey?

? Find answers by making necessary assumptions and approximations. Do guess first before calculating to check how close your guess was!

Note to the Teacher: Assumptions can vary greatly at times, and as a result the answers computed using these you can also vary. This is perfectly alright. Modelling the situation properly is crucial, which can also be done in different ways sometimes. The accuracy of the assumed numbers or quantities can get better with exposure and practice.

© NCERT not to be republished

Pādayātra, is the traditional practice of walking long distances as part of a religious or spiritual pursuit. People across religions in our country observe similar forms of pilgrimage or spiritual walking, although they may have different names or purposes.

Some of the pilgrimages are Ajmer Sharif Dargah Ziyarat, Pandharpur Wari, Kānwar Yatra, Sabarimala Yatra, Sammed Shikharji Yatra, Lumbini to Sarnath Yatra.

Before the rise of modern transport, people moved from one place to another by walking — sometimes merchants, sages, and scholars walked thousands of kilometres to different parts of the world across deserts, mountains, and rivers.

? How many times can a person circumnavigate (go around the world) the Earth in their lifetime if they walk non-stop? Consider the distance around the Earth as 40,000 km.

Linear Growth vs. Exponential Growth

Roxie tells Estu about a science-fiction novel she is reading where they build a ladder to reach the moon, "... I wonder if we actually had a ladder like that, how many steps would it have?".

? What do you think? Make an instinctive guess first.

? Would the number of steps be in thousands, lakhs, crores, or even more?

To find out, we would need to know the gap between consecutive steps of the ladder. Let's assume a reasonable distance of 20 cm. Visualising the problem as shown,

© NCERT not to be republished



? We have to find out how many 20 cm make 3,84,400 km.

If we calculate the value, we get the result as 1,92,20,00,000 steps, which is 192 crore and 20 lakh steps or 1 billion 922 million steps. The fixed increase in the distance from the earth with each step (a 20 cm gain after each step) is called **linear growth.**

To cover the distance between the Earth and the Moon, it takes 1,92,20,00,000 steps with linear growth whereas it takes just 46 folds of a piece of paper with exponential growth! Linear growth is additive, whereas exponential growth is multiplicative.

$\underbrace{20 + 20 + 20 + \ldots\ldots\ldots}_{1,92,20,00,000 \text{ times}}$ $\qquad$ $\underbrace{0.001 \times 2 \times 2 \times 2 \ldots\ldots\ldots}_{46 \text{ times}}$

Some examples of exponential growth we have seen earlier in this chapter are 'The Stones that Shine', 'Magical Pond', 'How Many Combinations'. We shall explore more such interesting examples in a later chapter and also in the next grade.

? Can you come up with some examples of linear growth and of exponential growth?

Getting a Sense for Large Numbers

Last year, we learnt about lakhs and crores, as well as millions and billions. A lakh is 10^5 (1,00,000), a crore is 10^7 (1,00,00,000), and an arab is 10^9 (1,00,00,00,000), whereas a million is 10^6 (1,000,000) and a billion is 10^9 (1,000,000,000).

You might know the size of the world's human population. Have you ever wondered how many ants there might be in the world or how long ago humans emerged? In this section, we shall explore numbers significantly larger than arabs and billions. We shall use powers of 10 to represent and compare these numbers in each case.

10^0 As of mid-2025, there are only two northern white rhinos remaining in the world, both females, and they reside at the Ol Pejeta Conservancy in Kenya (= 2×10^0).

© NCERT not to be republished

10^1 As of early 2024, the total population of Hainan gibbons is a meagre 42 ($\approx 4 \times 10^1$).

10^2 There are just 242 Kakapo alive as of mid-2025 ($\approx 2 \times 10^2$).

10^3 There are fewer than 3000 Komodo dragons in the world, all based in Indonesia ($\approx 3 \times 10^3$).

10^4 A 2005 estimate of the maned wolf population showed that there are more than 17000 of them; most are located in Brazil (1.7×10^4).

10^5 As of 2018, there are around 4.15 lakh African elephants ($\approx 4 \times 10^5$).

10^6 There are an estimated 50 lakh / 5 million American alligators as of 2025 (5×10^6).

10^7 The global camel population is estimated to be over 3.5 crore/ 35 million (3.5×10^7). India has only about 2.5 lakhs of them. The global horse population is around 5.8 crore / 58 million (5.8×10^7), with about half of them in America.

10^8 More than 20 crore / 200 million (2×10^8) water buffaloes are estimated worldwide, with a vast majority of them in Asia.

10^9 The estimated global population of starlings is around 1.3 arab/1.3 billion (_____). The global human population as of 2025 is 8.2 arab/8.2 billion (8.2×10^9).



A picture of a starling murmuration over a farm in the UK. Starling murmuration is a mesmerising aerial display of thousands of starlings flying in synchronised, swirling patterns. It is often described as a 'choreographed dance'.

© NCERT not to be republished

? With a global human population of about 8×10^9 and about 4×10^5 African elephants, can we say that there are nearly 20,000 people for every African elephant?

10^{10} The global chicken population living at any time is estimated at ≈ 33 billion (3.3×10^{10}).

10^{12} The estimated number of trees (2023) globally stands at 30 kharab/3 trillion (3×10^{12}). One kharab is 100 arab, and one trillion is 1000 billion.

10^{14} The estimated mosquito population worldwide (2023) is 11 neel/110 trillion (_____). A derived estimate of the population of the Antarctic krill stands at 50 neel/500 trillion (5×10^{14}).

10^{15} An estimate of the beetle population stands at 1 padma/1 quadrillion (1×10^{15}). The estimate of the earthworm population is also at 1 padma/1 quadrillion.

10^{16} The estimated population of ants globally is 20 padma/20 quadrillion (2×10^{16}). Ants alone outweigh all wild birds and wild mammals combined.

10^{21} is supposed to be the number of grains of sand on all beaches and deserts on Earth. This is enough sand to give every ant 10 little sand castles to live in.

10^{23} The estimated number of stars in the observable universe is 2×10^{23}.

10^{25} There are an estimated 2×10^{25} drops of water on Earth (assuming 16 drops per millilitre).

? Calculate and write the answer using scientific notation:

(i) How many ants are there for every human in the world?

(ii) If a flock of starlings contains 10,000 birds, how many flocks could there be in the world?

Reprint 2026-27

(iii) If each tree had about 10^4 leaves, find the total number of leaves on all the trees in the world.

(iv) If you stacked sheets of paper on top of each other, how many would you need to reach the Moon?

A different way to say your age!

"How old are you?" asked Estu.
"I completed 13 years a few weeks ago!" said Roxie.
"How old are you?" asked Estu again.
"I'm 4840 days old today!" said Roxie.
"How old are you?" asked Estu again.
"I'm _____ hours old!" said Roxie.
Make an estimate before finding this number.
Estu: "I am 4070 days old today. Can you find out my date of birth?"

What could this number mean? Find out!

? If you have lived for a million seconds, how old would you be?

We shall look at approximate times and timelines of some events and phenomena, and use powers of 10 to represent and compare these quantities.

Time in seconds	Comparison to real-world events/phenomena
10^0 = 1 second	- Time taken for a ball thrown up to fall back on the ground (typically a few seconds).
10^1 = 10 seconds	- Time blood takes to complete one full circulation through the body: 10–20 seconds ($1 \times 10^1 - 2 \times 10^1$ seconds). - Typical waiting time at a traffic signal.

Isn't it quite amazing how someone is able to estimate things like the number of ants in the world or the time blood takes to fully circulate? You may carry this wonder whenever you encounter such facts. You will come across such facts in subjects like Science and Social Science, where such estimates are made frequently.

10^2 seconds ≈1.6 minutes	- Time needed to make a cup of tea: 5–10 minutes (≈ $4 \times 10^2 - 8 \times 10^2$ seconds). - Time for light to reach the Earth from the Sun: about 8 minutes (≈ 5×10^2 seconds).

© NCERT not to be republished



10^3 seconds ≈ 16.6 minutes
- Satellites in low Earth orbits take between 90 minutes (≈ 5.5×10^3 seconds) to 2 hours to complete one full revolution around the Earth.

10^4 seconds ≈ 2.7 hours
- The time needed to digest a meal: about 2–4 hours to pass through the stomach.
- Lifespan of an adult mayfly: about a day (≈ 9×10^4 seconds).

? 10^5 seconds ≈ 1.16 days and 10^6 seconds ≈ 11.57 days. Think of some events or phenomena whose time is of the order of (i) 10^5 seconds and (ii) 10^6 seconds. Write them in scientific notation.

10^7 seconds ≈ 115.7 days / ≈ 3.8 months
- Time spent sleeping in a year: about 4 months.
- Time taken by Mangalyaan mission to reach Mars: 298 days (≈ 2.65×10^7 seconds).
- Time taken by Mars for one full revolution around the Sun: 687 Earth-days/1.88 Earth-years (≈ 6×10^7 seconds).



10^8 seconds ≈ 3.17 years
- The typical lifespan of most dogs is 3 to 15 years.

10^9 seconds ≈ 31.7 years
- The orbital period of Halley's comet is 75–79 years; the next expected return is in the year 2061 (≈ 2.4×10^9 seconds).
- Duration of one full revolution of Neptune around the Sun: 60,190 Earth-days/~165 Earth-years or 89,666 Neptunian days/1 Neptunian-year (≈ 5.2×10^9 seconds). A day on Neptune is about 16.1 hours

© NCERT not to be republished

Notice how rapid exponential growth is—10^6 seconds is less than a fortnight, but 10^9 seconds is a whopping 31 years (about half the life expectancy of a human)!

10^{10} seconds ≈ 317 years
- The Chola dynasty ruled for more than 900 years (≈ 3×10^{10} seconds) between the 3rd Century BCE and 12th Century CE.

10^{11} seconds ≈ 3,170 years
- Age of the oldest known living tree: about 5000 years (≈ 1.57×10^{11} seconds).
- Time since the last peak ice age: 19,000 – 26,000 years ago (≈ 6×10^{11} seconds – 8.2×10^{11} seconds).

10^{12} seconds ≈ 31,700 years
- Early Homo sapiens first appeared 2–3 lakh years ago (≈$7 \times 10^{12} – 9 \times 10^{12}$ seconds). The entire population around that time could fit in a large cricket stadium.

10^{13} seconds ≈ 3.17 lakh years
- The Steppe Mammoth is estimated to have appeared around 8–18 lakh years ago.

10^{14} seconds ≈ 3.17 million years
- A fossil of Kelenken Guillermoi, a type of terror bird, is dated to 15 million years ago (≈_____ seconds).

10^{15} seconds ≈ 3.17 crore years
- Age of Himalayas: 5.5 crore years/55 million years (≈ 1.7×10^{15} seconds); they continue to grow a few mm every year.
- Dinosaurs went extinct 6.6 crore years ago/66 million years ago (≈ 2×10^{15} seconds).
- Dinosaurs first appeared more than 20 crore/200 million years ago (≈ 6×10^{15} seconds).
- It takes about 23 crore years for the Sun to make one complete trip around the Milky Way (≈ 7×10^{15} seconds).

© NCERT not to be republished

10^{16} seconds
≈ 31.7 crore years

10^{17} seconds
≈ 3.17 billion years

- Plants on land started 47 crore/470 million years ago (≈ _____ seconds).

The oldest fossil evidence suggests that bacteria first appeared about 3.7 billion years ago.

- The Earth is 4.5 billion years old.
- The Milky Way galaxy was formed 13.6 billion years ago, and the Universe was formed 13.8 billion years ago.

Notice that 10^9 seconds is of the order of the lifespan of a human, whereas 10^{18} seconds ago the universe did not exist according to modern physics!! The exponential notation can capture very large quantities in a concise manner.

? Calculate and write the answer using scientific notation:

(i) If one star is counted every second, how long would it take to count all the stars in the universe? Answer in terms of the number of seconds using scientific notation.

(ii) If one could drink a glass of water (200 ml) every 10 seconds, how long would it take to finish the entire volume of water on Earth?

Try This

Very large quantities are often beyond our experience and comprehension. To put them into perspective, we can relate and compare them with quantities we are familiar with. This can give an essence of how large a number or a measure is!

2.5 A Pinch of History

In the *Lalitavistara*, a Buddhist treatise from the first century BCE, we see number-names for odd powers of ten up to 10^{53}. The following occurs as part of the dialogue between the mathematician Arjuna and Prince Gautama, the *Bodhisattva*.

"Hundred *kotis* are called an *ayuta* (10^9), hundred *ayutas* a *niyuta* (10^{11}), hundred *niyutas* a *kankara* (10^{13}), ..., hundred *sarva-balas* a *visamjna-gati* (10^{47}), hundred *visamjna-gatis* a *sarvajna* (10^{49}), hundred *sarvajnas* a *vibhutangama* (10^{51}), a hundred *vibhutangamas* is a *tallakshana* (10^{53})."

Mahaviracharya gives a list of 24 terms (i.e., up to 10^{23}) in his treatise *Ganita-sara-sangraha*. An anonymous Jaina treatise *Amalasiddhi* gives a list with a name for each power of ten up to 10^{96} *(dasha-ananta)*. A Pali grammar treatise of *Kāccāyana* lists number-names up to 10^{140}, named *asaṅkhyeya*.

© NCERT not to be republished

For expressing high powers of ten, Jaina and Buddhist texts use bases like *sahassa* (thousand) and *koṭi* (ten million); for instance, *prayuta* (10^6) would be *dasa sata sahassa* (ten hundred thousand).

The modern naming is similar to this, where we say,

A hundred thousand is a lakh	100 × 1000 = 1,00,000	$10^2 \times 10^3 = 10^5$
A hundred lakhs is a crore	100 × 1,00,000 = 1,00,00,000	$10^2 \times 10^5 = 10^7$
A hundred crores is an arab	100 × 1,00,00,000 = 1,00,00,00,000	$10^2 \times 10^7 = 10^9$
A hundred arab is a kharab	100 × 1,00,00,00,000 = 1,00,00,00,00,000	$10^2 \times 10^9 = 10^{11}$

Continuing this, a hundred kharab is a neel (10^{13}), a hundred *neel* is a padma (10^{15}), a hundred *padma* is a *shankh* (10^{17}) and a hundred *shankh* is a *maha shankh* (10^{19}).

In the American/International system, we say

A thousand thousand is a million	1000 × 1000 = 1,000,000	$10^3 \times 10^3 = 10^6$
A thousand million is a billion	1000 × 1,000,000 = 1,000,000,000	$10^3 \times 10^6 = 10^9$
A thousand billion is an trillion	1000 × 1,000,000,000 = 1,00,000,000,000	$10^3 \times 10^9 = 10^{12}$

Continuing this, a thousand trillion is a quadrillion (10^{15}). This pattern continues. Observe the names **mi**llion (10^6), **bi**llion (10^9), **tr**illion (10^{12}), **quad**rillion (10^{15}), **quin**tillion (10^{18}), **sext**illion (10^{21}), **sept**illion (10^{24}), **oct**illion (10^{27}), **non**illion (10^{30}), **dec**illion (10^{33}).

? What does the first part of each name denote?

The number 10^{100} is also called a googol. The estimated number of atoms in the universe is 10^{78} to 10^{82}. The number 10^{googol} is called a googolplex. It is hard to imagine how large this number is!

The currency note with the highest denomination in India currently is 2000 rupees. Guess what is the highest denomination of a currency note ever, across the world. The highest numerical value banknote ever printed was a special note valued 1 sextillion pengő (10^{21} or 1 milliard bilpengő) printed in Hungary in 1946, but it was never issued. In 2009, Zimbabwe printed a 100 trillion (10^{14}) Zimbabwean dollar note, which at the time of printing was worth about $30.

© NCERT not to be republished

Figure it Out

1. Find out the units digit in the value of $2^{224} \div 4^{32}$? [Hint: $4 = 2^2$]
2. There are 5 bottles in a container. Every day, a new container is brought in. How many bottles would be there after 40 days?
3. Write the given number as the product of two or more powers in three different ways. The powers can be any integers.
   (i) 64^3 (ii) 192^8 (iii) 32^{-5}
4. Examine each statement below and find out if it is 'Always True', 'Only Sometimes True', or 'Never True'. Explain your reasoning.
   (i) Cube numbers are also square numbers.
   (ii) Fourth powers are also square numbers.
   (iii) The fifth power of a number is divisible by the cube of that number.
   (iv) The product of two cube numbers is a cube number.
   (v) q^{46} is both a 4th power and a 6th power (q is a prime number).
5. Simplify and write these in the exponential form.
   (i) $10^{-2} \times 10^{-5}$ (ii) $5^7 \div 5^4$
   (iii) $9^{-7} \div 9^4$ (iv) $(13^{-2})^{-3}$
   (v) $m^5n^{12}(mn)^9$
6. If $12^2 = 144$ what is
   (i) $(1.2)^2$ (ii) $(0.12)^2$
   (iii) $(0.012)^2$ (iv) 120^2

© NCERT not to be republished

7. Circle the numbers that are the same—

$2^4 \times 3^6$ $6^4 \times 3^2$ 6^{10} $18^2 \times 6^2$ 6^{24}

8. Identify the greater number in each of the following—

(i) 4^3 or 3^4 (ii) 2^8 or 8^2 (iii) 100^2 or 2^{100}

9. A dairy plans to produce 8.5 billion packets of milk in a year. They want a unique ID (identifier) code for each packet. If they choose to use the digits 0–9, how many digits should the code consist of?

10. 64 is a square number (8^2) and a cube number (4^3). Are there other numbers that are both squares and cubes? Is there a way to describe such numbers in general?

Math Talk

11. A digital locker has an alphanumeric (it can have both digits and letters) passcode of length 5. Some example codes are G89P0, 38098, BRJKW, and 003AZ. How many such codes are possible?

12. The worldwide population of sheep (2024) is about 10^9, and that of goats is also about the same. What is the total population of sheep and goats?

(ii) 20^9 (ii) 10^{11} (iii) 10^{10}
(iv) 10^{18} (v) 2×10^9 (vi) $10^9 + 10^9$

13. Calculate and write the answer in scientific notation:

(i) If each person in the world had 30 pieces of clothing, find the total number of pieces of clothing.
(ii) There are about 100 million bee colonies in the world. Find the number of honeybees if each colony has about 50,000 bees.
(iii) The human body has about 38 trillion bacterial cells. Find the bacterial population residing in all humans in the world.
(iv) Total time spent eating in a lifetime in seconds.

14. What was the date 1 arab/1 billion seconds ago?

Try This

© NCERT not to be republished

SUMMARY

- We analysed some situations, asked questions, and found answers by first guessing, then modelling the problem statement, followed by making assumptions and approximations to carry out the calculations.
- We experienced how rapid exponential growth, also called multiplicative growth, can be compared to additive growth.
- n^a is $n \times n \times n \times n \times \ldots \times n$ (n multiplied by itself a times) and $n^{-a} = \frac{1}{n^a}$.
- Operations with exponents satisfy
  - $n^a \times n^b = n^{a+b}$
  - $(n^a)^b = (n^b)^a = n^{a \times b}$
  - $n^a \div n^b = n^{a-b}$ $(n \neq 0)$
  - $n^a \times m^a = (n \times m)^a$
  - $n^a \div m^a = (n \div m)^a$ $(m \neq 0)$
  - $n^0 = 1$ $(n \neq 0)$
- The scientific notation for the number 308100000 is 3.081×10^8. The **standard form** of the **scientific notation** of any number is $x \times 10^y$, where $x \geq 1$ and $x < 10$, and y is an integer.
- Engaging in interesting thought experiments can be used as means to understand how large a number or a quantity is.

© NCERT not to be republished



Tremendous in Ten!

Find a partner to play this game with. In 10 seconds, the person who writes a number or an expression, using only the digits 0-9 and arithmetic operations, that gives a number that is the larger between the two wins the round.

10000000000000 $\qquad$ 999999 × 999999

In Round 1, Roxie wrote 10000000000000 and Estu wrote 999999 × 999999. Between these two, Roxie's number is greater. Can you see why? Roxie's number is 10^{13}, whereas Estu's number is less than $(10^6)^2$.

In Round 2, Roxie wrote $10^{1000} + 10^{1000} + 10^{1000} + 10^{1000}$ and Estu wrote $(10^{1000000}) \times 9000$. Can you say which is greater?

$10^{1000} + 10^{1000} + 10^{1000} + 10^{1000}$ $\qquad$ $10^{1000000} \times 9000$

Below are some conditions that you may consider for different rounds.

(i) Exponents are not allowed. Only addition is allowed.

(ii) Exponents are not allowed. Only addition and multiplication are allowed.

(iii) Exponents are allowed. Only addition is allowed.

(iv) Exponents are allowed. Any arithmetic operation is allowed.

You can create your own conditions and/or involve more people to play together.

© NCERT not to be republished

3 A STORY OF NUMBERS

0874CH03

3.1 Reema's Curiosity

One lazy afternoon, Reema was flipping through an old book when—whoosh!—a piece of paper slipped out and floated to the floor. She picked it up and stared at the strange symbols all over it. "What is this?" she wondered.

She ran to her father, holding the paper as if it were a secret treasure. He looked at it and smiled. "Around 4000 years ago, there flourished a civilisation in a region called Mesopotamia, in the western part of Asia, containing a major part of the present-day Iraq and a few other neighbouring countries. This is one of the ways they wrote their numbers!"

Reema's eyes lit up, "Seriously? These strange symbols were numbers?" Her curiosity was sparked, and questions started swirling in her head.

© NCERT not to be republished

Sensing her curiosity, her father started telling her how the idea of number and number representation evolved over the course of time, across geographies, to finally reach its modern efficient form. Get ready to travel back in time with them!

Humans had the need to count even as early as the Stone Age. They were counting to determine the quantity of food they had, the number of animals in their livestock, details regarding trades of goods, the number of offerings given in rituals, etc. They also wanted to keep track of the passing days, e.g., to know and predict when important events such as the new moon, full moon, or onset of a season would occur. However, when they said or wrote down such numbers, they didn't make use of the numbers that we use today.

The structure of the modern oral and written numbers that we use today had its origin thousands of years ago in India. Ancient Indian texts, such as the *Yajurveda Samhita*, mentioned names of numbers based on powers of 10, almost as we say them orally today. For example, they listed names for the numbers one *(eka)*, ten *(dasha)*, hundred *(shata)*, thousand (*sahasra*), ten thousand *(āyuta)*, etc., all the way up to 10^{12} and beyond.

The way we write our numbers today — using the digits 0 through 9 — also originated and were developed in India, around 2000 years ago. The first known instance of numbers being written using ten digits, including the digit 0 (which was then notated as a dot), occurs in the *Bakhshali* manuscript (c. 3rd century CE). Aryabhata (c. 499 CE) was the first mathematician to fully explain, and do elaborate scientific computations with the Indian system of 10 symbols.

Zero in the *Bakhshali* manuscript

The Indian number system was transmitted to the Arab world by around 800 CE. It was popularised in the Arab world by the great Persian mathematician Al-Khwārizmī (after whom the word 'algorithm' is named) through his book *On the Calculation with Hindu Numerals* (*c.*825) and by the noted philosopher Al-Kindi through his work *On the Use of the Hindu Numerals* (*c.*830).

From the Arab world, the Hindu numerals were transmitted to Europe and to parts of Africa by around 1100 CE. Though Al-Khwārizmī's work on calculation with Hindu numerals was translated into Latin, it was the Italian mathematician Fibonacci who around the year 1200 really made the case to Europe to adopt the Indian numerals. However, the Roman numerals were so ingrained in European thinking and writing at the time that the Indian numerals did not gain widespread use for several more centuries. But eventually, during the European Renaissance and by the 17th century, not adopting them became impossible or it would impede scientific progress.

Reprint 2026-27

"The ingenious method of expressing every possible number using a set of ten symbols (each symbol having a place value and an absolute value) emerged in India. The idea seems so simple nowadays that its significance and profound importance is no longer appreciated. Its simplicity lies in the way it facilitated calculations and placed arithmetic foremost among useful inventions."

— Pierre-Simon Laplace (1749–1827)

Their use then spread to every continent, and are now used in every corner of the world.

Because European scholars learned the Indian numerals from the Arab world, they called them 'Arabic numerals' to reflect their European perspective. On the other hand, as noted above, Arab scholars, such as Al-Khwārizmī and Al-Kindi, called them 'Hindu numerals'. During the period of European colonisation, the European term Arabic numbers became widely used. However, in recent years, this mistake is being corrected in many textbooks and documents around the world, including in Europe. The most commonly used terminologies for the numbers we use today are 'Hindu numerals', 'Indian numerals', and the transitional 'Hindu-Arabic numerals'. It is worth noting that the word 'Hindu' here does not refer to a religion, but rather a geography/people from whom these numbers came.

The shape of the digits 0, 1, 2, ..., 9 used to write numbers in the Indian number system today evolved over a period of time, as shown below:



Evolution of the digits used in the Indian number system

Prior to the global adoption of the Indian system of numerals, different groups of people used different methods of representing numbers. We

Reprint 2026-27

shall take a glimpse of some of them. We will not be looking at different systems in a chronological order, but rather an order that shows us the main stages in the development of the idea of number representation.

But first, let us explore some of the foundational ideas needed to count and to determine the number of objects in a given collection.

The Mechanism of Counting

Imagine that we are living in the Stone Age, say, around ten thousand years ago. Suppose we have a herd of cows. Here are some natural questions that we might ask about our herd—

Q1. How do we ensure that all cows have returned safely after grazing?

Q2. Do we have fewer cows than our neighbour?

Q3. If there are fewer, how many more cows would we need so that we have the same number of cows as our neighbour?

Math Talk

We need to tackle these questions without the use of the number names or written numbers of the Hindu number system. How do we do it?

Here are some possible methods.

Method 1: We could tackle the questions by using pebbles, sticks or any object that is available in abundance. Let us choose sticks. For every cow in the herd, we could keep a stick. The final collection of sticks tells us the number of cows, which can be used to check if any cows have gone missing.



© NCERT not to be republished

This way of associating each cow with a stick, such that no two cows are associated or mapped to the same stick is called a one-to-one mapping. This mapping can then be used to come up with a way to represent numbers, as shown in the table.

Number	Its representation (using sticks)
1	
2	
3	
4	
5	
.	
.	
.	

? How will you use such sticks to answer the other two questions (Q2 and Q3)?

Method 2: Instead of objects, we could use a standard sequence of sounds or names. For example, we could use the sounds of the letters of any language. While counting, we could make a one-to-one mapping between the objects and the letters: that is, associate each object to be counted with a letter, following the letter-order. This mapping can then be used to come up with a way of verbally representing numbers.

For example, we get the following number representation if we use English letters '*a*' to '*z*'.

Number	Its representation (using sounds or names)
1	*a*
2	*b*
3	*c*
4	*d*
5	*e*
.	.
.	.
.	.
26	*z*

© NCERT not to be republished

An obvious limitation of using only the letters of the English alphabet in this form is that it cannot be used to count collections having more than 26 objects.

? How many numbers can you represent in this way using the sounds of the letters of your language?

Method 3: We could use a sequence of written symbols as follows.

Table 1

Number	1	2	3	4	5	6	7	8	9	10
Representation using symbols	I	II	III	IV	V	VI	VII	VIII	IX	X
Number	11	12	13	14	15	16	17	18	19	20
Representation using symbols	XI	XII	XIII	XIV	XV	XVI	XVII	XVIII	XIX	XX

? Do you see a way of extending this method to represent bigger numbers as well? How?

From the discussion above, we see that for counting and finding the size of a collection, we need a standard sequence of objects, or names, or written symbols, that has a fixed order. Let us call this standard sequence a **number system.** A collection of objects can be counted by making a one-to-one mapping between them and the standard sequence, following the sequence order.

Since there is no end to numbers, the challenge is to come up with an unending standard sequence/number system that is easy to count with. Using sticks gives an unending standard sequence/number system. However, it is not convenient to count larger collections, as we will need as many sticks as the number of objects being counted. Using the sounds of the letters of a language, as in Method 2, is convenient for the counting process but is not an unending standard sequence/number system. The standard sequence/number system given in Method 3 was actually the system used in Europe before it got replaced by the Hindu number system. It is called the **Roman number system.** It was widely used in Europe for centuries, and was convenient for many purposes, but had the similar drawback that one cannot write arbitrarily large numbers without introducing more and more symbols. We will learn more about this system of writing numbers later on.

© NCERT not to be republished

As illustrated by the three methods, history gives us examples of number systems formed using physical objects (such as sticks, pebbles, body parts, etc.), names, and written symbols. Some groups of people had numbers represented both by physical objects as well as by names, while others like the Chinese had all three forms of representation. The symbols occurring in a written number system are called **numerals.** For example, 0, 1, 5, 36, 193, etc., are some of the numerals occurring in the Hindu number system. Numerals representing 'smaller' numbers always had names, and so a number system composed of written symbols always went hand in hand with a number system composed of names, as is the case with the modern-day Hindu system.

Figure it Out

1. Suppose you are using the number system that uses sticks to represent numbers, as in Method 1. Without using either the number names or the numerals of the Hindu number system, give a method for adding, subtracting, multiplying and dividing two numbers or two collections of sticks.

Math Talk

2. One way of extending the number system in Method 2 is by using strings with more than one letter—for example, we could use '*aa*' for 27. How can you extend this system to represent all the numbers? There are many ways of doing it!

Math Talk

3. Try making your own number system.

Try This

3.2 Some Early Number Systems

I. Use of Body Parts

Many groups of people across the world have used their hands and body parts for counting. Here is how a group of people in Papua New Guinea used and still use their body parts as the standard sequence/number system.

© NCERT not to be republished



II. Tally Marks on Bones and Other Surfaces

One of the oldest methods of number representation is by making notches—marks cut on a surface such as a bone or a wall of a cave. These marks are also called **tally marks.**

In this method, a mark is made for each object that is being counted. So the final collection of marks represents the total number of objects. This method is very similar to the method of using sticks to count (Method 1), except for the fact that a mark is made instead of adding a stick.

Archaeologists have discovered bones dating back more than 20,000 years that seem to have tally marks. The oldest known such bones with markings that are thought to represent numbers are the Ishango bone and the Lebombo bone. The Ishango bone, dating back 20,000 to 35,000 years, was discovered in the Democratic Republic of Congo. It features notches arranged in columns, possibly indicating calendrical systems. The Lebombo bone, discovered in South Africa, is an even older tally stick with 29 notches, estimated to be around 44,000 years old. It is considered one of the oldest mathematical artefacts, and may have served as a tally stick or lunar calendar.

Lebombo bone



Ishango bone

© NCERT not to be republished

III. Number Names Obtained by Counting in Twos

A group of indigenous people in Australia called the Gumulgal had the following words for their numbers.

Gumulgal
(Australia)

1. urapon
2. ukasar
3. ukasar-urapon
4. ukasar-ukasar
5. ukasar-ukasar-urapon
6. ukasar-ukasar-ukasar

? Can you see how their number names are formed?

The number name for 3 is composed of number names of 2 and 1.

The number name for 4 is composed of two occurrences of the number name for 2.

? Can you see how the names of the other numbers are formed?

The numbers are counted in 2s, using which the number names are formed: 3 = 2 + 1, 4 = 2 + 2, 5 = 2 + 2 + 1, 6 = 2 + 2 + 2.
Gumulgal called any number greater than 6 *ras*.

There is a very interesting and puzzling historical phenomenon associated with this number system. Look at the following number systems of a group of indigenous people in South America, and the Bushmen of South Africa:



© NCERT not to be republished

Despite being so far apart geographically, and with no trace of contact between them, these three groups have developed equivalent number systems! Historians have wondered how this happened. One theory is that these three groups of people may have had common ancestors, who used this number system. In course of time, their descendants migrated to these places.

Even though the number system of Gumulgal had number names for numbers only till 6, we can see the emergence of an idea here. Counting in 2s is more efficient for representing numbers than, for example, a tally system. A general form which this idea has taken in different number systems is as follows: count in groups of a certain number (like 2 in the case of Gumulgal's system), and use the word or symbol associated with this group size to represent bigger numbers. Some of the commonly used group sizes in different number systems have been 2, 5, 10 and 20. You can find the idea of counting by 5s in the Roman system (Table 1).

This idea of counting in a certain group size and using it to represent numbers is an important idea in the history of the evolution of number systems.

One of the phenomena that could have led people to this idea might be the human limit for immediately knowing the size of a collection at a glance. Let us try out the following activity.

? Quickly count the number of objects in each of the following boxes:

Up to what group size could you immediately see the number of objects without counting? Most humans find it difficult to count groups having 5 or more objects in a single glance.

This limit of perception could have prompted people using tally marks to replace every group of, say, 5 marks, with a new symbol, as seen in the system shown in Table 1.

Math Talk

© NCERT not to be republished

? What could be the difficulties with using a number system that counts only in groups of a single particular size? How would you represent a number like 1345 in a system that counts only by 5s?

Even though counting in groups of a particular size and using it for number representation is more efficient than the tally system, this method can still become cumbersome for larger numbers. The next system shows a refinement of this idea.

IV. The Roman Numerals



We have already seen the Roman number system till 20 (Table 1). We have seen that it uses I for 1, V for 5, X for 10.

To get the Roman numeral for any number till 39, it is first grouped into as many 10s as possible, the remaining is grouped into as many 5s as possible, and finally the remaining is grouped into 1s.

Example: Let us take the number 27.

$$27 = 10 + 10 + 5 + 1 + 1$$

So, 27 in Roman numerals is XXVII.

Instead of representing 50 as XXXXX, a new symbol is given to it: L. Following the way the number 4 is represented as 1 less than 5 — that is, as IV — 40 is represented as 10 less than 50 — that is, as XL. However, people using this system were not always consistent with this practice. Sometimes, 40 was also represented as XXXX.

The Roman number system introduces newer symbols to represent certain bigger numbers. Let us call all these numbers that have a new basic symbol as **landmark numbers**. Here are some of the landmark numbers of the Roman system and their associated numerals.

I	V	X	L	C	D	M
1	5	10	50	100	500	1,000

© NCERT not to be republished

These symbols are used to denote other numbers as well. For example, consider the number 2367. Writing it as a sum of landmark numbers starting from 1000 such that we take as many 1000s as possible, 500s as possible, and so on, we get

$$2367 = 1000 + 1000 + 100 + 100 + 100 + 50 + 10 + 5 + 1 + 1$$

So in Roman numerals, this number is MMCCCLXII.

Figure it Out

1. Represent the following numbers in the Roman system.

   (i) 1222 (ii) 2999 (iii) 302 (iv) 715

We see how vastly efficient this system is compared to some of the previous number systems that we have seen. This system seems to have evolved out of the ancient Greek number system in around the 8th century BCE in Rome, and evolved over time. It spread throughout Europe with the expansion of the Roman empire.

The efficiency of this system is due to the grouping of a given number by not just one group size, but a sequence of group sizes that we call landmark numbers, and then using these landmark numbers to represent the given number. This idea is the next important breakthrough in the history of the evolution of number systems.

Despite the relative efficiency of the Roman system, it doesn't lend itself to an easy performance of arithmetic operations, particularly multiplication and division.

Example: Try adding the following numbers without converting them to Hindu numerals:

(a) CCXXXII + CCCCXIII

Let us find the total number of Is, Xs, and Cs, and group them starting from the largest landmark number.

Apparently, it looks like the largest landmark number is C, but note that 5 Cs (100s) make a D (500). So the sum is

D
C C X X X I I
C C C C X I I I

XL V
DC X X X I I
X I I I
= DCXLV

Reprint 2026-27

Do it yourself now:

(b) LXXXVII + LXXVIII

How will you multiply two numbers given in Roman numerals, without converting them to Hindu numerals? Try to find the product of the following pairs of landmark numbers: V × L, L × D, V × D, VII × IX.

Try This



People using the Roman system made use of a calculating tool called the ***abacus*** to perform their arithmetic operations. We will see what it is in a later section. However, only specially trained people used this tool for calculation.

While going through the number systems discussed above, it should not be understood that, historically, one system developed as an improvement over the previous system. This point should be kept in mind when studying the upcoming number systems too. The actual story of how each of the number systems developed is much more complex, and many times not clearly known, and so we will not try to trace this in the chapter.

Figure it Out

1. A group of indigenous people in a Pacific island use different sequences of number names to count different objects. Why do you think they do this?

Math Talk

2. Consider the extension of the Gumulgal number system beyond 6 in the same way of counting by 2s. Come up with ways of performing the different arithmetic operations (+, –, ×, ÷) for numbers occurring in this system, without using Hindu numerals. Use this to evaluate the following:

Math Talk

© NCERT not to be republished

(i) (ukasar-ukasar-ukasar-ukasar-urapon) + (ukasar-ukasar-ukasar-urapon)

(ii) (ukasar-ukasar-ukasar-ukasar-urapon) – (ukasar-ukasar-ukasar)

(iii) (ukasar-ukasar-ukasar-ukasar-urapon) × (ukasar-ukasar)

(iv) (ukasar-ukasar-ukasar-ukasar-ukasar-ukasar-ukasar-ukasar) ÷ (ukasar-ukasar)

3. Identify the features of the Hindu number system that make it efficient when compared to the Roman number system.

Math Talk

4. Using the ideas discussed in this section, try refining the number system you might have made earlier.

Try This

3.3 The Idea of a Base

I. The Egyptian Number System

We are now going to see a written number system that the Egyptians developed around 3000 BCE. In this system, we see the use of landmark numbers to group and represent a given number. However, what makes this system special is its sequence of landmark numbers.

Imagine making collections of pebbles. The first landmark number is 1. Group together 10 collections of the previous landmark number (1). Its size is the second landmark number which is 10. Group together 10 collections of the previous landmark number (10). Its size is the third landmark number which is 10 × 10 = 100, and so on.



© NCERT not to be republished

Each landmark number is 10 times the previous one. Since 1 is the first landmark number, they are all powers of 10. The following are the symbols given to these numbers —

1	10	10^2	10^3	10^4	10^5	10^6	10^7

As in the case of Roman numbers, a given number is counted in groups of the landmark numbers, starting from the largest landmark number less than the given number. This is then used to assign the numeral.

For example 324 which equals 100 + 100 + 100 + 10 + 10 + 4 is written as .

Figure it Out

1. Represent the following numbers in the Egyptian system: 10458, 1023, 2660, 784, 1111, 70707.

2. What numbers do these numerals stand for?

(i)

(ii) 

II. Variations on the Egyptian System and the Notion of Base

Instead of grouping together 10 collections of size equal to the previous landmark number (as in the case of the Egyptian system), can we get a number system by grouping together 5 collections of size equal to the previous landmark number? Can this 5 be replaced by any positive integer?

Let us examine this possibility. Let 1 be the first landmark number.

Group together 5 collections of size equal to the previous landmark number (1). Its size is the second landmark number which is 5.

Group together 5 collections of size equal to the previous landmark number (5). Its size is the third landmark number which is $5 \times 5 = 25$.

Group together 5 collections of size equal to the previous landmark number (5). Its size is the fourth landmark number which is $5 \times 25 = 125$.

© NCERT not to be republished



Thus, we have a new number system where each landmark number is 5 times the previous one. Since 1 is the first landmark number, they are all powers of 5.

$5^0 = 1$ $5^1 = 5$ $5^2 = 25$ $5^3 = 125$ $5^4 = 625$ $5^5 = 3125$

? Express the number 143 in this new system.

Let us start grouping, starting with the size $5^3 = 125$, as this is the largest landmark number smaller than 143. We get—

$$143 = 125 + 5 + 5 + 5 + 1 + 1 + 1.$$

So the number 143 in the new system is ○□□□△△△.

Number systems having landmark numbers in which the

(a) first landmark number is 1, and

(b) every next landmark number is obtained by multiplying the current landmark number by some fixed number n is said to be a **base-*n*** number system.

The Egyptian number system is a base-10 system, and the number system that we created is a base-5 system. A base-10 number system is also called a **decimal number system.**

? Figure it Out

1. Write the following numbers in the above base-5 system using the symbols in Table 2: 15, 50, 137, 293, 651.

2. Is there a number that cannot be represented in our base-5 system above? Why or why not?

3. Compute the landmark numbers of a base-7 system. In general, what are the landmark numbers of a base-n system?

The landmark numbers of a base-n number system are the powers of n starting from $n^0 = 1, n, n^2, n^3, \ldots$

© NCERT not to be republished

Advantages of a Base-*n* System

What is the advantage of having landmark numbers that are all the powers of a number? To understand this, let us perform some arithmetic operations using them.

Example: Add the following Egyptian numerals:



Let us find the total number of | and ∩ and group them starting from the largest possible landmark number. It has a total of—

15 ∩ and 15 |.

Since 10 ∩ gives the next landmark number ୨, the sum can be regrouped as—

Sum =



© NCERT not to be republished

Since 10| gives a ∩, we have

Sum = 

Figure it Out

1. Add the following Egyptian numerals:

(i)

(ii) 

2. Add the following numerals that are in the base-5 system that we created:

Remember that in this system, 5 times a landmark number gives the next one!

© NCERT not to be republished



Contrast the addition done in a base-*n* number system with that done in the Roman system. In the Roman system, the grouping and rearranging has to be done carefully as it is not always by the same size that each landmark number has to be grouped to get the next one.

The advantage of a number system with a base becomes more evident when we consider multiplication.

? How to multiply two numbers in Egyptian numerals?

Let us first consider the product of two landmark numbers.

? 1. What is any landmark number multiplied by ∩ (that is 10)? Find the following products—

(i) ∩ × ∩ (ii) 𓆼 × ∩ (iii) 𓎆 × ∩ (iv) 𓍢 × ∩

Each landmark number is a power of 10 and so multiplying it with 10 increases the power by 1, which is the next landmark number.

? 2. What is any landmark number multiplied by 𓆼 (10^2)? Find the following products—

(i) ∩ × 𓆼 (ii) 𓆼 × 𓆼 (iii) 𓎆 × 𓆼 (iv) 𓍢 × 𓆼

© NCERT not to be republished

? Find the following products—

(i) (ii) (iii) (iv)

Thus, the product of any two landmark numbers is another landmark number!

? Does this property hold true in the base-5 system that we created? Does this hold for any number system with a base?

Math Talk

? What can we conclude about the product of a number and ∩ (10), in the Egyptian system?

(i)



So,

As these are numbers, the distributive law holds. So,



(ii) 𓎆∩∩| × ∩

𓎆∩∩| is the same as 𓎆 + ∩∩ + |. Thus,

𓎆∩∩| × ∩ = (𓎆 + ∩∩ + |) × ∩

Will the distributive property hold here? For the same reason that it holds for $(a + b) \times n$, it also holds when one of the numbers has more than 2 terms. For example, $(a + b + c) \times n = an + bn + cn$. So,

(𓎆 + ∩∩ + |) × ∩ = (𓎆 × ∩) + (∩∩ × ∩) + (| × ∩)



© NCERT not to be republished

? Now find the following products—

(i) (ii)

? What would be a simple rule to multiply a number with ∩?

As has been seen, a process of multiplying two numbers involves the multiplication of landmark numbers. When the landmark numbers are powers of a number, then their product is another landmark number. This fact simplifies the process of multiplication. However, this is not the case with the Roman numerals, which is why multiplication using them is difficult.

Thus, a number system whose landmark numbers are powers of a number, i.e., a number system with a base, is efficient not only in number representation but also in its utility in carrying out arithmetic operations.

The idea of a number system with a base was a turning point in the history of the evolution of number systems. Our modern Hindu number system is built on this structure.

Abacus that Makes Use of the Decimal System

In around the 11th century, even the people still using the Roman numerals started using a calculating device—the abacus—constructed using a decimal system. It was a board with lines, as shown in the Fig. 3.1. Starting from the line that stood for 1, each successive line stood for a successive power of 10.



Fig. 3.1: Abacus

Numbers were represented in it as follows: the given number was first grouped into the landmark numbers (powers of 10), in exactly the same way we have been grouping them so far. For each power of 10, as many counters were placed on its line as the number of times it occurred

© NCERT not to be republished

in the grouping. The presence of a counter above a line contributed a value of 5.

For example let us take the number 3426. It can be grouped as

3426 = 1000 + 1000 + 1000 + 100 + 100 + 100 + 100 + 10 + 10+ 1 + 1 + 1 + 1 + 1 + 1

This number was represented as shown in Fig. 3.1. Notice how the 6 ones are represented.

To get an idea of how the abacus was used for calculations, let us consider a simple addition problem: 2907 + 43. The two numbers were taken on either side of the vertical partition.



How would you use this to find the sum?

The counters along each line were brought together. What is to be done if the total in a line exceeded 10?

Hint: In this problem, the 7 ones and the 3 ones together make 10 ones which contributes a counter to the line representing 10s.

III. Shortcomings of the Egyptian System

Despite being a number system that enabled relatively efficient number representations for numbers till a crore (10^7), and relatively easy computations, the Egyptian system had a drawback.

If larger and larger numbers needed to be represented, then there was a need for inventing an unending sequence of symbols for higher and higher powers of 10. Here we see the original challenge of number representation resurfacing in a different form!

The next and the final idea in the history of the evolution of number systems not only solves this problem but also remarkably simplifies number representation and computations!

Figure it Out

1. Can there be a number whose representation in Egyptian numerals has one of the symbols occurring 10 or more times? Why not?

Math Talk

© NCERT not to be republished

2. Create your own number system of base 4, and represent numbers from 1 to 16.

Math Talk

3. Give a simple rule to multiply a given number by 5 in the base-5 system that we created.

3.4. Place Value Representation

I. The Mesopotamian Number System

In the beginning, the number system used in ancient Mesopotamia had different symbols for different landmark numbers. In later times, it became a base-60 system, also called the **sexagesimal system**, with a very efficient number representation.

It has puzzled many why they chose base 60. Different theories exist to explain this, ranging from the connection between 60 and the periods of some important events (like the length of their lunar month which had 30 days, or the time taken for the Sun to complete one revolution around the Earth when Earth is taken to be stationary), the ease of representing fractions (we will not go into this here), their earlier sequence of landmark numbers — 1, 10, 60, 600, 3600, 36000,... — getting reduced to only the powers of 60, and so on.

The influence of the Mesopotamian sexagesimal system, also known as the **Babylonian number system**, can be seen even now in our units of time measurements—1 hour = 60 minutes and 1 minute = 60 seconds. This system used the symbol 𒁹 for 1 and 𒌋 for 10.

Let us now briefly pause on the study of their number system, and ideate on how one can build an efficient number system using the Mesopotamian features seen so far.

© NCERT not to be republished

Let us give our own symbols to their landmark numbers—



Note that we have actually used Indian numerals in creating these symbols. We could have invented our own symbols but for the sake of easy recall and use, we have chosen to take help of the familiar numerals 1, 2, 3, ...

Using and , numbers from 1 to 59 can be represented—





Reproduction of a Mesopotamian Tablet

Example: Let us represent the number 640 in this system.

Grouping it into landmark numbers, we see that

$$640 = (10) \times 60 + 40.$$

If we use the Egyptian idea, this number would be represented using 10 s, and 40 would be represented using 4 s.

© NCERT not to be republished

? Can we represent this more compactly?

We can simply represent this number as

which can be read as ten 60s and one 40, just as we have written in the equation.

? **Example:** Let us try another number — 7530.

$$7530 = (2) \times 3600 + (5) \times 60 + 30$$

So, its representation would be

Note that when a number is grouped into powers of 60 for its representation, no power of 60 can occur 60 or more times. If this happens, then 60 of them can be grouped to form the next power of 60. For example, consider the expression—

$$\begin{aligned}(1) \times 3600 + (70) \times 60 + 2 &= (1) \times 60^2 + (60 + 10) \times 60 + 2 \\ &= (1) \times 60^2 + 60^2 + (10) \times 60 + 2 \\ &= (2) \times 60^2 + (10) \times 60 + 2\end{aligned}$$

Therefore, any number can be represented using the numerals from 1–59, along with the numerals for landmark numbers.

Now, what if we make the representation even more compact by dropping the symbols for the different powers of 60 altogether?

	640	7530
Our earlier representation		
Our compact representation		

© NCERT not to be republished

This is exactly what the Mesopotamians did! In their numeral, the rightmost set of symbols showed the number of 1s, the set of symbols to its left showed the number of 60s, the next showed the number of 3600s and so on. Whenever there was no occurrence of a power of 60, a blank space was given in that position.

It does not seem that the Mesopotamians arrived at this idea in the same way we did. Some scholars suggest that the similarity of symbols given to the landmark numbers 1 and 60 in their earlier number system, and an accidental usage of them, might have made them stumble upon this idea.

Figure it Out

1. Represent the following numbers in the Mesopotamian system —

   (i) 63 (ii) 132 (iii) 200 (iv) 60 (v) 3605

Thus, we can see how the Mesopotamian system removes the need for generating an unending sequence of symbols for the landmark numbers by making use of the positions where the symbols are written. Such a number system (having a base) that makes use of the position of each symbol in determining the landmark number that it is associated with is called a **positional number system** or a **place value system.**

This idea of place value marks the highest point in the history of evolution of number systems, and gives a very elegant solution to the problem of representing the unending sequence of numbers using only a finite number of different symbols!

The Mesopotamian system however cannot be considered a fully developed place value system. It has certain defects that lead to confusion while reading a number.

Look at the representation of 60. What will be the representation for 3,600?

While writing the numerals, the spacing between symbols was not given the way we are giving it here. It was also difficult to maintain a consistent spacing for blanks across different manuscripts written by different people. These created ambiguities. For example, consider the representations of the following numbers —

Numbers	1	60	3600	12	602	36002
Our representation	𒁹	𒁹	𒁹	𒌋𒁹	𒌋 𒁹	𒌋 𒁹
Mesopotamian representation	𒁹	𒁹	𒁹	𒌋𒁹	𒌋𒁹	𒌋𒁹

© NCERT not to be republished

Because of the ambiguity in finding which symbols correspond to which powers of 60, the same numeral can be read in different ways. Even in our representation which uses uniform spacing between symbols for different powers of 60, it is difficult to know the number of blanks between two sets of symbols, as in the representation of 36002.

To address the issue arising out of blank spaces, the later Mesopotamians used a brilliant idea of assigning a 'placeholder' symbol 𒌋 to denote a blank space. This is like the 0 (zero) we use in our system. Thus, zero—the symbol that shows nothingness—is indispensable as a placeholder in a place value system in which numbers are written in an unambiguous manner.

Even with the problem arising out of blank spaces solved, other ambiguities still remained in the system. For example, the placeholder symbol was primarily used in the middle of numbers and not at the end; so they would not use it to represent a number like (what we would write as) 3600.

II. The Mayan Number System

In Central America, there flourished a civilisation known as the Mayan civilisation that made great intellectual and cultural progress between the 3rd and 10th centuries CE. Among their intellectual achievements stands their place value system designed independently of those in Asia. They also made use of a placeholder symbol, for the modern-day '0', that looked like a seashell.

© NCERT not to be republished

MAYAN NUMBER SYSTEM

Almost a base-20 system

LANDMARK NUMBERS

1, 20, $20 \times 18 = 360$, $20^2 \times 18 = 7200$, $20^3 \times 18 = 144000$

SYMBOLS is 0 • is 1 —— is 5

Symbols in the Mayan Number system are placed vertically to represent a number.

A numeral

How is this to be read ?

360	• • • •	4
20		11
1		0

Landmark number positions | Vertically placed symbols | Meaning of the symbols

$= (4) \times 360 + (11) \times 20 + (3) \times 10$

$= 1660$

© NCERT not to be republished

Here we find a puzzling phenomenon. Why was their third landmark number 360 rather than 400? Some scholars feel that this might have something to do with their calendars.

They used a dot for 1, and a bar — for 5. These were used to denote numbers from 1 to 19.

The symbols associated with different landmark numbers were written one below the other with the lowermost set of symbols corresponding to the number of 1s, the set above corresponding to the number of 20s, the set above to the number of 360s and so on.

? Represent the following numbers using the Mayan system:

(i) 77 (ii) 100 (iii) 361 (iv) 721

Because the Mayan system is not an actual base-20 system, it lacks the advantages that a system with a base has for computations. Nevertheless, their place value notation and their use of a placeholder symbol for zero is considered an important advance in the history of number systems.

A curious fact is that we can still find the use of base-20 in the number names of some European languages.

III. The Chinese Number System

The Chinese used two number systems—a written system for recording quantities, and a system making use of rods for performing computations. The numerals in the rod-based number system are called **rod numerals.** Here we discuss the rod numerals, which are more efficient in writing and computing with numbers than the written system of the Chinese.

The rod numerals developed in China by at least by 3rd century AD and were used till the 17th century. It was a decimal system (base-10). The symbols for 1 to 9 were as follows:

© NCERT not to be republished

CHINESE NUMBER SYSTEM

Base-10 or Decimal

	1	2	3	4	5	6	7	8	9
Zongs	𝍠	𝍡	𝍢	𝍣	𝍤	𝍥	𝍦	𝍧	𝍨
Hengs	𝍩	𝍪	𝍫	𝍬	𝍭	𝍮	𝍯	𝍰	𝍱

Note: The *zongs* represent units, hundreds, tens of thousands, etc., and the *hengs* tens, thousands, hundreds of thousands, etc.

A numeral 𝍫 𝍥 𝍢 𝍣

How is this to be read?

2 (*Heng*)	6 (*Zong*)	3 (*Heng*)	4 (*Zong*)
𝍪	𝍥	𝍢	𝍣
10^3	10^2	10	1

$= (2) \times 10^3 + (6) \times 10^2 + (3) \times 10 + (4) \times 1$

$= 2634$

数学

Like the Mesopotamians, the rod numerals used a blank space to indicate the skipping of a place value. However, because of the slightly more uniform sizes of the symbols for one through nine, the blank spaces were easier to locate than in the Mesopotamian system.

© NCERT not to be republished

Notice how similar the rod numerals are to the Hindu system. The Chinese system, with a symbol for zero, would be a fully developed place value system.

IV. The Hindu Number System

? Where does the Hindu/Indian number system figure in the evolution of ideas of number representation? What are its landmark numbers? And does it use a place value system?

Hindu Number System

Base-10 or Decimal

Ten symbols 0, 1, 2, 3, 4, 5, 6, 7, 8, 9

A numeral 375

How is this to be read?	3	7	5
Landmark number positions	10^2	10	1

$= (3) \times 10^2 + (7) \times 10 + (5) \times 1$

$= 375$

As can be seen, the Hindu number system is a place value system. The Hindu number system has had a symbol for 0 at least as early as 200 BCE. Because of the use of 0 as a digit, and the use of a single digit in each position, this system does not lead to any kind of ambiguity when

© NCERT not to be republished

reading or writing numerals. It is for this reason that the Hindu number system is now used throughout the world.

The use of 0 as a digit, and indeed as a number, was a breakthrough that truly changed the world of mathematics and science. In Indian mathematics, indeed, zero was not just used as a placeholder in the place value system, but was also given the status of a number in its own right, on par with other numbers. The arithmetic properties of the number 0 (e.g., that 0 plus any number is the same number, and that 0 times any number is zero) were explicitly used by Aryabhata in his *Āryabhaṭīya* in 499 CE to compute with and do elaborate scientific computations using Hindu numerals. The use of 0 as a number like any other number, on which one can perform the basic arithmetic operations, was codified by Brahmagupta in his work *Brāhmasphuṭasiddhānta* in 628 CE, as we learned in an earlier grade.

By introducing 0 as a number, along with the negative numbers, Brahmagupta created what in modern terms is called a **ring**, i.e., a set of numbers that is closed under addition, subtraction, and multiplication (i.e., any two numbers in the set can be added, subtracted, or multiplied to get another number in that set). These new ideas laid the foundations for modern mathematics, and particularly for the areas of algebra and analysis.

Hopefully, this gives you a sense of all the ideas that went into writing and computing with numbers in the way that we do today. The discovery of 0 and the resulting Indian number system is truly one of the greatest, most creative, and most influential inventions of all time—appearing constantly in our daily lives and forming the basis of much of modern science, technology, computing, accounting, surveying, and more. The next time you are writing numbers, think about the incredible history behind them and all the deep ideas that went into their discovery!



Reprint 2026-27

Figure it Out

1. Why do you think the Chinese alternated between the *Zong* and *Heng* symbols? If only the *Zong* symbols were to be used, how would 41 be represented? Could this numeral be interpreted in any other way if there is no significant space between two successive positions?

Math Talk

2. Form a base-2 place value system using '*ukasar*' and '*urapon*' as the digits. Compare this system with that of the Gumulgal's.

3. Where in your daily lives, and in which professions, do the Hindu numerals, and 0, play an important role? How might our lives have been different if our number system and 0 hadn't been invented or conceived of?

4. The ancient Indians likely used base 10 for the Hindu number system because humans have 10 fingers, and so we can use our fingers to count. But what if we had only 8 fingers? How would we be writing numbers then? What would the Hindu numerals look like if we were using base 8 instead? Base 5? Try writing the base-10 Hindu numeral 25 as base-8 and base-5 Hindu numerals, respectively. Can you write it in base-2?

Math Talk



The map shows the locations of the different civilisations. They existed in different time periods.

© NCERT not to be republished

SUMMARY

- To represent numbers, we need a standard sequence of objects, names, or written symbols that have a fixed order. This standard sequence is called a **number system.**
- The symbols representing numbers in a written number system are called **numerals.**
- In a number system, **landmark numbers** are numbers that are easily recognisable and used as reference points for understanding and working with other numbers. They serve as anchors within the number system, helping people to orient themselves and make sense of quantities, particularly larger ones.
- A number system whose landmark numbers are the powers of a number n is referred to as a **base-*n* number system.**
- Number systems having a base that make use of the position of a symbol in determining the landmark number that it is associated with are called **positional number systems** or **place value systems.**
- Place value representations were used in the Mesopotamian (Babylonian), Mayan, Chinese and Indian civilisations.
- The system of numerals that we use throughout the world today is the **Hindu number system** (also sometimes called the **Indian number system,** or the **Hindu-Arabic number system).** It is a place value system with (usually) 10 digits, including the digit 0 which is treated on par with other digits. Due to its use of 0 as a number, the system enables the writing of all numbers unambiguously using just finitely many symbols, and also enables efficient computation. The system originated in India around 2000 years ago, and then spread across the world, and is considered one of human history's greatest inventions.

© NCERT not to be republished

4 QUADRILATERALS

0874CH04

In this chapter, we will study some interesting types of four-sided figures and solve problems based on them. Such figures are commonly known as quadrilaterals. The word 'quadrilateral' is derived from Latin words — *quadri* meaning four, and *latus* referring to sides.

? Observe the following figures.



(i) (ii) (iii)



(iv) (v)

Figs. (i), (ii), and (iii) are quadrilaterals, and the others are not. Why?

The angles of a quadrilateral are the angles between its sides, as marked in Figs. (i), (ii), and (iii).

We will start with the most familiar quadrilaterals—rectangles and squares.

© NCERT not to be republished

4.1 Rectangles and Squares

We know what rectangles are. Let us define them.

Rectangle: A rectangle is a quadrilateral in which—

(i) The angles are all right angles (90°), and

(ii) The opposite sides are of equal length.

The definition precisely states the conditions a quadrilateral has to satisfy to be called a rectangle.

? Are there other ways to define a rectangle?

Let us consider the following problem related to the construction of rectangles.

A Carpenter's Problem

? A carpenter needs to put together two thin strips of wood, as shown in Fig. 1, so that when a thread is passed through their endpoints, it forms a rectangle.



Fig. 1

She already has one 8 cm long strip. What should be the length of the other strip? Where should they both be joined?

Let us first model the structure that the carpenter has to make. The strips can be modelled as line segments. They are the diagonals of the quadrilateral formed by their endpoints. For the quadrilateral to be a rectangle, we need to answer the following questions —

? 1. What is the length of the other diagonal?

? 2. What is the point of intersection of the two diagonals?

? 3. What should the angle be between the diagonals?

? Let us answer these questions using geometric reasoning (deduction). If that is challenging, try to construct/ measure some rectangles.

To find the answers to these questions, let us suppose that we have placed the diagonals such that their endpoints form the vertices of a rectangle, as shown in Fig. 2.



Fig. 2

© NCERT not to be republished

Deduction 1— What is the length of the other diagonal?

This can be deduced using congruence as follows—

Since ABCD is a rectangle, we have

AB = CD
∠BAD = ∠CDA = 90°
AD is common to both triangles.

So, ΔADC ≅ ΔDAB by the SAS congruence condition.



Therefore, AC = BD, since they are corresponding parts of congruent triangles. This shows that the diagonals of a rectangle always have the same length.

So the other diagonal must also be 8 cm long. You can verify this property by constructing/measuring some rectangles.

Deduction 2—What is the point of intersection of the two diagonals?

This can also be found using congruence. Since we need to know the relation between OA and OC, and OB and OD, which two triangles of the rectangle ABCD should we consider?



The blue angles are equal since they are vertically opposite angles.



In order to show congruence, consider ∠1 and ∠2. Are they equal?



Since ∠B = 90°,
∠3 + ∠1 = 90°.



In ΔBCD, since
∠3 + ∠2 + 90 = 180,
we have ∠3 + ∠2 = 90°.

© NCERT not to be republished

So, $\angle 1 = \angle 2$ (= $90° - \angle 3$).
Thus, by the AAS condition for congruence, $\Delta AOB \cong \Delta COD$.

Hence OA = OC and OB = OD, since they are corresponding parts of congruent triangles. So, O is the midpoint of AC and BD.

This shows that **the diagonals of a rectangle always intersect at their midpoints.**

Therefore, to get a rectangle, the diagonals must be drawn so that they are equal and intersect at their midpoints.

When the diagonals cross at their midpoints, we say that the diagonals bisect each other. **Bisecting** a quantity means **dividing it into two equal parts.**

Verify this property by constructing some rectangles and measuring their diagonals and the points of intersection.

? Can the following equalities be used to establish that $\Delta AOD \cong \Delta COB$?

Math Talk

AO = CO (proved above)
$\angle AOB = \angle COD$ (vertically opposite angles)
AD = CB

Deduction 3— What are the angles between the diagonals?

Let us check what quadrilateral we get if we draw the two diagonals such that their lengths are equal, they bisect each other and have an arbitrary angle, say 60°, between them as shown in the figure to the right.



? Can you find all the remaining angles?



We can find the remaining angles between the diagonals using our understanding of vertically opposite angles and linear pairs.



In ΔAOB, since OA = OB, the angles opposite them are equal, say a.

? Can you find the value of a?

© NCERT not to be republished

In ΔAOB, we have,
$a + a + 60 = 180$ (interior angles of a triangle).
Therefore $2a = 120$.
Thus $a = 60$.

Similarly, we can find the values of all the other angles.



? Can we now identify what type of quadrilateral ABCD is?
Notice that its angles all add up to 90° (30° + 60°).

? What can we say about its sides?



We can see that ΔAOB ≅ ΔCOD and ΔAOD ≅ ΔCOB. Hence, AB = CD, and AD = CB, since they are corresponding parts of congruent triangles.

Therefore, ABCD is a rectangle since it satisfies the definition of a rectangle.

? Will ABCD remain a rectangle if the angles between the diagonals are changed? Can we generalise this?

Take one of the angles between the diagonals as x.



© NCERT not to be republished



We can compute the four angles between the diagonals to be x, x, $180 - x$, and $180 - x$.

? Can you find the other angles?

Since we know that ΔAOB is isosceles, we can denote the measures of both of its base angles by a.



? What is the value of a (in degrees) in terms of x?

We have,

$$a + a + x = 180$$

(sum of the interior angles of a triangle)

$$2a = 180 - x$$

$$a = \frac{(180 - x)}{2} = 90 - \frac{x}{2}.$$

Similarly, in the isosceles ΔAOD, let the base angles be b.

$$b + b + 180 - x = 180$$

$$2b = 180 - (180 - x)$$

$$2b = 180 - 180 + x$$

$$2b = x$$

$$b = \frac{x}{2}.$$



All the angles of the quadrilateral are $a + b$, which is

$$90 - \frac{x}{2} + \frac{x}{2} = 90.$$

Thus, all four angles of the quadrilateral ABCD are 90°.

? What can we say about AB and CD, and AD and BC?

We have ΔAOB ≅ ΔCOD and ΔAOD ≅ ΔCOB. Hence, AB = CD, and AD = CB, since they are the corresponding parts of congruent triangles.

© NCERT not to be republished

Hence, no matter what the angles between the diagonals are, if the diagonals are equal and they bisect each other, then the angles of the quadrilateral formed are 90° each, and the opposite sides are equal. Thus, the quadrilateral is a rectangle.

Now we know how the wooden strips have to be put together to form the vertices of a rectangle! They should be equal and connected at their midpoints.







This method is actually used in practice to make rectangles. Carpenters in Europe use this method to get a rectangular frame. It is also known that farmers in Mozambique, a country in Africa, use this method while constructing houses to get the base of the house in a rectangular shape.

The Process of Finding Properties

As we have been seeing from lower grades, properties of geometric objects such as parallel lines, angles, and triangles can be deduced through geometric reasoning. We will continue to deduce properties of special types of quadrilaterals in this chapter.

Once you have deduced a property of a quadrilateral, it is good to verify it with a real-world quadrilateral, either the quadrilateral constructed on paper or simply a surface having the shape of the quadrilateral.

If you are not able to figure out the property using deduction, you could experiment by taking real-world quadrilaterals and observing the property through measurement. Note that these observations give useful insights about the property, but with them, we can only form a **conjecture**, that is, **a statement about which we are highly confident, but not yet sure if it always holds true.** For example, constructing a few rectangles and observing through measurement that their diagonals bisect each other does not necessarily mean that this will always be the case—can we be sure that the 1000th rectangle we construct will also have this property? The only way we can be sure of this property is by justifying or proving the statement, just as we did in Deduction 2.

Note to the Teacher: Gently encourage students to deduce or justify properties. Whenever students face challenges in doing it, encourage them to experiment and observe, and use their intuition to figure out the properties.

© NCERT not to be republished

The Carpenter's Problem shows that rectangles can also be defined as follows—

Rectangle: A rectangle is a quadrilateral whose diagonals are equal and bisect each other.

Observe how different this definition is from the earlier one. Yet, both capture the same class of quadrilaterals. Further, it turns out that the first definition can be simplified.

? In the earlier definition, we stated that a rectangle has (a) opposite sides of equal length, and (b) all angles equal to 90°. Would we be wrong if we just define a rectangle as a quadrilateral in which all the angles are 90°?

? If you think that this definition is incomplete, try constructing a quadrilateral in which the angles are all 90° but the opposite sides are not equal.

Are you able to construct such a quadrilateral?
Let us prove why this is impossible.

Deduction 4—What is the shape of a quadrilateral with all the angles equal to 90°?

? Consider a quadrilateral ABCD with all angles measuring 90°. What can we say about the opposite sides of such a quadrilateral?

Join BD. ΔBAD and ΔDCB seem congruent. Can we justify this claim?



Two equalities can be directly seen in the triangles. What can we say about ∠1 and ∠2?

Recall that we tackled a very similar problem in Deduction 2. We can use the same reasoning here.



Since ∠B = 90°,
∠3 + ∠1 = 90°.



In ΔBCD, since
∠3 + ∠2 + 90° = 180°,
∠3 + ∠2 = 90°.

© NCERT not to be republished

So, $\angle 1 = \angle 2$.
Thus, by the AAS congruence condition, $\Delta BAD \cong \Delta DCB$.

Therefore, AD = CB, and DC = BA, since these are corresponding sides of congruent triangles.

? Is it wrong to write $\Delta BAD \cong \Delta CDB$? Why?

Thus, we have established that if all the angles of a quadrilateral are right angles, then the opposite sides have equal lengths. Therefore, the quadrilateral is a rectangle. Thus, a rectangle can simply be defined as follows —

Rectangle: A rectangle is a quadrilateral in which the angles are all 90°.

Let us list the properties of a rectangle.

Property 1: All the angles of a rectangle are 90°.

Property 2: The opposite sides of a rectangle are equal.

? Are the opposite sides of a rectangle parallel?

They definitely seem so. This fact can be justified using one of the transversal properties.

Notice that AB acts as a transversal to AD and BC, and that $\angle A + \angle B = 90° + 90° = 180°$.

When the sum of the internal angles on the same side of the transversal is 180°, the lines are parallel. We can use this fact to conclude that the lines AD and BC are parallel, which we represent as AD || BC.

Can you similarly show that AB is parallel to DC (AB||DC)?

Property 3: The opposite sides of a rectangle are parallel to each other.

Property 4: The diagonals of a rectangle are of equal length and they bisect each other.

A Special Rectangle

In the quadrilaterals below, are there any non-rectangles?



(i) (ii) (iii) (iv)

© NCERT not to be republished

All these quadrilaterals are rectangles, including (iv). Quadrilateral (iv) is a rectangle because all its angles are 90°. However, it is a special kind of rectangle with all sides of equal length. We know that this quadrilateral is also called a square.

Square: A square is a quadrilateral in which all the angles are equal to 90°, and all the sides are of equal length.

Thus, every square is also a rectangle, but clearly every rectangle is not a square.



This relation can be pictorially represented using a **Venn diagram**. We have seen these diagrams before. In a Venn diagram, a set of objects is represented as points inside a closed curve. Typically, these closed curves are ovals or circles.

For example, the set of all squares is represented as



Each point in the region represents a square, thereby covering all the possible squares.

Since every square is a rectangle, the Venn diagram representation of these two sets would be as follows —



© NCERT not to be republished

? Let us consider the Carpenter's Problem again. If the wooden strips have to be placed such that the thread passing through their endpoints forms a square, what must be done?



As in the previous case, let us try to construct a square, one of whose diagonals is of length 8 cm.

While solving the Carpenter's Problem for the case of a rectangle, we have seen that to get a quadrilateral with all angles 90° (and opposite sides of equal length), the diagonals have to be drawn such that —

(i) they are of equal lengths, and

(ii) they bisect each other.

? What more needs to be done to get equal sidelengths as well? Can this be achieved by properly choosing the angle between the diagonals? See if you can reason and/or experiment to figure this out!

Deduction 5— What should be the angle formed by the diagonals?

The angle between the diagonals can be found using the notion of congruence! Suppose we join the equal diagonals such that they bisect each other and result in a square. Let us label the square ABCD.

To find the angle formed by the diagonals, what are the two triangles we should consider for congruence?



By the SSS condition for congruence, $\Delta BOA \cong \Delta BOC$

? Can this be used to find the angles **$\angle$BOA and $\angle$BOC** formed by the diagonals?

Since these angles are corresponding parts of congruent triangles, they are equal. Further, these angles together form a straight angle. So **$\angle BOA + \angle BOC = 180°$.** Thus, these angles have to be 90° each.

© NCERT not to be republished

This shows that the diagonals of a square bisect each other at right angles. This means that the diagonals have to be drawn such that they are of equal lengths and bisect each other at right angles. Since the endpoints of the diagonals uniquely determine the vertices of a quadrilateral, we will get a square when the diagonals are joined this way.

? Using this fact, construct a square with a diagonal of length 8 cm.

Properties of a Square

Since a square is a special type of rectangle, all the properties of a rectangle hold true for a square.

? Verify if this is true by going through geometric reasoning in Deduction 1 and Deduction 2, and see if they apply to a square as well.

Property 1: All the sides of a square are equal to each other.

Property 2: The opposite sides of a square are parallel to each other.

Property 3: The angles of a square are all 90°.

Property 4: The diagonals of a square are of equal length and they bisect each other at 90°.

There is one more special property of a square.

? What are the measures of ∠1, ∠2, ∠3, and ∠4? See if you can reason and/or experiment to figure this out!



In ΔADC, we have,
∠1 + ∠3 + 90 = 180
Since AD = DC, we have ∠1 = ∠3.
Thus, ∠1 = ∠3 = 45°.

Similarly, find ∠2 and ∠4.

Thus, we have another property of a square —

Property 5: The diagonals of a square divide the angles of the square into equal halves. This can also be expressed as — The diagonals of a square bisect the angles of the square.

© NCERT not to be republished

Figure it Out

1. Find all the other angles inside the following rectangles.



(i)



(ii)

2. Draw a quadrilateral whose diagonals have equal lengths of 8 cm that bisect each other, and intersect at an angle of

   (i) 30° (ii) 40° (iii) 90° (iv) 140°

3. Consider a circle with centre O. Line segments PL and AM are two perpendicular diameters of the circle. What is the figure APML? Reason and/or experiment to figure this out.

4. We have seen how to get 90° using paper folding. Now, suppose we do not have any paper but two sticks of equal length, and a thread. How do we make an exact 90° using these?

Math Talk

5. We saw that one of the properties of a rectangle is that its opposite sides are parallel. Can this be chosen as a definition of a rectangle? In other words, is every quadrilateral that has opposite sides parallel and equal, a rectangle?

Try This

4.2 Angles in a Quadrilateral

Is it possible to construct a quadrilateral with three angles equal to 90° and the fourth angle not equal to 90°?

You might have observed through constructions that this may not be possible.

But why not?

This is due to a general property of quadrilaterals related to their angles.

We have seen that the sum of the angles of a triangle is 180°. There is a similar regularity in the sum of the angles of a quadrilateral.

© NCERT not to be republished

Consider a quadrilateral SOME.

Draw a diagonal SM. We get two triangles ΔSEM and ΔSOM.

In ΔSEM, we have $\angle 1 + \angle 2 + \angle 3 = 180°$.

And in ΔSOM, $\angle 4 + \angle 5 + \angle 6 = 180°$.

What do we get when we add all six angles?

We will have

$\angle 1 + \angle 2 + \angle 3 + \angle 4 + \angle 5 + \angle 6 = 180° + 180°$
$= 360°$.

Or, $(\angle 1 + \angle 4) + (\angle 3 + \angle 6) + \angle 2 + \angle 5 = 360°$.



Since $(\angle 1 + \angle 4)$, $(\angle 3 + \angle 6)$, $\angle 2$ and $\angle 5$ are the angles of this quadrilateral, we have the following result—

The sum of all angles in any quadrilateral is 360°.

This explains why it is impossible for a quadrilateral to have three right angles, with the fourth angle not right angle.

4.3 More Quadrilaterals with Parallel Opposite Sides

Rectangles (and therefore squares) have parallel opposite sides.

? Are there quadrilaterals that have parallel opposite sides that are not rectangles?

Let us try constructing one.

This can be easily done by drawing two pairs of parallel lines, ensuring that they do not meet at right angles.

? Construct such a figure by recalling how parallel lines can be constructed using a ruler and a set-square, or a compass and a ruler.



Observe the quadrilateral ABCD. It has parallel opposite sides but is not a rectangle.

Thus, a larger set of quadrilaterals exists in which the opposite sides are parallel. Such quadrilaterals are called **parallelograms.**

© NCERT not to be republished

? Is a rectangle a parallelogram?

A rectangle has opposite sides parallel. So, it satisfies the parallelogram's definition. Hence, it is indeed a parallelogram. More specifically, a rectangle is a special kind of parallelogram with all its angles equal to 90°.

Let us represent this relation using a Venn diagram.



To understand the relations between the sides and the angles of a parallelogram, let us construct the following figure.

? Draw a parallelogram with adjacent sides of lengths 4 cm and 5 cm, and an angle of 30° between them.



Step 1: Draw line segments AB = 4 cm and AD = 5 cm with an angle of 30° between them.



Step 2: Draw a line parallel to AB through the point D, and a line parallel to AD through B. Mark the point at which these lines intersect as C.

ABCD is the required parallelogram.



? What are the remaining angles of the parallelogram? What are the lengths of the remaining sides? See if you can reason out and/or experiment to figure these out.

© NCERT not to be republished

Deduction 6— What can we say about the angles of a parallelogram?

In the parallelogram ABCD, AB||CD, and AD is a transversal to them.

$\angle A + \angle D = 180°$ (sum of the internal angles on the same side of a transversal).

Therefore,
$\angle D = 180 - \angle A = 180 - 30 = 150°$.

Similarly, AD||BC, and AB and CD are transversals to them.



So, $\angle A + \angle B = 180°$.

So, $\angle C + \angle D = 180°$.

Using these equations, we get $\angle B = 150°$ and $\angle C = 30°$.

We see that in this parallelogram, the **adjacent pairs of angles add up to 180° and opposite pairs of angles are equal.**

Thus,

$\angle A + \angle B = 180°$, $\angle A + \angle D = 180°$, $\angle C + \angle D = 180°$, and $\angle B + \angle C = 180°$.

And,

$\angle A = \angle C$, and $\angle B = \angle D$.

Since the adjacent angles are the interior angles on the same side of a transversal to a pair of parallel lines, they must add up to 180°.

What about the opposite angles? Will they be equal in all parallelograms? If yes, how can we be sure?

Let us take one of the angles to be x.
What are the other angles?
Since $\angle P + \angle R = 180°$,
$\angle R = 180 - \angle P = 180 - x$.
Similarly, since $\angle A + \angle R = 180°$,
$\angle A = 180 - \angle R = 180 - (180 - x) = 180 - 180 + x = x$.
Thus, $\angle P = \angle A = x$.
Similarly, we can deduce that $\angle R = \angle E = 180 - x$.



Therefore, this shows that **the opposite angles of a parallelogram are always equal.**

Deduction 7— What can we say about the sides of a parallelogram?

By looking at a parallelogram, it appears that the opposite sides are equal.

Can we again use congruence to show this? Which two triangles can be considered for this?

© NCERT not to be republished

In ΔABD and ΔCDB, the angles marked with a single arc are equal as they are the opposite angles of a parallelogram.

Since AD | | BC, and BD is a transversal to it, the angles marked with double arcs are equal as they are alternate angles.

So, by the AAS condition, the triangles are congruent, that is, ΔABD ≅ ΔCDB.



Therefore, AD = CB, and AB = CD.
Thus, **the opposite sides of a parallelogram are equal.**

? Is it wrong to write ΔABD ≅ ΔCBD? Why?

From these deductions we can find the remaining sides and angles of the parallelogram.



Let us list the properties of a parallelogram.

Property 1: The opposite sides of a parallelogram are equal.

Property 2: The opposite sides of a parallelogram are parallel.

Property 3: In a parallelogram, the adjacent angles add up to 180°, and the opposite angles are equal.

? Are the diagonals of a parallelogram always equal? Check with the parallelogram that you have constructed.

We see that the diagonals of a parallelogram need not be equal.

? Do they bisect each other (do they intersect at their midpoints)? Reason and/or experiment to figure this out.

Deduction 8— What is the point of intersection of the two diagonals in a parallelogram?

As in the case of a rectangle, we can find out if the diagonals bisect each other by examining the congruence of ΔAOE and ΔYOS in the parallelogram EASY.

© NCERT not to be republished



AE = YS (as they are the opposite sides of the parallelogram)

The angles marked using a single arc are equal, and so are the angles marked using a double arc, since they are alternate angles of parallel lines.

Thus, by the ASA condition, the triangles are congruent, that is,
$\Delta AOE \cong \Delta YOS$.

Therefore, OA = OY, and OE = OS, since they are corresponding parts of congruent triangles.
Thus, O is the midpoint of both diagonals.

? Is it wrong to write $\Delta AOE \cong \Delta SOY$? Why?

Property 4: The diagonals of a parallelogram bisect each other.

? Do the diagonals of a parallelogram intersect at a particular angle?

4.4 Quadrilaterals with Equal Sidelengths

? Are squares the only quadrilaterals that have equal sidelengths? Let us explore this question through construction.

Draw two equal sides AD and AB, that are not perpendicular to each other.



? Can we complete this quadrilateral so that all its sides are of the same length?

Mark a point C whose distance from B and D is equal to AB (or AD). To do this, measure AB using a compass. Keeping this length as the radius, cut arcs from B and D.



Now we have a quadrilateral with equal sidelengths and one of its angles 50°. Note that we could have constructed such a quadrilateral by taking any angle less than 180° (in place of 50°).

A quadrilateral in which all the sides have the same length is a rhombus.

© NCERT not to be republished

? What are the other angles of the rhombus ABCD that we have constructed? Reason and/or experiment to figure this out.

Deduction 9— What can we say about the angles in a rhombus?

Consider a rhombus GAME.
In ΔGAE, since GE = GA, $a = d$.
Similarly, in ΔMAE, since ME = MA, $b = c$.



? It can be seen that ΔGAE ≅ ΔMAE (How?)

So, $a = b$, $c = d$ and ∠G = ∠M (since they are corresponding parts of congruent triangles).
Thus, we have, $a = b = c = d$.

These facts hold for any rhombus. Let us apply them to the rhombus ABCD that we constructed earlier. Let the four equal angles formed by the diagonal be a, as shown in the figure



In ΔADB, we have
$a + a + 50 = 180°$.
So, $a = 65°$.

Thus, the angles of the rhombus *ABCD* are 50°, 130°, 50°, and 130°.



So, **in a rhombus opposite angles are equal to each other.**

Interestingly, there is one more way by which we could have figured out the other angles of the rhombus ABCD. We have shown that in a general rhombus GAME, the four angles formed by a diagonal are equal to each other.



Consider the lines EM and GA and its transversal AE. Since the alternate angles are equal, EM||GA.



Similarly consider the lines GE and AM and its transversal AE. Since the alternate angles are equal, GE||AM.

© NCERT not to be republished

As opposite sides are parallel, GAME is also a parallelogram. Thus, every rhombus is a parallelogram, and the properties of a parallelogram hold true for a rhombus as well. Thus, the adjacent angles of a rhombus add up to 180°, and the opposite angles are equal (verify that the arguments in Deduction 6 can be applied to a rhombus as well!).



Thus, in rhombus ABCD,

$$\angle A = \angle C = 50°, \text{ and}$$

$$\angle D = \angle B = 180 - 50 = 130°.$$

? So a rhombus is a parallelogram, and a rectangle is also a parallelogram. How can this be represented using a Venn diagram?

? Where will the set of squares occur in this diagram?

We know that a square is a rectangle. Since the opposite sides of a square are parallel, a square is also a parallelogram. Further, since all the sides of a square have the same length, a square is also a rhombus. Thus, the Venn diagram will be as follows.



Let us list the properties of a rhombus.

Property 1: All the sides of a rhombus are equal to each other.

Property 2: The opposite sides of a rhombus are parallel to each other.

Property 3: In a rhombus, the adjacent angles add up to 180°, and the opposite angles are equal.

? Are the diagonals of a rhombus equal?

Property 4: The diagonals of a rhombus bisect each other.

Property 5: The diagonals of a rhombus bisect its angles.

© NCERT not to be republished

? Do the diagonals of a rhombus intersect at any particular angle? Reason out and/or experiment to figure this out!

Deduction 10—What can we say about the angles formed by the diagonals of a rhombus at their point of intersection?

? In the rhombus GAME, we have ΔGEO ≅ ΔMEO (why?).

So, ∠GOE = ∠MOE, as they are corresponding parts of congruent triangles. As they add up to 180°, they should be 90° each.



Property 6: Diagonals of a rhombus intersect each other at an angle of 90°.

? Figure it Out

1. Find the remaining angles in the following quadrilaterals.

(i)



(ii)



(iii)



(iv)



2. Using the diagonal properties, construct a parallelogram whose diagonals are of lengths 7 cm and 5 cm, and intersect at an angle of 140°.

3. Using the diagonal properties, construct a rhombus whose diagonals are of lengths 4 cm and 5 cm.

© NCERT not to be republished

4.5 Playing with Quadrilaterals

Geoboard Activity

Take a geoboard and some rubber bands. If you do not have these, you could just use the dot grid papers given at the end of the book for this activity.

Place two rubber bands perpendicular to each other, forming diagonals of equal length. Join the ends.



? What is the quadrilateral that you get? Justify your answer.

Extend one of the diagonals on both sides by 2 cm.



? What quadrilateral will you get now? Justify your answer.

© NCERT not to be republished

Joining Triangles

1. Take two cardboard cutouts of an equilateral triangle of sidelength 8 cm.



? Can you join them to get a quadrilateral?



? What type of a quadrilateral is this? Justify your answer.

2. Take two cardboard cutouts of an isosceles triangle with sidelengths 8 cm, 8 cm, and 6 cm.



? What are the different ways they can be joined to get a quadrilateral?

Joining them in this way you get



Joining them in this way you get



? What quadrilaterals are these? Justify your answers.

© NCERT not to be republished

3. Take two cardboard cutouts of a scalene triangle with sides 6 cm, 9 cm, and 12 cm.



? What are the different ways they can be joined to get a quadrilateral?

? Are you able to identify the different quadrilaterals that are obtained by joining the triangles? Justify your answer whenever you identify a quadrilateral.

4.6 Kite and Trapezium

Kite

One of the ways the two triangles of sides 6 cm, 9 cm and 12 cm can be joined together is as follows —



This quadrilateral looks like a kite. Observe that the adjacent sides are of the same length.

Kite: A kite is a quadrilateral that can be labelled ABCD such that AB = BC, and CD = DA.

? **Property 1:** In the kite, show that the diagonal BD

(i) bisects ∠ABC and ∠ADC,

(ii) bisects the diagonal AC, that is, AO = OC, and is perpendicular to it.

Hint: Is ΔAOB ≅ ΔCOB?



© NCERT not to be republished

Trapezium

Parallelograms are quadrilaterals that have parallel opposite sides. We get a new type of quadrilateral if we relax this condition.
Trapezium: A trapezium is a quadrilateral with at least one pair of parallel opposite sides.



? Construct a trapezium. Measure the base angles (marked in the figure).

? Can you find the remaining angles without measuring them?

Since PQ||SR, we have

Property 1: ∠S + ∠P = **180°** and ∠R + ∠Q = **180°**.

Using these facts, the remaining angles can easily be found. Verify your answer after finding them.

When the non-parallel sides of a trapezium have the same lengths, the trapezium is called an **isosceles trapezium.**

? How do we construct an isosceles trapezium?

? Construct an isosceles trapezium UVWX, with UV||XW. Measure ∠U.



Mark X and W such that UX = VW



Can you find the remaining angles without measuring them?

Does it appear that the angles opposite to the equal sides—∠U and ∠V—are also equal? Can we find congruent triangles here?
Consider line segments XY and WZ perpendicular to UV.

? What type of quadrilateral is XWZY?

Since XW||UV,
a = 180° – ∠XYZ = 90°, and
b = 180° – ∠WZY = 90° (since the internal angles on the same side of a transversal add up to 180°)
Hence, XWZY is a rectangle.



© NCERT not to be republished

Now, it can be shown that $\Delta UXY \cong \Delta VWZ$. (How?)

Thus, $\angle U = \angle V$.

Using this fact, the remaining angles of the isosceles trapezium can be determined. Verify the angles by measurement.

Property 2: In an isosceles trapezium, the angles opposite to the equal sides are equal.

Figure it Out

1. Find all the sides and the angles of the quadrilateral obtained by joining two equilateral triangles with sides 4 cm.
2. Construct a kite whose diagonals are of lengths 6 cm and 8 cm.
3. Find the remaining angles in the following trapeziums—



4. Draw a Venn diagram showing the set of parallelograms, kites, rhombuses, rectangles, and squares. Then, answer the following questions—
   (i) What is the quadrilateral that is both a kite and a parallelogram?
   (ii) Can there be a quadrilateral that is both a kite and a rectangle?
   (iii) Is every kite a rhombus? If not, what is the correct relationship between these two types of quadrilaterals?
5. If PAIR and RODS are two rectangles, find $\angle IOD$.



© NCERT not to be republished

6. Construct a square with diagonal 6 cm without using a protractor.

7. CASE is a square. The points U, V, W and X are the midpoints of the sides of the square. What type of quadrilateral is UVWX? Find this by using geometric reasoning, as well as by construction and measurement. Find other ways of constructing a square within a square such that the vertices of the inner square lie on the sides of the outer square, as shown in Figure (b).



(a)



(b)

8. If a quadrilateral has four equal sides and one angle of 90°, will it be a square? Find the answer using geometric reasoning as well as by construction and measurement.

9. What type of a quadrilateral is one in which the opposite sides are equal? Justify your answer.

   Hint: Draw a diagonal and check for congruent triangles.

10. Will the sum of the angles in a quadrilateral such as the following one also be 360°? Find the answer using geometric reasoning as well as by constructing this figure and measuring.

Try This



11. State whether the following statements are true or false. Justify your answers.

    (i) A quadrilateral whose diagonals are equal and bisect each other must be a square.

© NCERT not to be republished

(ii) A quadrilateral having three right angles must be a rectangle.

(iii) A quadrilateral whose diagonals bisect each other must be a parallelogram.

(iv) A quadrilateral whose diagonals are perpendicular to each other must be a rhombus.

(v) A quadrilateral in which the opposite angles are equal must be a parallelogram.

(vi) A quadrilateral in which all the angles are equal is a rectangle.

(vii) Isosceles trapeziums are parallelograms.

SUMMARY

- A **rectangle** is a quadrilateral in which the angles are all 90°.

  Properties of a rectangle —
  - Opposite sides of a rectangle are equal.
  - Opposite sides of a rectangle are parallel to each other.
  - Diagonals of a rectangle are of equal length and they bisect each other.
- A **square** is a quadrilateral in which all the angles are 90°, and all the sides are of equal length.

  Properties of a square —
  - The opposite sides of a square are parallel to each other.
  - The diagonals of a square are of equal lengths and they bisect each other at 90°.
  - The diagonals of a square bisect the angles of the square.
- A **parallelogram** is a quadrilateral in which opposite sides are parallel.

  Properties of a parallelogram —
  - The opposite sides of a parallelogram are equal.
  - In a parallelogram, the adjacent angles add up to 180°, and the opposite angles are equal.
  - The diagonals of a parallelogram bisect each other.
- A **rhombus** is a quadrilateral in which all the sides have the same length.

© NCERT not to be republished

Properties of a rhombus —

- The opposite sides of a rhombus are parallel to each other.
- In a rhombus, the adjacent angles add up to 180°, and the opposite angles are equal.
- The diagonals of a rhombus bisect each other at right angles.
- The diagonals of a rhombus bisect its angles.

- A **kite** is a quadrilateral with two non-overlapping adjacent pairs of sides having the same length.
- A **trapezium** is a quadrilateral having at least one pair of parallel opposite sides.
- The sum of the angle measures in a quadrilateral is 360°.



© NCERT not to be republished

IT'S PUZZLE TIME!

Which Quad?

Gameplay

1. Fold a sheet into half.





2. Now, fold it once more into a quarter.

3. Make a triangular crease at the corner that is at the middle of the paper.

4. Open the sheet. What is the shape formed by the creases?

5. How would you fold the quarter paper to get the kinds of creases shown in the following image.



6. How would you fold the quarter paper such that a square is formed?

© NCERT not to be republished

5 NUMBER PLAY

0874CH05

5.1 Is This a Multiple Of?

Sum of Consecutive Numbers

Anshu is exploring sums of consecutive numbers. He has written the following—

$7 = 3 + 4$
$10 = 1 + 2 + 3 + 4$
$12 = 3 + 4 + 5$
$15 = 7 + 8$
$= 4 + 5 + 6$
$= 1 + 2 + 3 + 4 + 5$

Now, he is wondering—

- "Can I write every natural number as a sum of consecutive numbers?"
- "Which numbers can I write as the sum of consecutive numbers in more than one way?"
- "Ohh, I know all odd numbers can be written as a sum of two consecutive numbers. Can we write all even numbers as a sum of consecutive numbers?"
- "Can I write 0 as a sum of consecutive numbers? Maybe I should use negative numbers."

Math Talk

? Explore these questions and any others that may occur to you. Discuss them with the class.

? Take any 4 consecutive numbers. For example, 3, 4, 5, and 6. Place '+' and '–' signs in between the numbers. How many different possibilities exist? Write all of them.

$3 + 4 - 5 + 6$
$3 - 4 - 5 - 6$

© NCERT not to be republished

Eight such expressions are possible. You can use the diagram below to systematically list all the possibilities.



? Evaluate each expression and write the result next to it. Do you notice anything interesting?

? Now, take four other consecutive numbers. Place the '+' and '–' signs as you have done before. Find out the results of each expression. What do you observe?

? Repeat this for one more set of 4 consecutive numbers. Share your findings.

Math Talk

3 + 4 – 5 + 6 = 8 3 – 4 – 5 – 6 = – 12 . . .	5 + 6 – 7 + 8 = 12 5 – 6 – 7 – 8 = – 16 . . .	__ + __ – __ + __ = __ __ – __ – __ – __ = __ . . .

Some sums appear always no matter which 4 consecutive numbers are chosen. Isn't that interesting?

? Do these patterns occur no matter which 4 consecutive numbers are chosen? Is there a way to find out through reasoning?

Hint: Use algebra and describe the 8 expressions in a general form.

You might have noticed that the results of all expressions are even numbers. Even numbers have a factor of 2. Negative numbers having a factor 2 are also even numbers, for example, – 2, – 4, – 6, and so on. Check if anyone in your class got an odd number.

When 4 consecutive numbers are chosen, no matter how the '+' and '–' signs are placed between them, the resulting expressions always have even parity.

© NCERT not to be republished

Now take any 4 numbers, place '+' and '–' signs in the eight different ways, and evaluate the resulting expression. What do you observe about their parities?
Repeat this with other sets of 4 numbers.

Math Talk

? Is there a way to explain why this happens?

Hint: Think of the rules for parity of the sum or difference of two numbers.

Explanation 1: Let us consider any of the 8 expressions formed by four numbers a, b, c, and d. When one of its signs is switched, its value always increases or decreases by an even number! Let us see why.
Consider one of the expressions: $a + b - c - d$.
Replacing $+b$ by $-b$, we get

$$a - b - c - d.$$

By how much has the number changed? It has changed by

$$(a + b - c - d) - (a - b - c - d)$$

$= a + b - c - d - a + b + c + d$ (notice how the signs changed when we opened the second set of brackets)

$= 2b$ (this is an even number).

If the difference between two numbers is even, can they have different parities? No! So either both are even or both are odd.

Now, let us see what happens when a negative sign is switched to a positive sign.

? Replace any negative sign in the expression $a + b - c - d$ with a positive sign and find the difference between the two numbers.

? What do you conclude from this observation?

Starting from any expression, we can get 7 expressions by switching one or more '+' and '–' signs. Thus, all the expressions have the same parity!

Explanation 2: We know that

$$\text{odd} \pm \text{odd} = \text{even}$$

$$\text{even} \pm \text{even} = \text{even}$$

$$\text{odd} \pm \text{even} = \text{odd}.$$

We have seen that the parity of $a + b$ and $a - b$ is the same, regardless of the parities of a and b.

In short, $a \pm b$ have the same parity. By the same argument, $a \pm b + c$ and $a \pm b - c$ have the same parity. Extending this further, we can say that all the expressions $a \pm b \pm c \pm d$ have the same parity.

© NCERT not to be republished

Explanation 3: This can also be explained using the positive and negative token model you studied in the chapter on Integers. Try to think how.

The number of ways to choose 4 numbers a, b, c, d and combine them using '+' and '–' signs is infinite. Mathematical reasoning allows us to prove that all the combinations $a \pm b \pm c \pm d$ always have the same parity, without having to go through them one by one.



Several problems in mathematics can be thought about and solved in different ways. While the method you came up with may be dear to you, it can be amusing and enriching to know how others thought about it. Two tidbits: 'share' and 'listen'.

? Is the phenomenon of all the expressions having the same parity limited to taking 4 numbers? What do you think?

'What if ...?', 'Will it always happen?'— Wondering and posing questions and conjectures is as much a part of mathematics as problem solving.

Breaking Even

We know how to identify even numbers. Without computing them, find out which of the following arithmetic expressions are even.

$43 + 37$	$672 - 348$	$4 \times 347 \times 3$	$708 - 477$
$809 + 214$	119×303	$543 - 479$	513^3

? Using our understanding of how parity behaves under different operations, identify which of the following algebraic expressions give an even number for any integer values for the letter-numbers.

$2a + 2b$	$3g + 5h$	$4m + 2n$	$2u - 4v$	
$13k - 5k$	$6m - 3n$	$x^2 + 2$	$b^2 + 1$	$4k \times 3j$

© NCERT not to be republished

The expression $4m + 2q$ will always evaluate to an even number for any integer values of m and q. We can justify this in two different ways—

- We know $4m$ is even and $2q$ is even for any integers m and q. Therefore, their sum will also be even.
- The expression $4m + 2q$ is equal to the expression $2(2m + q)$. Here, the expression $2(2m + q)$ means 2 times $2m + q$. In other words, 2 is a factor of this expression. Therefore, this expression will always give an even number for any integers m and q.

For example, if $m = 4$ and $q = -9$, the expression $4m + 2q$ becomes $4 \times 4 + 2 \times (-9) = -2$, which is an even number.

In the expression $x^2 + 2$, x^2 is even if x is even, and x^2 is odd if x is odd. Therefore, the expression $x^2 + 2$ will **not** always give an even number. An example and a non-example for when the expression evaluates to an even number — (i) if $x = 6$, then $x^2 + 2 = 38$, and (ii) if $x = 3$, then $x^2 + 2 = 11$.

? Similarly, determine and explain which of the other expressions always give even numbers. Write a couple of examples and non-examples, as appropriate, for each expression.

? Write a few algebraic expressions which always give an even number.

Pairs to Make Fours

? Take a pair of even numbers. Add them. Is the sum divisible by 4?

Try this with different pairs of even numbers.
When is the sum a multiple of 4, and when is it not?
Is there a general rule or a pattern?

Even numbers can be of two types based on the remainders they leave when divided by 4.



Even numbers that are multiples of 4 leave a remainder of 0 when divided by 4.



Even numbers that are not multiples of 4 leave a remainder 2 when divided by 4.

© NCERT not to be republished

? When will two even numbers add up to give a multiple of 4?

This problem is similar to the question of identifying when adding two numbers will result in an even number. Can you see this?

There are three cases to examine:

Explanation with Algebra and Visualisation			Examples
Adding two (even) numbers that are multiples of 4 will always give a multiple of 4.	$4p$ and $4q$. $4p + 4q$ $= 4\,(p + q)$.		4, 12, 16, 24, 36. $12 + 16$ $= 4\,(3 + 4)$ $= 28.$ $16 + 28$ $= 4\,(4 + 7)$ $= 44.$
Adding two even numbers that are not multiples of 4 will always give a multiple of 4 because their remainders of 2 add up to 4.	$(4p + 2)$ and $(4q + 2)$. $(4p + 2) + (4q + 2)$ $= 4p + 4q + 4$ $= 4\,(p + q + 1)$.		2, 6, 10, 18, 22, 42. $2 + 6 = 8.$ $6 + 10 = 16.$ $22 + 6 = 28.$

What happens when we add a multiple of 4 to an even number that is not a multiple of 4? Is it similar to the case of the parity of the sum of an even and an odd number?

? Look at the following expressions and the visualisation. Write the corresponding explanation and examples.

© NCERT not to be republished

Explanation with Algebra and Visualisation			Examples
	$4p$ and $(4q + 2)$ $= 4p + (4q + 2)$ $= 4p + 4q + 2$ $= 4 (p + q) + 2.$		

Notice how we are able to generalise and prove properties of arithmetic using algebra and also using visualisation.

Always, Sometimes, or Never

We examine different statements about factors and multiples and determine whether a statement is 'Always True', 'Sometimes True', or 'Never True'.

We know that the sum of any two multiples of 2 is also a multiple of 2.

1. If 8 exactly divides two numbers separately, it must exactly divide their sum.

Explanation with Algebra and Visualisation			Examples
The two numbers have 8 as a factor; in other words, the two numbers are multiples of 8.	$8a$ and $8b$.		8 and 16. 16 and 56. 80 and 120.
As multiples of 8 are obtained by repeatedly adding 8, the sum of two multiples of 8 will also be a multiple of 8.	$8a + 8b$ $= 8 (a + b)$.		8 + 16 = 8(1 + 2) = 24. 16 + 56 = 72. 80 + 120 = 200.

Statement 1 is always true. Determine if it is true with subtraction.

© NCERT not to be republished

In general, **if *a* divides *M* and *a* divides *N*, then *a* divides *M* + *N* and *a* divides *M* – *N*. In other words, if *M* and *N* are multiples of *a*, then *M* + *N* and *M* – *N* will also be multiples of *a*.**

2. If a number is divisible by 8, then 8 also divides any two numbers (separately) that add up to the number.

Explanation with Algebra and Visualisation			Examples
A number divisible by 8 is a multiple of 8.	$8m$		8, 16, 56, 72.
A number divisible by 8 can be expressed as a sum of two multiples of 8 or sum of two non-multiples of 8.	$8m = 8a + 8b$ $8m = p + q$ (p, q not multiples of 8)		72 = 48 + 24 (8×9 = 8×6 + 8×3). 72 = 50 + 22

So, statement 2 is sometimes true.

3. If a number is divisible by 7, then all multiples of that number will be divisible by 7.

Explanation with Algebra and Visualisation			Examples
Numbers divisible by 7 will have 7 as a factor.	$7j$		14 = 7 × 2 (j = 2). 42 = 7 × 6 (j = 6). 98 = 7 × 14 (j = 14).
This contains a total of mj rows. So this is also a multiple of 7.	$(7j) \times m$		Some multiples of 14: 28 = (7 × 2) × 2. 70 = (7 × 2) × 5. 154 = (7 × 2) × 11

The number $7jm$ or $(7 \times j \times m)$ has a factor of 7. We can see that Statement 3 is always true.

© NCERT not to be republished

In general, **if *A* is divisible by *k*, then all multiples of *A* are divisible by *k*.**

? 4. If a number is divisible by 12, then the number is also divisible by all the factors of 12.

Explanation with Algebra and Visualisation			Examples
A number divisible by 12 is a multiple of 12.	$12m$		12, 24, 36, 48, 108, 132.
Factors of multiples of 12 will include factors of 12.	$12m$ $= 2 \times 6 \times m$ $= 3 \times 4 \times m$	 A factor of 12 covers a row fully. Hence, it covers all multiples of 12 fully.	Factors of 24: 1, 2, 3, 4, 6, 8, 12, 24.

In general, **if *A* is divisible by *k*, then *A* is divisible by all the factors of *k*.** Hence, Statement 4 is always true.

? 5. If a number is divisible by 7, then it is also divisible by any multiple of 7.

Explanation with Algebra and Visualisation			Examples
Numbers divisible by 7 are multiples of 7.	$7k$		
Multiples of 7. $7k$ will be divisible by $7m$ if and only if m is a factor of k.	$7m$ *If* $k = ym$ then $7k \div 7m =$ $7ym \div 7m$ $= y$		42 (7×6) is divisible by 7 but it is not divisible by 28 (7×4). 42 (7×6) is divisible by 7 and it is divisible by 14 (7×2).

We can see that this statement is only sometimes true.

© NCERT not to be republished

Examine each of the following statements, and determine whether it is 'Always true', 'Sometimes true', 'Never true'.

Math Talk

6. If a number is divisible by both 9 and 4, it must be divisible by 36.

7. If a number is divisible by both 6 and 4, it must be divisible by 24.

In general, if *A* is divisible by *k* and *A* is also divisible by *m*, then *A* is divisible by the LCM of *k* and *m*. This is because *A* is a multiple of *k* and also a multiple of *m*, so A's prime factorisation should contain the prime factorisation of LCM (*k*, *m*).

8. When you add an odd number to an even number we get a multiple of 6.

We know that multiples of 6 are all even numbers. The sum of an odd number and an even number will be an odd number. Therefore, this statement is never true. We can also explain this algebraically. Suppose,



$$(2n) + (2m + 1) = 6j,$$

where $2n$ is an even number, $2m + 1$ is an odd number, and $6j$ is a multiple of 6. Then

$$2n + 2m = 6j - 1$$

$$2(n + m) = 6j - 1$$

which means $2(n + m)$, which is an even number, should be equal to $6j - 1$, which is an odd number. This is never true.

What Remains?

Find a number that has a remainder of 3 when divided by 5. Write more such numbers.

Which algebraic expression(s) capture all such numbers?

(i) $3k + 5$ (ii) $3k - 5$ (iii) $\frac{3k}{5}$ (iv) $5k + 3$ (v) $5k - 2$ (vi) $5k - 3$

The numbers that leave a remainder of 0 when divided by 5 are the multiples of 5. But we want numbers that leave a remainder of 3 when divided by 5. These numbers are 3 more than multiples of 5. Multiples of 5 are of the form $5k$. So, numbers that leave a remainder of 3 when divided by 5 are those of the form $5k + 3$



k =	0	1	2	3	4
$5k + 3$ =	3	8	13	18	23

© NCERT not to be republished

Let us consider another expression, $5k - 2$, and see the values it takes for different values of k.

Numbers that leave a remainder of 3 when divided by 5 can also be seen as 2 less than multiples of 5; $5k - 2$, where $k \geq 1$.

k =	1	2	3	4	5
$5k - 2$ =	3	8	13	18	23

Are there other expressions that generate numbers that are 3 more than a multiple of 5?

Figure it Out

1. The sum of four consecutive numbers is 34. What are these numbers?
2. Suppose p is the greatest of five consecutive numbers. Describe the other four numbers in terms of p.
3. For each statement below, determine whether it is always true, sometimes true, or never true. Explain your answer. Mention examples and non-examples as appropriate. Justify your claim using algebra.
   (i) The sum of two even numbers is a multiple of 3.
   (ii) If a number is not divisible by 18, then it is also not divisible by 9.
   (iii) If two numbers are not divisible by 6, then their sum is not divisible by 6.
   (iv) The sum of a multiple of 6 and a multiple of 9 is a multiple of 3.
   (v) The sum of a multiple of 6 and a multiple of 3 is a multiple of 9.
4. Find a few numbers that leave a remainder of 2 when divided by 3 and a remainder of 2 when divided by 4. Write an algebraic expression to describe all such numbers.
5. "I hold some pebbles, not too many,
   When I group them in 3's, one stays with me.
   Try pairing them up — it simply won't do,
   A stubborn odd pebble remains in my view.
   Group them by 5, yet one's still around,
   But grouping by seven, perfection is found.
   More than one hundred would be far too bold,
   Can you tell me the number of pebbles I hold?"

6. Tathagat has written several numbers that leave a remainder of 2 when divided by 6. He claims, "If you add any three such numbers, the sum will always be a multiple of 6." Is Tathagat's claim true?

© NCERT not to be republished

7. When divided by 7, the number 661 leaves a remainder of 3, and 4779 leaves a remainder of 5. Without calculating, can you say what remainders the following expressions will leave when divided by 7? Show the solution both algebraically and visually.

   (i) 4779 + 661 (ii) 4779 – 661

8. Find a number that leaves a remainder of 2 when divided by 3, a remainder of 3 when divided by 4, and a remainder of 4 when divided by 5. What is the smallest such number? Can you give a simple explanation of why it is the smallest?

5.2 Checking Divisibility Quickly

Earlier, you have learnt shortcuts to check whether a given number, written in the Indian number system is divisible by 2, 4, 5, 8, and 10. Let us revisit them.

Divisibility by 10, 5, and 2: If the units digit of a number is '0', then it is divisible by 10. Let us understand why this works through algebra.

We can write the general form of a number in the Indian system using a set of letter-numbers. For example, a 5-digit number can be expressed as, *edcba* denoting $e \times 10000 + d \times 1000 + c \times 100 + b \times 10 + a$. The letter-numbers *e*, *d*, *c*, *b*, and *a* denote each digit of a 5-digit number.

Any number can be written in general as ... *dcba*, where the letter-numbers *a*, *b*, *c* and *d* represent the units, tens, hundreds and thousands digit, respectively, and so on. As a sum of place values, this number is —

$$\ldots + 1000d + 100c + 10b + a.$$

(For example, in the number 4075, $d = 4$, $c = 0$, $b = 7$, and $a = 5$.)

We know that each place value, with the exception of the units place, is a multiple of 10. So, $10b$, $100c$, ... all will be multiples of 10. Hence, the number will be divisible by 10 if and only if the units digit *a* is 0.

? Similarly, explain using algebra why the divisibility shortcuts for 5, 2, 4, and 8 work.

Let us now examine shortcuts to check divisibility by some other numbers and explain why they work!

A Shortcut for Divisibility by 9

? Can you say, without actually calculating, which of these numbers are divisible by 9: 999, 909, 900, 90, 990?

All of them.

© NCERT not to be republished

? Can we say that any number made up of only the digits '0' and '9', in any order, will always be divisible by 9?

Yes, if each digit is either 0 or 9, then each term in its expanded form will be 9 × □ or 0 × □ (the '□' denotes a place value). This means each term will be a multiple of 9, for example,

$$99009 = 9 \times 10000 + 9 \times 1000 + 0 \times 100 + 0 \times 10 + 9 \times 1.$$

But this shortcut alone cannot identify all the multiples of 9. Unlike the numbers 2, 5, and 10, we cannot identify the multiples of 9 by just looking at the unit's digit. 99 and 109 are two numbers with 9 as the units digit; but 99 is divisible by 9, while 109 is not.



? Is 10 divisible by 9? If not, what is the remainder?

Check the divisibility of other multiples of 10 (10, 20, 30, ...) by 9.

You will notice that for any multiple of 10, the remainder is the same as the number of tens.

? Similarly, look at the remainder when the multiples of 100 (100, 200, 300, ...) are divided by 9. What do you notice?

The remainder is the same as the number of hundreds for any multiple of 100.

? Using this observation, find the remainder when 427 is divided by 9.



We see that 427 has 4 hundreds; thus, its corresponding remainder (upon division by 9) would be 4. 427 has 2 tens, and its corresponding remainder would be 2. We have 7 units also remaining. Adding all the remainders, we get 4 + 2 + 7 = 13. We can make one more group of 9 with 13, leaving a remainder of 4. Therefore, 427 ÷ 9 gives a remainder of 4.



(Remainder)

© NCERT not to be republished

? Will this work with bigger numbers?



You can see that this is true for any place value:

1 = 0 + 1
10 = 9 + 1
100 = 99 + 1
1000 = 999 + 1
10000 = 9999 + 1, and so on. Each digit thus denotes the remainder when the corresponding place value is divided by 9.

For example, to find the remainder of 7309 when divided by 9, we can just add all the digits—7 + 3 + 0 + 9—to get 19. This can be seen as follows:



$7 \times 1000 + 3 \times 100 + 0 \times 10 + 9 \times 1$
$= 7 \times (999 + 1) + 3 \times (99 + 1) + 0 \times (9 + 1) + 9 \times (0+1)$
$= (7 \times 999 + 3 \times 99 + 0 \times 9 + 9 \times 0) + (7 \times 1 + 3 \times 1 + 0 \times 1 + 9 \times 1)$
$= \underline{(7 \times 999 + 3 \times 99 + 0 \times 9 + 9 \times 0)} + \underline{(7 + 3 + 0 + 9)}.$

This is a multiple of 9 — So, we need to just consider this part

This means that the number 7309 is 19 more than some multiple of 9. The digits 1 and 9 can further be added to get 1 + 9 = 10. Now, we can say that 7309 is 10 more than a multiple of 9. And repeating this step for the number 10, we get the remainder to be 1 + 0 = 1, meaning 7309 is 1 more than a multiple of 9. Therefore, 7309 ÷ 9 gives a remainder of 1.

A number is divisible by 9 if and only if the sum of its digits is divisible by 9. Also, we can add the digits of a number repeatedly till a single digit is obtained. This single digit is the remainder when the number is divided by 9.

? Look at each of the following statements. Which are correct and why?

(i) If a number is divisible by 9, then the sum of its digits is divisible by 9.

© NCERT not to be republished

(ii) If the sum of the digits of a number is divisible by 9, then the number is divisible by 9.

(iii) If a number is not divisible by 9, then the sum of its digits is not divisible by 9.

(iv) If the sum of the digits of a number is not divisible by 9, then the number is not divisible by 9.

Learning maths is not just about knowing some shortcuts and following procedures but about understanding 'why' something works.

Figure it Out

1. Find, without dividing, whether the following numbers are divisible by 9.

   (i) 123 (ii) 405 (iii) 8888 (iv) 93547 (v) 358095

2. Find the smallest multiple of 9 with no odd digits.

3. Find the multiple of 9 that is closest to the number 6000.

4. How many multiples of 9 are there between the numbers 4300 and 4400?

A Shortcut for Divisibility by 3

We know that all the multiples of 9 are also multiples of 3. That is, if a number is divisible by 9, it will also be divisible by 3. However, there are other multiples of 3 that are not multiples of 9 for example— 15, 33, and 87.

The shortcut to find the divisibility by 3 is similar to the method for 9. A number is divisible by 3 if the sum of its digits is divisible by 3. Explore the remainders when powers of 10 are divided by 3. Explain why this method works.

A Shortcut for Divisibility by 11

Interestingly, the shortcut for 11 is also based on checking the remainders with place value. Let us see how.

© NCERT not to be republished

Units place (1)	$11 \times 0 = 0$ $1 = 11 \times 0 + \mathbf{1}$	1 is one more than a multiple of 11.	○
Tens place (10)	$11 \times 1 = 11$ $10 = 11 \times 1 - \mathbf{1}$	10 is one less than a multiple of 11.	
Hundreds place (100)	$11 \times 9 = 99$ $100 = 11 \times 9 + \mathbf{1}$	100 is one more than a multiple of 11.	
Thousands place (1000)	$11 \times 91 = 1001$ $1000 = 11 \times 91 - \mathbf{1}$	1000 is one less than a multiple of 11.	
. . . .	. . . .	. . . .	. . . .

This alternating pattern of one more than 11 and one less than 11 continues for higher place values.

Since 400 contains 4 hundreds, 400 is 4 more than a multiple of 11 (396 + 4). Since 60 contains 6 tens, 60 is 6 less than a multiple of 11 (66 – 6). Since 2 contains 2 units, 2 is 2 more than a multiple of 11, i.e., 2 = (0 + 2).

? Using these observations, can you tell whether the number 462 is divisible by 11?

Math Talk

? What could be a general method or shortcut to check divisibility by 11?

Math Talk

© NCERT not to be republished

We saw that the place values alternate as 1 more and 1 less than a multiple of 11. Using this observation,

Steps	Purpose	Example for the Number 320185
1. Add the digits of place values which are 1 more (than a multiple of 11), i.e., place values corresponding to 1, 100, 10000, and so on.	To know how much in excess we are with respect to a multiple of 11 for these place values.	 Total excess, 2 + 1 + 5 = 8.
2. Add the digits of place values which are 1 less (than a multiple of 11), i.e., place values corresponding to 10, 1000, 100000, and so on.	To know how short we are with respect to a multiple of 11 for these place values.	 Total short, 3 + 0 + 8 = 11.
3. Compute the difference between these two sums, i.e., (number in excess) – (number short).	To know the remainder obtained when divided by 11.	8 – 11 = – 3. (3 short of a multiple of 11)

The difference between these two sums 8 – 11 = – 3, indicating that the number 3,28,105 is 3 short of or 8 more than a multiple of 11.

? If this difference is 11 or a multiple of 11, what does that say about the remainder obtained when the number is divisible by 11?

? Using this shortcut, find out whether the following numbers are divisible by 11. Further, find the remainder if the number is not divisible by 11.

(i) 158 (ii) 841 (iii) 481 (iv) 5529 (v) 90904 (vi) 857076

© NCERT not to be republished

Look at the following procedure—

Steps to follow	Example for the number 328105
1. Place alternating '+' and '–' signs before every digit starting from the unit's digit.	–3 + 2 – 8 + 1 – 0 + 5
2. Evaluate the expression.	–3 + 2 – 8 + 1 – 0 + 5 = – 3
3. The result denotes the remainder obtained when the number is divided by 11.	328105 is 3 less than or 8 more than a multiple of 11

? Is this method similar to or different from the method we saw just before?

? Fill in the following table. Find a quick way to do this?

Math Talk

Number	Divisible by								
	2	3	4	5	6	8	9	10	11
128	Yes	No	No	No	No	Yes	No	No	No
990									
1586									
275									
6686									
639210									
429714									
2856									
3060									
406839									

More on Divisibility Shortcuts

Divisibility Shortcuts for Other Numbers

? How can we find out if a number is divisible by 6?

? Will checking its divisibility by its factors 2 and 3 work? Use the shortcuts for 2 and 3 on these numbers and divide each number by 6 to verify—38, 225, 186, 64.

© NCERT not to be republished

? How about checking divisibility by 24? Will checking the divisibility by its factors, 4 and 6, work? Why or why not?

Determining divisibility by 24 by checking divisibility by 4 and by 6 does not work. For example, the number 12 is divisible by both 4 and 6, but not by 24.

To check for the divisibility by 24, we can instead check for the divisibility by 3 and divisibility by 8.

Explain using prime factorisation why checking divisibility by 3 and 8 works for checking divisibility by 24, but checking divisibility by 4 and 6 is not sufficient for checking divisibility by 24.

There are such shortcuts to check divisibility by every number until 100, and for some numbers beyond 100. You may try to understand how these work after learning certain concepts in higher grades.

Digital Roots

Take a number. Add its digits repeatedly till you get a single-digit number. This single-digit number is called the digital root of the number. For example, the digital root of the number 489710 will be

2 (4 + 8 + 9 + 7 + 1 + 0 = 29, 2 + 9 = 11, 1 + 1 = 2).

? What property do you think this digital root will have? Recall that we did this while finding the divisibility shortcut for 9.

? Between the numbers 600 and 700, which numbers have the digital root: (i) 5, (ii) 7, (iii) 3?

Math Talk

? Write the digital roots of any 12 consecutive numbers. What do you observe?

We saw that the digital root of multiples of 9 is always 9.

? Now, find the digital roots of some consecutive multiples of (i) 3, (ii) 4, and (iii) 6.

? What are the digital roots of numbers that are 1 more than a multiple of 6? What do you notice?

Try to explain the patterns noticed.

? I'm made of digits, each tiniest and odd,
No shared ground with root #1—how odd!

My digits count, their sum, my root—
All point to one bold number's pursuit—
The largest odd single-digit I proudly claim.

What's my number? What's my name?

© NCERT not to be republished

Aryabhata II's (c. 950 CE) work *Mahāsiddhānta*, mentions the method of computing the digital root of a number by repeatedly adding the digits till a single-digit number is obtained. This method is known to have been used to perform checks on calculations of arithmetic operations.

Figure it Out

1. The digital root of an 8-digit number is 5. What will be the digital root of 10 more than that number?
2. Write any number. Generate a sequence of numbers by repeatedly adding 11. What would be the digital roots of this sequence of numbers? Share your observations.
3. What will be the digital root of the number $9a + 36b + 13$?
4. Make conjectures by examining if there are any patterns or relations between
   (i) the parity of a number and its digital root.
   (ii) the digital root of a number and the remainder obtained when the number is divided by 3 or 9.

Math Talk

5.3 Digits in Disguise

Last year, we saw cryptarithms—puzzles where each letter stands for a digit, each digit is represented by at most one letter, and the first digit of a number is never 0.

Solve the cryptarithms given below.

(i) $\begin{array}{r} A1 \\ +\ 1B \\ \hline B0 \end{array}$ (ii) $\begin{array}{r} AB \\ +\ 37 \\ \hline 6A \end{array}$ (iii) $\begin{array}{r} ON \\ ON \\ +\ ON \\ \hline PO \end{array}$ (iv) $\begin{array}{r} QR \\ QR \\ +\ QR \\ \hline PRR \end{array}$

Let us now try solving some cryptarithms involving multiplication.

(v) PQ × 8 = RS.



Guna says, "Oh, this means a 2-digit number multiplied by 8 should give another 2-digit number. I know that 10 × 8 = 80. But the units digits of 10 and 80 are the same, which we don't want. For the same reason PQ cannot be 11 as P and Q correspond to different digits. 12 × 8 = 96 fits all the conditions". Can PQ be 13? Think.

It is not possible because 13 × 8 = 104. For all 2-digit numbers greater than 12, the product with 8 is a 3-digit number.

© NCERT not to be republished

(vi) Try this now: GH × H = 9K.

This means a 2-digit number multiplied by a 1-digit number gives another 2-digit number in the 90s. Observe the letters corresponding to the units digits in this cryptarithm. Pick the solution to this question from the options given below:

11 × 9 = 99, 12 × 8 = 96, 46 × 2 = 92, 24 × 4 = 96, 47 × 2 = 94, 31 × 3 = 93, 16 × 6 = 96.

(vii) Here is one more: BYE × 6 = RAY.

Anshu says, "Since the product is a 3-digit number, B can't be 2 or more. If B = 2, i.e., 2 hundreds, the product will be more than 1200. So, B = 1."

What can you say about 'Y'? What digits are possible/not possible?

"Y cannot be 7 or more because, if Y = 7, then 170 × 6 = 1020; but we want a 3-digit product. Also, Y will be even", Anshu explains.

We can solve cryptarithms using patterns, properties, and reasoning related to numbers and operations.

Solve the following:

(i) UT × 3 = PUT (ii) AB × 5 = BC (iii) L2N × 2 = 2NP
(iv) XY × 4 = ZX (v) PP × QQ = PRP (vi) JK × 6 = KKK

Figure it Out

1. If 31z5 is a multiple of 9, where z is a digit, what is the value of z? Explain why there are two answers to this problem.

2. "I take a number that leaves a remainder of 8 when divided by 12. I take another number which is 4 short of a multiple of 12. Their sum will always be a multiple of 8", claims Snehal. Examine his claim and justify your conclusion.

3. When is the sum of two multiples of 3, a multiple of 6 and when is it not? Explain the different possible cases, and generalise the pattern.

4. Sreelatha says, "I have a number that is divisible by 9. If I reverse its digits, it will still be divisible by 9".
   (i) Examine if her conjecture is true for any multiple of 9.
   (ii) Are any other digit shuffles possible such that the number formed is still a multiple of 9?

5. If 48a23b is a multiple of 18, list all possible pairs of values for a and b.

© NCERT not to be republished

6. If $3p7q8$ is divisible by 44, list all possible pairs of values for p and q.

7. Find three consecutive numbers such that the first number is a multiple of 2, the second number is a multiple of 3, and the third number is a multiple of 4.
Are there more such numbers? How often do they occur?

Try This

8. Write five multiples of 36 between 45,000 and 47,000. Share your approach with the class.

Math Talk

9. The middle number in the sequence of 5 consecutive even numbers is $5p$. Express the other four numbers in sequence in terms of p.

10. Write a 6-digit number that it is divisible by 15, such that when the digits are reversed, it is divisible by 6.

11. Deepak claims, "There are some multiples of 11 which, when doubled, are still multiples of 11. But other multiples of 11 don't remain multiples of 11 when doubled". Examine if his conjecture is true; explain your conclusion.

12. Determine whether the statements below are 'Always True', 'Sometimes True', or 'Never True'. Explain your reasoning.
    (i) The product of a multiple of 6 and a multiple of 3 is a multiple of 9.
    (ii) The sum of three consecutive even numbers will be divisible by 6.
    (iii) If *abcdef* is a multiple of 6, then *badcef* will be a multiple of 6.
    (iv) $8\,(7b - 3) - 4\,(11b + 1)$ is a multiple of 12.

13. Choose any 3 numbers. When is their sum divisible by 3? Explore all possible cases and generalise.

14. Is the product of two consecutive integers always multiple of 2? Why? What about the product of these consecutive integers? Is it always a multiple of 6? Why or why not? What can you say about the product of 4 consecutive integers? What about the product of five consecutive integers?

15. Solve the cryptarithms —
    (i) EF × E = GGG
    (ii) WOW × 5 = MEOW

16. Which of the following Venn diagrams captures the relationship between the multiples of 4, 8, and 32?

© NCERT not to be republished

(i)



(ii)



(iii)



(iv)



SUMMARY

- We explored and learnt various properties of divisibility—
  - If a is divisible by b, then all multiples of a are divisible by b.
  - If a is divisible by b, then a is divisible by all the factors of b.
  - If a divides m and a divides n, then a divides $m + n$ and $m - n$.
  - If a is divisible by b and is also divisible by c, then a is divisible by the LCM of b and c.
- We learnt shortcuts to check divisibility by 3, 9 and 11, and why they work.
- Through all this we were exposed to the power of mathematical thinking and reasoning, using algebra, visualisation, examples and counterexamples.

© NCERT not to be republished



Navakankari

Navakankari, also known as *Sālu Mane Āṭa*, *Chār-Pār*, or *Navkakri*, is a traditional Indian board game that is the same as 'Nine Men's Morris' or 'Mills in the West'. It is a strategy game for two players where the goal is to form lines of three pawns to eliminate the opponent's pawns or block their movement.



Gameplay

1. Each player starts with 9 pawns. The players take turns in placing their pawns on the marked intersections. An intersection can have at most one pawn.
2. Once all the pawns are placed, the players take turns to move one of their pawns to adjacent empty intersections to form lines of three. The line can be horizontal or vertical.
3. Once a player makes a line with their pawns they can remove any one of the opponent's pawns as long as it is not a part of one of their lines.

A player wins if the opponent has less than 3 pawns or is unable to make a move.

© NCERT not to be republished

6 WE DISTRIBUTE, YET THINGS MULTIPLY

We have seen how algebra makes use of letter symbols to write general statements about patterns and relations in a compact manner. Algebra can also be used to justify or prove claims and conjectures (like the many properties you saw in the previous chapter) and to solve problems of various kinds.

Distributivity is a property relating multiplication and addition that is captured concisely using algebra. In this chapter, we explore different types of multiplication patterns and show how they can be described in the language of algebra by making use of distributivity.

6.1 Some Properties of Multiplication

Increments in Products

Consider the multiplication of two numbers, say, 23 × 27.

? 1. By how much does the product increase if the first number (23) is increased by 1?

? 2. What if the second number (27) is increased by 1?

? 3. How about when both numbers are increased by 1?

? Do you see a pattern that could help generalise our observations to the product of any two numbers?

Let us first consider a simpler problem—find the increase in the product when 27 is increased by 1. From the definition of multiplication (and the commutative property), it is clear that the product increases by 23. This can be seen from the distributive property of multiplication as well. If a, b and c are three numbers, then—

© NCERT not to be republished

$$a\,(b + c) = ab + ac$$

This property can be visualised nicely using a diagram:



$a\,(b + c)$

This is called the **distributive property** of multiplication over addition. Using the identity $a\,(b + c) = ab + ac$ with $a = 23$, $b = 27$, and $c = 1$, we have

$$23\,(27 + 1) = 23 \times 27 + \boxed{23}$$
Increase

Remember that here, $a\,(b + c)$ and $23\,(27 + 1)$ mean $a \times (b + c)$, and $23 \times (27 + 1)$, respectively. We usually skip writing the '×' symbol before or after brackets, just as in the case of expressions like $5a$, xy, etc.

We can also similarly expand $(a + b)\,c$ using the distributive property as follows—

$$\begin{aligned}(a + b)\,c &= c\,(a + b) \text{ (commutativity of multiplication)}\\ &= ca + cb \text{ (distributivity)}\\ &= ac + bc \text{ (commutativity of multiplication)}\end{aligned}$$

We can use the distributive property to find, in general, how much a product increases if one or both the numbers in the product are increased by 1. Suppose the initial two numbers are a and b. If one of the numbers, say b, is increased by 1, then we have—

$$a\,(b + 1) = ab + \boxed{a}$$
Increase

Now let us see what happens if both numbers in a product are increased by 1. If in a product ab, both a and b are increased by 1, then we obtain $(a + 1)\,(b + 1)$.

© NCERT not to be republished

? How do we expand this?

Let us consider $(a + 1)$ as a single term. Then, by the distributive property, we have

$(a + 1)(b + 1) = (a + 1)\, b + (a + 1)\, 1$

Again applying the distributive property, we obtain

$(a + 1)(b + 1) = (a + 1)\, b + (a + 1)\, 1$

$= ab + \boxed{(b + a + 1)}$

Increase

If $a = 23$, and, $b = 27$, we get

$(23 + 1)(27 + 1) = (23 + 1)\, 27 + (23 + 1)\, 1$

$= 23 \times 27 + \boxed{(27 + 23 + 1)}$

Increase

Thus, the product ab increases by $a + b + 1$ when each of a and b are increased by 1.

? What would we get if we had expanded $(a + 1)(b + 1)$ by first taking $(b + 1)$ as a single term? Try it?

? What happens when one of the numbers in a product is increased by 1 and the other is decreased by 1? Will there be any change in the product?

Let us again take the product ab of two numbers a and b. If a is increased by 1 and b is decreased by 1, then their product will be $(a + 1)(b - 1)$. Expanding this, we get

$(a + 1)(b - 1) = (a + 1)\, b - (a + 1)\, 1$

$= ab + b - (a + 1)$

$= ab + \boxed{b - a - 1}$

Increase

If $a = 23$, and $b = 27$, we get

$(23 + 1)(27 - 1) = (23 + 1)\, 27 - (23 + 1)\, 1$

$= 23 \times 27 + 27 - (23 + 1)$

$= 23 \times 27 + \boxed{27 - 23 - 1}$

Increase

? Will the product always increase? Find 3 examples where the product decreases.

? What happens when a and b are negative integers?

Check by substituting different values for a and b in each of the above cases. For example, $a = -5$, $b = 8$; $a = -4$, $b = -5$; etc.

We have seen that integers also satisfy the distributive property, that is, if x, y and z are any three integers, then $x\,(y + z) = xy + xz$.

Thus, the expressions we have for increase of products hold when the letter-numbers take on negative integer values as well.

Recall that two algebraic expressions are equal if they take on the same values when their letter-numbers are replaced by numbers. These

© NCERT not to be republished

numbers could be any integers. Mathematical statements that express the equality of two algebraic expressions, such as

$$a\,(b + 8) = ab + 8a,$$

$$(a + 1)\,(b - 1) = ab + b - a - 1, \text{ etc.,}$$

are called **identities.**

? By how much will the product of two numbers change if one of the numbers is increased by m and the other by n?

If a and b are the initial numbers being multiplied, they become $a + m$ and $b + n$.

$$(a + m)\,(b + n) = (a + m)b + (a + m)n$$

$$= ab + mb + an + mn$$

The increase is $an + bm + mn$.

Notice that the product is the sum of the product of each term of $(a + m)$ with each term of $(b + n)$.

Identity 1 $(a + m)\,(b + n) = ab + mb + an + mn$

This identity can be visualised as follows—



$(a + m)\,(b + n)$

© NCERT not to be republished

? This identity can be used to find how products change when the numbers being multiplied are increased or decreased by any amount. Can you see how this identity can be used when one or both numbers are decreased?

For example, let us reconsider the case when one number is increased by 1 and the other decreased by 1. Let us write the product $(a + 1)(b – 1)$ as $(a + 1)(b + (–1))$. Taking $m = 1$ and $n = –1$ in Identity 1, we have

$$ab + (1) \times b + a \times (–1) + (1) \times (–1) = ab + b – a – 1,$$

which is the same expression that we obtain earlier.

? Use Identity 1 to find how the product changes when

(i) one number is decreased by 2 and the other increased by 3;

(ii) both numbers are decreased, one by 3 and the other by 4.

? Verify the answers by finding the products without converting the subtractions to additions.

Generalising this, we can find the product $(a + u)(b – v)$ as follows.

$$\begin{aligned}(a + u)(b – v) &= (a + u)\, b – (a + u)\, v \\ &= ab + ub – (av + uv) \\ &= ab + ub – av – uv.\end{aligned}$$

Check that this is the same as taking $m = u$ and $n = –v$ in Identity 1.

As in Identity 1, the product $(a + u)(b – v)$ is the sum of the product of each term of $a + u$ (a and u) with each term of $b – v$ (b and $(–v)$). Notice that the signs of the terms in the products can be determined using the usual rules of integer multiplication.

See how the rules of integer multiplication allows us to handle multiple cases using a single identity!

? Expand (i) $(a – u)(b + v)$, (ii) $(a – u)(b – v)$.

We get

$$(a – u)(b + v) = ab – ub + av – uv, \text{ and}$$

$$(a – u)(b – v) = ab – ub – av + uv.$$

The distributive property is not restricted to two terms within a bracket.

? **Example 1:** Expand $\frac{3a}{2}(a – b + \frac{1}{5})$.

$$\frac{3a}{2}(a – \text{b} + \frac{1}{5}) = (\frac{3a}{2} \times a) – (\frac{3a}{2} \times b) + (\frac{3a}{2} \times \frac{1}{5}).$$

The terms can be simplified as follows—

$$\frac{3a}{2} \times a = \frac{3}{2} \times (a \times a).$$

© NCERT not to be republished

Using exponent notation, we can write $\frac{3}{2} \times (a \times a) = \frac{3}{2} a^2$.

$$\frac{3a}{2} \times b = \frac{3}{2} \times (a \times b) = \frac{3}{2} ab.$$

$$\frac{3a}{2} \times \frac{1}{5} = (\frac{3}{2} \times \frac{1}{5})\ a = \frac{3}{10} a$$

So we get

$$\frac{3a}{2} (a - b + \frac{1}{5}) = \frac{3}{2}a^2 - \frac{3}{2} ab + \frac{3}{10} a.$$

? Can any two terms be added to get a single term?

For example, can $\frac{3}{2} a^2$ and $\frac{3}{10} a$ be added to get a single term?

We see that no two terms have exactly the same letter-numbers, which would have allowed them to be simplified into a single term. So, a further simplification of the expression is not possible.
Recall that we call terms having the same letter-numbers **like terms.**

? **Example 2:** Expand $(a + b)\ (a + b)$.

We have $(a + b)\ (a + b) = (a+b)\ a + (a + b)b = a \times a + b \times a + ab + b \times b$

$$= a^2 + ba + ab + b^2$$

Since $ba = ab$, we have two terms having the same letter-numbers ab (or, that are like terms), and so can be added —

$$ba + ab = ab + ab = 2ab$$

So we get

$$(a + b)\ (a + b) = a^2 + 2ab + b^2.$$

? **Example 3:** Expand $(a + b)\ (a^2 + 2ab + b^2)$.

$(a + b)\ (a^2 + 2ab + b^2) = (a + b)a^2 + (a + b) \times 2ab + (a + b)b^2$
$= (a \times a^2) + ba^2 + (a \times 2ab) + (b \times 2ab) + ab^2 + (b \times b^2)$

The terms can be simplified as follows—

$$a \times a^2 = a^3 \text{ (why?)}$$

$$ba^2 = a^2b$$

$$a \times 2ab = 2 \times a \times a \times b = 2a^2b$$

$$b \times 2ab = 2 \times a \times b \times b = 2ab^2$$

$$b \times b^2 = b^3$$

So, $(a + b)(a^2 + 2ab + b^2) = a^3 + a^2b + 2a^2b + 2ab^2 + ab^2 + b^3$.

We see that a^2b and $2a^2b$ have the same letter-numbers (or, are like terms) and so can be added—

© NCERT not to be republished

$$a^2b + 2a^2b = (1 + 2)\, a^2\, b = 3a^2\, b.$$

Similarly, ab^2 and $2ab^2$ are like terms and so can be added—

$$ab^2 + 2ab^2 = (1 + 2)ab^2 = 3ab^2.$$

Thus, we have

$$(a + b) \times (a^2 + 2ab + b^2) = a^3 + 3a^2b + 3ab^2 + b^3.$$

A Pinch of History

The distributive property of multiplication over addition was implicit in the calculations of mathematicians in many ancient civilisations, particularly in ancient Egypt, Mesopotamia, Greece, China, and India. For example, the mathematicians Euclid (in geometric form) and Āryabhaṭa (in algebraic form) used the distributive law in an implicit manner extensively in their mathematical and scientific works. The first explicit statement of the distributive property was given by Brahmagupta in his work *Brahmasphuṭasiddhānta* (Verse 12.55), who referred to the use of the property for multiplication as *khaṇḍa-guṇanam* (multiplication by parts). His verse states, "The multiplier is broken up into two or more parts whose sum is equal to it; the multiplicand is then multiplied by each of these and the results added". That is, if there are two parts, then using letter symbols this is equivalent to the identity $(a + b)\, c = ac + bc$. In the next verse (Verse 12.56), Brahmagupta further describes a method for doing fast multiplication using this distributive property, which we explore further in the next section.

Figure it Out

1. Observe the multiplication grid below. Each number inside the grid is formed by multiplying two numbers. If the middle number of a 3 × 3 frame is given by the expression pq, as shown in the figure, write the expressions for the other numbers in the grid.

x	1	2	3	4	5	6	7	8	9	10
1	1	2	3	4	5	6	7	8	9	10
2	2	4	6	8	10	12	14	16	18	20
3	3	6	9	12	15	18	21	24	27	30
4	4	8	12	16	20	24	28	32	36	40
5	5	10	15	20	25	30	35	40	45	50
6	6	12	18	24	30	36	42	48	54	60
7	7	14	21	28	35	42	49	56	63	70
8	8	16	24	32	40	48	56	64	72	80
9	9	18	27	36	45	54	63	72	81	90
10	10	20	30	40	50	60	70	80	90	100

3 × 5	3 × 6	3 × 7
4 × 5	4 × 6	4 × 7
5 × 5	5 × 6	5 × 7

	pq	

Reprint 2026-27

2. Expand the following products.

(i) $(3 + u)(v - 3)$ (ii) $\frac{2}{3}(15 + 6a)$

(iii) $(10a + b)(10c + d)$ (iv) $(3 - x)(x - 6)$

(v) $(-5a + b)(c + d)$ (vi) $(5 + z)(y + 9)$

3. Find 3 examples where the product of two numbers remains unchanged when one of them is increased by 2 and the other is decreased by 4.

Math Talk

4. Expand (i) $(a + ab - 3b^2)(4 + b)$, and (ii) $(4y + 7)(y + 11z - 3)$.

5. Expand (i) $(a - b)(a + b)$, (ii) $(a - b)(a^2 + ab + b^2)$ and (iii) $(a - b)(a^3 + a^2b + ab^2 + b^3)$, Do you see a pattern? What would be the next identity in the pattern that you see? Can you check it by expanding?

Fast Multiplications Using the Distributive Property

The distributive property can be used to come up with quick methods of multiplication when certain types of numbers are multiplied.

When one of the numbers is 11, 101, 1001, ...

? Use the following multiplications to find the product of a number with 11 in a single step.

(a) 3874×11 (b) 5678×11

Let us take the first multiplication.

$$3874 \times 11 = 3874\,(10 + 1) = 38740 + 3874$$

$$\begin{array}{r} 38740 \\ +\ \ 3874 \\ \hline \\ \hline \end{array}$$

Notice how the digits are getting added.

Let us take a 4-digit number *dcba*, that is, the number that has *d* in the thousands place, *c* in the hundreds place, b in the tens place and *a* in the units place.

$$dcba \times (10 + 1) = dcba \times 10 + dcba.$$

This becomes

	d	c	b	a	o
+		d	c	b	a
	d	$(c + d)$	$(b + c)$	$(a + b)$	a

© NCERT not to be republished

This can be used to obtain the product in one line.

Step 1

$$\begin{array}{r} 3874 \times 11 \\ \hline 4 \end{array}$$

Step 2

$$\begin{array}{r} \overset{1}{\frown}+ \\ 3874 \times 11 \\ \hline 14 \end{array}$$

Step 3

$$\begin{array}{r} \overset{11}{\frown}+ \\ 3874 \times 11 \\ \hline 614 \end{array}$$

Step 4

$$\begin{array}{r} \overset{111}{\frown}+ \\ 3874 \times 11 \\ \hline 2614 \end{array}$$

Step 5

$$\begin{array}{r} 111 \\ 3874 \times 11 \\ \hline 42614 \end{array}$$

? Describe a general rule to multiply a number (of any number of digits) by 11 and write the product in one line.

Evaluate (i) 94 × 11, (ii) 495 × 11, (iii) 3279 × 11, (iv) 4791256 × 11.

Math Talk

? Can we come up with a similar rule for multiplying a number by 101?

? Multiply 3874 by 101.

Let us take a 4-digit number *dcba*.

$$dcba \times 101 = dcba \times (100 + 1) = dcba \times 100 + dcba.$$

This becomes

$$\begin{array}{cccccccc} & d & c & b & a & o & o \\ + & & & d & c & b & a \\ \hline & d & c & (b+d) & (a+c) & b & a \end{array}$$

? Use this to multiply 3874 × 101 in one line.

? What could be a general rule to multiply a number by 101 and write the product in one line? Extend this rule for multiplication by 1001, 10001, ...

? Use this to find (i) 89 × 101, (ii) 949 × 101, (iii) 265831 × 1001, (iv) 1111 × 1001, (v) 9734 × 99 and (vi) 23478 × 999.

Math Talk

Such methods of applying the distributive property to easily multiply two numbers were discussed extensively in the ancient mathematical works of Brahmagupta (628 CE), Sridharacharya (750 CE) and Bhaskaracharya (Lilavati, 1150 CE). In his work *Brahmasphuṭasiddhānta* (Verse 12.56), Brahmagupta refers to such methods for fast multiplication using the distributive property as **ista-gunana.**

© NCERT not to be republished

6.2 Special Cases of the Distributive Property

Square of the Sum/Difference of Two Numbers

? The area of a square of sidelength 60 units is 3600 sq. units (60^2) and that of a square of sidelength 5 units is 25 sq. units (5^2). Can we use this to find the area of a square of sidelength 65 units?

A square of sidelength 65 can be split into 4 regions as shown in the figure—a square of sidelength 60, a square of sidelength 5, and two rectangles of sidelengths 60 and 5. The area of the square of sidelength 65 is the sum of the areas of all its constituent parts. Can you find the areas of the four parts in the figure above?



We get

$65^2 = (60 + 5)^2 = 60^2 + 5^2 + 2 \times (60 \times 5)$.

$= 3600 + 25 + 600 = 4225$ sq. units.

Let us multiply $(60 + 5) \times (60 + 5)$ using the distributive property.

$(60 + 5) \times (60 + 5) = 60 \times 60 + 5 \times 60 + 60 \times 5 + 5 \times 5$

$= 60^2 + 2 \times (60 \times 5) + 5^2$.

? What if we write 65^2 as $(30 + 35)^2$ or $(52 + 13)^2$? Draw the figures and check the area that you get.

Let us look at the general expression for the square of sum of two numbers, $(a + b)^2$.



Using the distributive property, $(a+b)^2$ can be expanded as

$(a+b) \times (a+b) = a \times a + a \times b + b \times a + b \times b$

$= a^2 + 2ab + b^2$,

as we had already seen in Example 2.

Identity 1A $(a+b)^2 = a^2 + 2ab + b^2$

? If a and b are any two integers, is $(a + b)^2$ always greater than $a^2 + b^2$? If not, when is it greater?

Math Talk

? Use Identity 1A to find the values of 104^2, 37^2. (**Hint:** Decompose 104 and 37 into sums or differences of numbers whose squares are easy to compute.)

© NCERT not to be republished

? Use Identity 1A to write the expressions for the following.

(i) $(m + 3)^2$ (ii) $(6 + p)^2$

? Expand $(6x + 5)^2$.

Using the Distributive Property	Using the Identity
$(6x + 5)^2 = (6x + 5)(6x + 5)$ $= (6x \times 6x) + (5 \times 6x) + (6x \times 5) + 5 \times 5$ $= (6x)^2 + 2(6x \times 5) + 5^2$ $= 36x^2 + 60x + 25.$	$(6x + 5)^2 = (6x)^2 + 5^2 + 2 \times (6x \times 5)$ $= 36x^2 + 25 + 60x.$

If you have difficulty remembering or using the general rule, you can just apply the distributive property to multiply and get the desired result.

? Expand $(3j + 2k)^2$ using both the identity and by applying the distributive property.

? Can we use 60^2 (=3600) and 5^2 (=25) to find the value of $(60 - 5)^2$ or 55^2? Let us approach this through geometry by drawing a square of side length 55 sitting inside a square of sidelength 60.

Area of a square of sidelength 55 is $(60 - 5)^2 = 55^2$.



We can get the area of the square of sidelength 55 by taking the area of the square of sidelength 60 and removing the areas of the two rectangles of sidelengths 60 and 5, i.e., $60^2 - (60 \times 5) - (5 \times 60)$. By doing this, we remove the area of the small square of sidelength 5 twice. What can we do with this expression to get the actual area?

We can add back the area of the square of sidelength 5 to this expression. That way, we are only subtracting this area once.

© NCERT not to be republished

So,

$$(60 - 5)^2 = 60^2 - (60 \times 5) - (5 \times 60) + 5^2$$
$$= 3600 - 300 - 300 + 25$$
$$= 3025.$$

The area of the square of sidelength 55 is 3025 sq. units.

We have seen what $(a + b)^2$ gives when expanded. What is the expansion of $(a - b)^2$?

Using the distributive property,

$$(a - b)^2 = (a - b) \times (a - b)$$
$$= (a)^2 - ba - ab + (b)^2$$
$$= a^2 - 2ab + b^2.$$

? We can also use the expansion of $(a + b)^2$ to find the expansion of $(a - b)^2$. Think how.

Hint: $(a - b)^2 = (a + (-b))^2$.

We can now directly use the expansion of $(a + b)^2$.

$$(a + (-b)^2 = (a)^2 + (-b)^2 + 2 \times (a) \times (-b)$$

Identity 1B $(a - b)^2 = a^2 + b^2 - 2ab$

? Find the general expansion of $(a - b)^2$ using geometry, as we did for 55^2.

? Use the identity $(a - b)^2$ to find the values of (a) 99^2 and (b) 58^2.

? Expand the following using both Identity 1B and by applying the distributive property

(i) $(b - 6)^2$ (ii) $(-2a + 3)^2$ (iii) $(7y - \frac{3}{4z})^2$

Investigating Patterns

Pattern 1

Look at the following pattern.

$$2\,(2^2 + 1^2) = 3^2 + 1^2$$
$$2\,(3^2 + 1^2) = 4^2 + 2^2$$
$$2\,(6^2 + 5^2) = 11^2 + 1^2$$
$$2\,(5^2 + 3^2) = 8^2 + 2^2.$$

© NCERT not to be republished

? Take a pair of natural numbers. Calculate the sum of their squares. Can you write twice this sum as a sum of two squares?

Try this with other pairs of numbers. Have you figured out a pattern?

Notice that $2(5^2 + 6^2) = (6 + 5)^2 + (6 – 5)^2$.

? Do the identities below help in explaining the observed pattern?

$$(a + b)^2 = a^2 + 2ab + b^2$$

$$(a – b)^2 = a^2 – 2ab + b^2$$

$$(a + b)^2 + (a – b)^2 = (a^2 + 2ab + b^2) + (a^2 – 2ab + b^2)$$

Adding the like terms $a^2 + a^2 = 2a^2$, $b^2 + b^2 = 2b^2$ and $2ab – 2ab = 0$, we get

$$2(a^2 + b^2) = (a + b)^2 + (a – b)^2.$$

Pattern 2

? Here is a related pattern. Try to describe the pattern using algebra to determine if the pattern always holds.

$$9 \times 9 – 1 \times 1 = 10 \times 8$$

$$8 \times 8 – 6 \times 6 = 14 \times 2$$

$$7 \times 7 – 2 \times 2 = 9 \times 5$$

$$10 \times 10 – 4 \times 4 = 14 \times 6$$

The pattern here appears to be $a^2 – b^2 = (a + b) \times (a – b)$.

Is this a true identity? Using the distributive property, we get

$$(a + b) \times (a – b) = a^2 – ab + ba – a^2.$$

Adding the like terms, $ab + (–ab) = 0$, we see that indeed

Identity 1C $(a + b) \times (a – b) = a^2 – b^2$.

You had seen this identity earlier in Figure it Out 5 (i).

? Use Identity 1C to calculate 98×102, and 45×55.

? Show that $(a + b) \times (a – b) = a^2 – b^2$ geometrically.

Try This

© NCERT not to be republished

Hint:



Sridharacharya (750 CE) gave an interesting method to quickly compute the squares of numbers using Identity 1C! Consider the following modified form of this identity —

$$a^2 = (a + b)(a - b) + b^2$$

? Why is this identity true?

Now, for example, 31^2 can be found by taking $a = 31$ and $b = 1$.

$$31^2 = (31 + 1)(31 - 1) + 1^2$$
$$= 32 \times 30 + 1$$
$$= 961.$$

197^2 can be found by taking $a = 197$, and $b = 3$.

$$197^2 = (197 + 3)(197 - 3) + 3^2$$
$$= 200 \times 194 + 9$$
$$= 38809.$$

? Figure it Out

1. Which is greater: $(a - b)^2$ or $(b - a)^2$? Justify your answer.
2. Express 100 as the difference of two squares.
3. Find 406^2, 72^2, 145^2, 1097^2, and 124^2 using the identities you have learnt so far.
4. Do Patterns 1 and 2 hold only for counting numbers? Do they hold for negative integers as well? What about fractions? Justify your answer.

Math Talk

© NCERT not to be republished

6.3 Mind the Mistake, Mend the Mistake

We have expanded and simplified some algebraic expressions below to their simplest forms.

(i) Check each of the simplifications and see if there is a mistake.

(ii) If there is a mistake, try to explain what could have gone wrong.

(iii) Then write the correct expression.

1
$$-3p(-5p + 2q)$$
$$= -3p + 5p - 2q$$
$$= p - 2q$$

2
$$2(x - 1) + 3(x + 4)$$
$$= 2x - 1 + 3x + 4$$
$$= 5x + 3$$

3
$$y + 2(y + 2)$$
$$= (y + 2)^2$$
$$= y^2 + 4y + 4$$

4
$$(5m + 6n)^2$$
$$= 25m^2 + 36n^2$$

5
$$(-q + 2)^2$$
$$= q^2 - 4q + 4$$

6
$$3a(2b \times 3c)$$
$$= 6ab \times 9ac$$
$$= 54a2bc$$

7
$$\frac{1}{2}(10s - 6) + 3$$
$$= 5s - 3 + 3$$
$$= 5s$$

8
$$5w^2 + 6w$$
$$= 11w^2$$

9
$$2a^3 + 3a^3 + 6a^2b + 6ab^2$$
$$= 5a^3 + 12a^2b^2$$

10
$$(x + 2)(x + 5)$$
$$= (x + 2)x + (x + 2)5$$
$$= x^2 + 2x + 5x + 10$$
$$= x^2 + 7x + 10$$

11
$$(a + 2)(b + 4)$$
$$= ab + 8$$

12
$$ab^2 + a^2b + a^2b^2$$
$$= ab(a + b + ab)$$

6.4 This Way or That Way, All Ways Lead to the Bay

Observe the pattern in the figure below. Draw the next figure in the sequence. How many circles does it have? How many total circles are there in Step 10? Write an expression for the number of circles in Step k.

Math Talk



There are many ways of interpreting this pattern. Here are some possibilities:

© NCERT not to be republished

Method 1

Step 1 | Step 2 | Step 3 | Step 4 | ... | Step k



$2^2 - 1$
$= (1 + 1)^2 - 1$

$3^2 - 1$
$= (2 + 1)^2 - 1$

$4^2 - 1$
$= (3 + 1)^2 - 1$

$5^2 - 1$
$= (4 + 1)^2 - 1$ ... $(k + 1)^2 - 1$

Method 2

Step 1 | Step 2 | Step 3 | Step 4 | ... | Step k



$1 + 2 \times 1$
$= 1^2 + 2 \times 1$

$2^2 + 2 \times 2$
$= 2^2 + 2 \times 2$

$3^2 + 2 \times 3$
$= 3^2 + 2 \times 3$

$4^2 + 2 \times 4$
$= 4^2 + 2 \times 4$ ... $k^2 + 2 \times k$

Method 3

Step 1 | Step 2 | Step 3 | Step 4 | ... | Step k



$1 \times 2 + 1$
$= 1 \times (1 + 1) + 1$

$2 \times 3 + 2$
$= 2 \times (2 + 1) + 2$

$3 \times 4 + 3$
$= 3 \times (3 + 1) + 3$

$4 \times 5 + 4$
$= 4 \times (4 + 1) + 4$ ... $k \times (k + 1) + k$

© NCERT not to be republished

Method 4

Step 1 Step 2 Step 3 Step 4 ... Step k



1×3 2×4 3×5 4×6 ... $k \times (k+2)$

$= 1 \times (1 + 2)$ $= 2 \times (2 + 2)$ $= 3 \times (3 + 2)$ $= 4 \times (4 + 2)$

Does your method match any of these, or is it different? Each expression that we have identified appears different, but are they really different? Since they describe the same pattern, they should all be the same. Let us simplify each expression and find out.

$$(k+1)^2 - 1 = k^2 + 1 + 2k - 1 = k^2 + 2k$$

$$k^2 + 2 \times k = k^2 + 2k$$

$$k \times (k+1) + k = k^2 + k + k = k^2 + 2k$$

$$k \times (k+2) = k^2 + 2k$$

When carried out correctly, all methods lead to the same answer; $k^2 + 2k$. The expression $k^2 + 2k$ gives the number of circles at Step k of this pattern.

In Mathematics, there are often multiple ways of looking at a pattern, and different ways of approaching and solving the same problem. Finding such ways often requires a great deal of creativity and imagination! While one or two of the ways might be your favourite(s), it can be amusing and enriching to explore other ways as well.

? Use this formula to find the number of circles in Step 15.

? Consider the pattern made of square tiles in the picture below.

1 2 3



.....

© NCERT not to be republished

? How many square tiles are there in each figure?

? How many are there in Step 4 of the sequence? What about Step 10?

? Write an algebraic expression for the number of tiles in Step n. Share your methods with the class. Can you find more than one method to arrive at the answer?

Math Talk

? Find the area of the (interior) shaded region in the figure below. All four rectangles have the same dimensions.



Tadang's method:
The total region is a square of side $(m + n)$ with an area $(m + n)^2$.

Subtracting the area of four rectangles from the total area will give the area of the interior shaded region.
That is, $(m + n)^2 - 4mn$.

Yusuf's method:
The shaded region is a square with sidelength $(n - m)$. So, its area is $(n - m)^2$.

? By expanding both expressions,
check that $(m + n)^2 - 4mn = (n - m)^2$.

? Find out the area of the region with slanting lines in the figure. All three rectangles have the same dimensions (Fig. 1).



Fig. 1

Anusha's method:
Required area = Area (ABCD) – Area (EFGH)
Area of ABCD = x^2.
Area of EFGH = xy.
Required area = $x^2 - xy$.



Vaishnavi's method:

$$QS = y + x + y$$
$$= x + 2y.$$
$$\text{Area of PQSR} = x(x + 2y)$$

Required area = Area of PQSR – (area of the three rectangles)

$$= x(x + 2y) - 3xy.$$



© NCERT not to be republished

Aditya's method:
The required area is 2 times the area of JKLM.



$$JK = \frac{x-y}{2},\ KM = x$$

Area (JKML) = $x\left(\frac{x-y}{2}\right)$

Required area = 2 × Area of JKML

$= 2x\left(\frac{x-y}{2}\right)$

$= x(x-y)$.

? By expanding the expressions, verify that all three expressions are equivalent. If $x = 8$ and $y = 3$, find the area of the shaded region.

? Write an expression for the area of the dashed region in the figure below. Use more than one method to arrive at the answer. Substitute p = 6, $r = 3.5$, and $s = 9$, and calculate the area.

Math Talk



? Figure it Out

1. Compute these products using the suggested identity.
   (i) 46^2 using Identity 1A for $(a + b)^2$
   (ii) 397 × 403 using Identity 1C for $(a + b)(a - b)$
   (iii) 91^2 using Identity 1B for $(a - b)^2$
   (iv) 43 × 45 using Identity 1C for $(a + b)(a - b)$
2. Use either a suitable identity or the distributive property to find each of the following products.
   (i) $(p - 1)(p + 11)$
   (ii) $(3a - 9b)(3a + 9b)$
   (iii) $-(2y + 5)(3y + 4)$
   (iv) $(6x + 5y)^2$
   (v) $(2x - \frac{1}{2})^2$
   (vi) $(7p) \times (3r) \times (p + 2)$

© NCERT not to be republished

3. For each statement identify the appropriate algebraic expression(s).

   (i) Two more than a square number.

   $2 + s$ $\quad (s + 2)^2$ $\quad s^2 + 2$ $\quad s^2 + 4$ $\quad 2s^2$ $\quad 2^2s$

   (ii) The sum of the squares of two consecutive numbers

   $m^2 + n^2$ $\quad (m + n)^2$ $\quad m^2 + 1$ $\quad m^2 + (m + 1)^2$

   $m^2 + (m - 1)^2$ $\quad (m + (m + 1))^2$ $\quad (2m)^2 + (2m + 1)^2$

4. Consider any 2 by 2 square of numbers in a calendar, as shown in the figure.

February						
Su	**M**	**Tu**	**W**	**Th**	**F**	**Sa**
						1
2	3	4	5	6	7	8
9	10	11	12	13	14	15
16	17	18	19	20	21	22
23	24	25	26	27	28	

Find products of numbers lying along each diagonal — $4 \times 12 = 48$, $5 \times 11 = 55$. Do this for the other 2 by 2 squares. What do you observe about the diagonal products? Explain why this happens.



Hint: Label the numbers in each 2 by 2 square as

a	$(a + 1)$
$a + 7$	$(a + 8)$

5. Verify which of the following statements are true.

   (i) $(k + 1)(k + 2) - (k + 3)$ is always 2.

   (ii) $(2q + 1)(2q - 3)$ is a multiple of 4.

   (iii) Squares of even numbers are multiples of 4, and squares of odd numbers are 1 more than multiples of 8.

   (iv) $(6n + 2)^2 - (4n + 3)^2$ is 5 less than a square number.

6. A number leaves a remainder of 3 when divided by 7, and another number leaves a remainder of 5 when divided by 7. What is the remainder when their sum, difference, and product are divided by 7?

7. Choose three consecutive numbers, square the middle one, and subtract the product of the other two. Repeat the same with other

© NCERT not to be republished

sets of numbers. What pattern do you notice? How do we write this as an algebraic equation? Expand both sides of the equation to check that it is a true identity.

8. What is the algebraic expression describing the following steps—add any two numbers. Multiply this by half of the sum of the two numbers? Prove that this result will be half of the square of the sum of the two numbers.

9. Which is larger? Find out without fully computing the product.
   (i) 14×26 or 16×24
   (ii) 25×75 or 26×74

10. A tiny park is coming up in Dhauli. The plan is shown in the figure. The two square plots, each of area g^2 sq. ft., will have a green cover. All the remaining area is a walking path w ft. wide that needs to be tiled. Write an expression for the area that needs to be tiled.



11. For each pattern shown below,
   (i) Draw the next figure in the sequence.
   (ii) How many basic units are there in Step 10?
   (iii) Write an expression to describe the number of basic units in Step y.



© NCERT not to be republished

SUMMARY

- We extended the distributive property to find the product of two expressions each of which has two terms. The general form for the same is $(a + b) \times (c + d) = ac + ad + bc + bd$.
- We saw some special cases of this identity.
  - $(a + b)^2 = a^2 + 2ab + b^2$
  - $(a - b)^2 = a^2 - 2ab + b^2$
  - $(a + b)(a - b) = a^2 - b^2$.
- We considered different patterns, and explored how to understand them using algebra. We saw that, often, there are multiple ways to solve a problem and arrive at the same correct answer. Finding different methods to approach and solve the same problem is a creative process.

© NCERT not to be republished

Coin Conjoin

Arrange 10 coins in a triangle as shown in the figure below on the left. The task is to turn the triangle upside down by moving one coin at a time. How many moves are needed? What is the minimum number of moves?

A triangle of 3 coins can be inverted (turned upside down) with a single move, and a triangle of 6 coins can be inverted by moving 2 coins.

The 10-coin triangle can be flipped with just 3 moves; did you figure out how? Find out the minimum possible moves needed to flip the next bigger triangle having 15 coins. Try the same for bigger triangular numbers.

Is there a simple way to calculate the minimum number of coin moves needed for any such triangular arrangement?

© NCERT not to be republished

7 PROPORTIONAL REASONING-1

0874CH07

7.1 Observing Similarity in Change

We are all familiar with digital images. We often change the size and orientation of these images to suit our needs. Observe the set of images below—

Image A

Image B

Image C

Image D

Image E

We can see that all the images are of different sizes.

? Which images look similar and which ones look different?

Images (A, C, and D) look similar, even though they have different sizes.

© NCERT not to be republished

? Do images B and E look like the other three images?

No, they are slightly distorted. The tiger appears elongated in B, and compressed and fatter in E!

? Why?

You may notice that images A, C, and D are rectangular, but E is square. Maybe that is why E looks different. But B is also a rectangle! Why does it look different from the other rectangular images?

Math Talk

Can we observe any pattern to answer this question? Perhaps by measuring the rectangles?

Image	Width (in mm)	Height (in mm)
Image A	60	40
Image B	40	20
Image C	30	20
Image D	90	60
Image E	60	60

? What makes images A, C, and D appear similar, and B and E different?

When we compare image A with C, we notice that the width of C is half that of A. The height is also half of A. Both the width and height have **changed by the same factor** (through multiplication), $\frac{1}{2}$ in this case. Since the widths and heights have changed by the same factor, the **images look similar**.

When we compare image A with image B, we notice that the width of B is 20 millimetre (mm) less than that of A. The height too is 20 mm less than the height of A. Even though the difference (through subtraction) is the same, the images look different. Have the width and height changed by the same factor? The height of B is half the height of A. But the width of B is not half the width of A. Since the width and height have not changed by the same factor, the images look different.

? Can you check by what factors the width and height of image D change as compared to image A? Are the factors the same?

Images A, C, and D look similar because their widths and heights have changed by the same factor. We say that the changes to their widths and heights are **proportional.**

© NCERT not to be republished

7.2 Ratios

We use the notion of a **ratio** to represent such proportional relationships in mathematics.

We can say that the ratio of width to height of image A is

$$60 : 40.$$

The numbers 60 and 40 are called the **terms** of the ratio.

The ratio of width to height of image C is 30 : 20, and that of image D is 90 : 60.

> In a ratio of the form $a : b$, we can say that for every 'a' units of the first quantity, there are 'b' units of the second quantity.

So, in image A, we can say that for every 60 mm of width, there are 40 mm of height.

We can say that the ratios of width to height of images A, C, and D are proportional because the terms of these ratios change by the same factor. Let us see how.

Image A — 60 : 40

Multiplying both the terms by $\frac{1}{2}$, we get

$$60 \times \frac{1}{2} : 40 \times \frac{1}{2}$$

which is 30 : 20, the ratio of width to height in image C.

? By what factor should we multiply the ratio 60 : 40 (image A) to get 90 : 60 (image D)?

A more systematic way to compare whether the ratios are proportional is to reduce them to their **simplest form** and see if these simplest forms are the same.

7.3 Ratios in their Simplest Form

We can reduce ratios to their simplest form by dividing the terms by their HCF.

In image A, the terms are 60 and 40. What is the HCF of 60 and 40? It is 20. Dividing the terms by 20, we get the ratio of image A to be 3 : 2 in its simplest form.

The ratio of image D is 90 : 60. Dividing both terms by 30 (HCF of 90 and 60), we get the simplest form to be 3 : 2. So the ratios of images A and D are proportional as well.

What is the simplest form of the ratios of images B and E?
The ratio of image B is 40 : 20; in its simplest form, it is 2 : 1.
The ratio of image E is 60 : 60; in its simplest form, it is 1 : 1.

© NCERT not to be republished

These ratios are not the same as 3 : 2. So, we can say that the ratios of width to height of images B and E are not proportional to the ratios of images A, C, and D.

When two ratios are the same in their simplest forms, we say that the ratios are in **proportion**, or that the ratios are **proportional**. We use the '::' symbol to indicate that they are proportional.
So $a : b :: c : d$ indicates that the ratios $a : b$ and $c : d$ are proportional.

Thus,

60 : 40 :: 30 : 20 and 60 : 40 :: 90 : 60.

7.4 Problem Solving with Proportional Reasoning

Example 1: Are the ratios 3 : 4 and 72 : 96 proportional?

3 : 4 is already in its simplest form.

To find the simplest form of 72 : 96, we need to divide both terms by their HCF.

What is the HCF of 72 and 96?

The HCF of 72 and 96 is 24. Dividing both terms by 24, we get 3 : 4.
Since both ratios in their simplest form are the same, they are proportional.

Example 2: Kesang wanted to make lemonade for a celebration. She made 6 glasses of lemonade in a vessel and added 10 spoons of sugar to the drink. Her father expected more people to join the celebration. So he asked her to make 18 more glasses of lemonade.

To make the lemonade with the same sweetness, how many spoons of sugar should she add?

To maintain the same sweetness, the ratio of the number of glasses of lemonade to the number of spoons of sugar should be proportional. For 6 glasses of lemonade, she added 10 spoons of sugar.

The ratio of glasses of lemonade to spoons of sugar is 6 : 10. If she needs to make 18 more glasses of lemonade, how many spoons of sugar should she use? We can model this problem as —

6 : 10 :: 18 : ?

We know that each term in the ratio must change by the same factor, for the ratios to be proportional.

How can we find the factor of change in the ratio?

The first term has increased from 6 to 18. To find the factor of change, we can divide 18 by 6 to get 3.

© NCERT not to be republished

The second term should also change by the same factor. When 10 increases by a factor of 3, it becomes 30. Thus,

6 : 10 :: 18 : 30.

So, she should use 30 spoons of sugar to make 18 glasses of lemonade with the same sweetness as earlier.

Example 3: Nitin and Hari were constructing a compound wall around their house. Nitin was building the longer side, 60 ft in length, and Hari was building the shorter side, 40 ft in length. Nitin used 3 bags of cement but Hari used only 2 bags of cement. Nitin was worried that the wall Hari built would not be as strong as the wall he built because she used less cement.

Is Nitin correct in his thinking?

In Nitin and Hari's case, we should compare the ratio of the length of the wall to the bags of cement used by each of them and see whether they are proportional.

The ratio in Nitin's case is 60 : 3, i.e., 20 : 1 (in its simplest form).
The ratio in Hari's case is 40 : 2, i.e., 20 : 1 (in its simplest form).

Since both ratios are proportional, the walls are equally strong. Nitin should not worry!

Example 4: In my school, there are 5 teachers and 170 students. The ratio of teachers to students in my school is 5 : 170. Count the number of teachers and students in your school. What is the ratio of teachers to students in your school? Write it below.

_____ : _____

Is the teacher-to-student ratio in your school proportional to the one in my school?

Example 5: Measure the width and height (to the nearest cm) of the blackboard in your classroom. What is the ratio of width to height of the blackboard?

_____ : _____

Can you draw a rectangle in your notebook whose width and height are proportional to the ratio of the blackboard?

Compare the rectangle you have drawn to those drawn by your classmates. Do they all look the same?

Math Talk

Note to the Teacher: Give more such examples that students can relate to and ask them to give reasons why they think they are correct. Engaging with these problems and finding solutions through a process of **proportional reasoning** should go along with learning procedures and methods to solve the problems.

© NCERT not to be republished

Reprint 2026-27

Example 6: When Neelima was 3 years old, her mother's age was 10 times her age. What is the ratio of Neelima's age to her mother's age? What would be the ratio of their ages when Neelima is 12 years old? Would it remain the same?

The ratio of Neelima's age to her mother's age when Neelima is 3 years old is 3 : 30 (her mother's age is 10 times Neelima's age). In the simplest form, it is 1 : 10.

When Neelima is 12 years old (i.e., 9 years later), the ratio of their ages will be 12 : 39 (9 years later, her mother would be 39 years old). In the simplest form, it is 4 : 13.

When we add (or subtract) the same number from the terms of a ratio, the ratio changes and is not necessarily proportional to the original ratio.

Example 7: Fill in the missing numbers for the following ratios that are proportional to 14 : 21.

_____ : 42 6 : _____ 2 : _____

In the first ratio, we don't know the first term. But the second term is 42. It is 2 times the second term of the ratio 14 : 21. So, the first term should also be 2 times 14 (the first term). Hence the proportional ratio is 28 : 42.



For the second ratio, the first term is 6.

What factor should we multiply 14 by to get 6? Can it be an integer? Or should it be a fraction?

We can model this as $14y = 6$. So, $y = \frac{6}{14} = \frac{3}{7}$.

So, we need to multiply 21 (the second term of 14 : 21) also by the same factor $\frac{3}{7}$.

$21 \times \frac{3}{7}$ is 9. So, the ratio is 6 : 9.

In the third ratio, the first term is 2.

We can see that when we divide 14 (the first term of 14 : 21) by 7 (HCF of 14 and 21) we get 2.

If we divide 21 also by 7, we get 3. So, the ratio is 2 : 3.

Filter Coffee!

Filter coffee is a beverage made by mixing coffee decoction with milk. Manjunath usually mixes 15 mL of coffee decoction with 35 mL of milk to make one cup of filter coffee in his coffee shop.

In this case, we can say that the ratio of coffee decoction to milk is 15 : 35.

If customers want 'stronger' filter coffee, Manjunath mixes 20 mL of decoction with 30 mL of milk. The ratio here is 20 : 30.

© NCERT not to be republished

Why is this coffee stronger?

Math Talk

And when they want 'lighter' filter coffee, he mixes 10 mL of coffee and 40 mL of milk, making the ratio 10 : 40.

Why is this coffee lighter?

Math Talk

The following table shows the different ratios in which Manjunath mixes coffee decoction with milk. Write in the last column if the coffee is stronger or lighter than the regular coffee.

Coffee Decoction (in mL)	Milk (in mL)	Regular/Strong/ Light
300	600	
150	500	
200	400	
24	56	
100	300	

Figure it Out

1. Circle the following statements of proportion that are true.

   (i) 4 : 7 :: 12 : 21 (ii) 8 : 3 :: 24 : 6

   (iii) 7 : 12 :: 12 : 7 (iv) 21 : 6 :: 35 : 10

   (v) 12 : 18 :: 28 : 12 (vi) 24 : 8 :: 9 : 3

2. Give 3 ratios that are proportional to 4 : 9.

   _____ : _____ _____ : _____ _____ : _____

3. Fill in the missing numbers for these ratios that are proportional to 18 : 24.

   3 : _____ 12 : _____ 20 : _____ 27 : _____

© NCERT not to be republished

4. Look at the following rectangles. Which rectangles are similar to each other? You can verify this by measuring the width and height using a scale and comparing their ratios.



5. Look at the following rectangle. Can you draw a smaller rectangle and a bigger rectangle with the same width to height ratio in your notebooks? Compare your rectangles with your classmates' drawings.

Are all of them the same? If they are different from yours, can you think why? Are they wrong?

Math Talk

6. The following figure shows a small portion of a long brick wall with patterns made using coloured bricks. Each wall continues this pattern throughout the wall. What is the ratio of grey bricks to coloured bricks? Try to give the ratios in their simplest form.

(a)



(b)



© NCERT not to be republished

7. Let us draw some human figures. Measure your friend's body—the lengths of their head, torso, arms, and legs. Write the ratios as mentioned below—



head : torso

_____ : _____

torso : arms

_____ : _____

torso : legs

_____ : _____



Now, draw a figure with head, torso, arms, and legs with equivalent ratios as above.

? Does the drawing look more realistic if the ratios are proportional? Why? Why not?

Math Talk

Note to the Teacher: In all these activities, encourage students to reason why their drawings are proportional.

Trairasika—The Rule of Three

? **Example 8:** For the mid-day meal in a school with 120 students, the cook usually makes 15 kg of rice. On a rainy day, only 80 students came to school. How many kilograms of rice should the cook make so that the food is not wasted?

The ratio of the number of students to the amount of rice needs to be proportional.

So, 120 : 15 :: 80 : ?

? What is the factor of change in the first term?

We can find that by dividing the terms $\frac{80}{120} = \frac{2}{3}$.

The number of students is reduced by a factor of $\frac{2}{3}$.

On multiplying the weight of rice by the same factor, we get,

$$15 \times \frac{2}{3} = 10.$$

So, the cook should make 10 kg of rice on that day.

The situation above is a typical example of a problem where we need to use proportional reasoning to find a solution. Four quantities are

Reprint 2026-27

© NCERT not to be republished

linked proportionally, out of which three are known and we must find the fourth, unknown, quantity.

To solve such problems, we can model two proportional ratios using algebraic notation as —

$$a : b :: c : d.$$

For these two ratios to be proportional, we know that term c should be a multiple of term a by a factor, say f, and term d should be a multiple of term b by the same factor f. So,

$$c = fa \quad ...(1)$$

$$d = fb \quad ...(2)$$

From (1) and (2), we can say that,

$$f = \frac{c}{a} \text{ and } f = \frac{d}{b}.$$

$$\text{Therefore, } \frac{c}{a} = \frac{d}{b}.$$

Multiplying both sides by ab, we get,

$$ab \times \frac{c}{a} = ab \times \frac{d}{b}$$

$$\cancel{a}b \times \frac{c}{\cancel{a}} = a\cancel{b} \times \frac{d}{\cancel{b}}$$

$$bc = ad \text{ or } ad = bc$$

Thus, when $a : b :: c : d$, then $ad = bc$. This is known as cross multiplication of terms.

Since $ad = bc$, we can show that

$$d = \frac{bc}{a}.$$

Two ratios are proportional if their terms are equal when cross multiplied. The fourth unknown quantity can be found through such cross multiplication.

In ancient India, Āryabhaṭa (199 CE) and others called such problems of proportionality *Rule of Three* problems. There were 3 numbers given—the *pramāṇa* (measure—'a' in our case), the *phala* (fruit—'b' in our case), and the *ichchhā* (requisition—'c' in our case). To find the *ichchhāphala* (yield—'d' in our case), Āryabhaṭa says,

"Multiply the *phala* by the *ichchhā* and divide the resulting product by the *pramāṇa*."

In other words, Āryabhaṭa says,

"pramāṇa : phala :: ichchhā : ichchhāphala," therefore,

pramāṇa × *ichchhāphala* = *phala* × *ichchhā.*

© NCERT not to be republished

Thus,

$$ichchhāphala = \frac{phala \times ichchhā}{pramāṇa}.$$

Using the cross multiplication method proposed by Āryabhaṭa, ancient Indians solved complex problems that involved proportionality.

Example 9: A car travels 90 km in 150 minutes. If it continues at the same speed, what distance will it cover in 4 hours?

If it continues at the same speed, the ratio of the time taken should be proportional to the ratio of the distance covered.

$$150 : 90 :: 4 : ?$$

Is this the right way to formulate the question?

No, because 150 is in minutes, but 4 is in hours. The second ratio should use the same units for time as the first ratio. Since 4 hours is 240 minutes, the right form is

$$150 : 90 :: 240 : ?$$

How can you find the distance covered in 240 minutes?

Discuss with your classmates and find the answer using different strategies.

Note to the Teacher: Instead of giving one 'method' to solve the problem of the distance, encourage students to reason out the answer through different strategies. They can use their understanding of equivalent fractions and equivalent ratios to find the answer.

We can model this proportion as

$$150 : 90 :: 240 : x.$$

By cross multiplication, we get

$$150 \times x = 240 \times 90$$

Therefore,
$$x = \frac{240 \times 90}{150}.$$

$$= \frac{\cancel{240}^{48} \times \cancel{90}^{3}}{\cancel{150}_{5}_{1}} = 144.$$

The distance covered by the car in 4 hours is 144 km.

Example 10: A small farmer in Himachal Pradesh sells each 200 g packet of tea for ₹200. A large estate in Meghalaya sells each 1 kg packet of tea for ₹800. Are the weight-to-price ratios in both places proportional? Which tea is more expensive?

© NCERT not to be republished

The ratio of weight to price of the Himachal tea is 200 : 200.

What is the weight to price ratio of the Meghalaya tea? Is it 1 : 800? This would not be appropriate, because we considered the weight in grams in the case of Himachal. So, the weight to price ratio is 1000 : 800 in Meghalaya after we convert the weight to grams.

To check if the ratios are proportional, we need to see if both ratios are the same in their simplest forms.

The Himachal tea ratio in its simplest form is 1 : 1.

The Meghalaya tea ratio in its simplest form is 5 : 4.

So, the ratios are not proportional.

? Which tea is more expensive? Why?

Note to the Teacher: Encourage a discussion on the more expensive tea, how they came to their conclusions and what the reasons for that tea being more expensive could be.

To answer the question as to which tea is more expensive, we should compare the price of tea for the same weight in both places.

What is the price of 1 kg of tea from Meghalaya? It is ₹800.

In Himachal, if 200 g of tea costs rupees 200, what is the cost of 1 kg of tea?

Let us say that the price of 1 kg of tea is x rupees. 200 g is $\frac{1}{5}$ of 1 kg.

So, $\frac{1}{5} \times x = 200$.

Multiplying both sides by 5, we get

$$\frac{1}{5} \times x \times 5 = 200 \times 5$$

$$\frac{1}{\cancel{5}} \times x \times \cancel{5} = 1000$$

$$x = 1000.$$

So, the cost of 1 kg of tea is ₹800 in Meghalaya and ₹1,000 in Himachal Pradesh.

Therefore, the tea from Himachal Pradesh is more expensive.

Activity 1: Take your favourite dish. Find out all the ingredients and their respective quantities needed to make the dish for your family. Suppose you are celebrating a festival and you want to invite 15 guests. Find out the quantities of the ingredients required to cook the same dish for them.

? Figure it Out

1. The Earth travels approximately 940 million kilometres around the Sun in a year. How many kilometres will it travel in a week?

2. A mason is building a house in the shape shown in the diagram. He needs to construct both the outer walls and the inner wall that

© NCERT not to be republished

separates two rooms. To build a wall of 10-feet, he requires approximately 1450 bricks. How many bricks would he need to build the house? Assume all walls are of the same height and thickness.



? Puneeth's father went from Lucknow to Kanpur in 2 hours by riding his motorcycle at a speed of 50 km/h. If he drives at 75 km/h, how long will it take him to reach Kanpur? Can we form this problem as a proportion—

Math Talk

50 : 2 :: 75 : __

Would it take Puneeth's father more time or less time to reach Kanpur? Think about it.

Even though this problem looks similar to the previous problems, it cannot be solved using the Rule of Three!

The time of travel would actually decrease when the speed increases. So this problem cannot be modelled as 50 : 2 :: 75 : __.

? **Activity 2:** Go to the market and collect the prices of different sizes of shampoo containers of the same shampoo and create a table like the one given below. See if the volume of shampoo is proportional to the price.

Container	Volume	Price
Sachet	6 mL	₹2
Small Bottle	180 mL	₹154
Medium Bottle	340 mL	₹276
Large Bottle	1000 mL	₹540

© NCERT not to be republished

Let us compare the ratios for the sample table above.

The ratio of the volume of a sachet to a small bottle is 6 : 180. The ratio of their prices is 2 : 154. Are these ratios proportional?

? Why do you think that the ratio of the prices is not proportional to the ratio of the volumes?

Math Talk

Discuss the pros and cons of different size bottles for the company and for customers. For reducing ecological footprint, what would you recommend to the company and to the customer?
Does the same occur for other products?

Make similar tables for other products in the market, capturing different prices for different measures of the same product, e.g., rice or *atta* (flour).

Observe the products for which the prices are proportional to the different measures.

Discuss in class the proportionality of prices to measures of the same product.

Note to the Teacher: Give a project to students. Start by dividing the class into groups. Each group should go to one shop and collect prices for different measures of the same product. For example, they should note down the prices of 500 g of rice, 1 kg of rice, and 10 kg of rice. They should make tables with measure sizes and prices, and present them to the rest of the class. They should discuss if the prices are proportional or not, and why.

7.5 Sharing, but Not Equally!

? **Activity 3:** Form a pair. Collect 12 countable objects or counters (it can be coins, seeds, or pebbles). Now, share them between the two of you in different ways.

? If you divide them equally, what is the ratio of the number of counters with each of you?

Each of you will get 6 counters. So, the ratio is 6 : 6, or 1 : 1 in its simplest form.

Now let us not share equally.

? If your partner gets 5 counters, how many objects will you get? What is the ratio of the counters?

© NCERT not to be republished

The ratio of the counters of your partner to yours is 5 : 7.

? Now, if you want to share the counters between the two of you in the ratio of 3 : 1, how many counters would each of you get?

Share the counters in different ways and see which combination is in the ratio 3 : 1.

One way to share the counters in the ratio of 3 : 1 is as follows —

1. Your partner takes 3 counters and you take 1 counter. There are now 8 counters left.
2. Your partner takes 3 more counters and you take 1 more counter. There are now 4 counters left.
3. Your partner takes 3 more counters and you take 1 more counter. There are no more counters left.

So, your partner gets 9 counters in total and you get 3 counters.

When we divide 12 counters in the ratio of 3 : 1 between two people, one gets 9 counters and the other gets 3 counters.



? Now, if you want to share 42 counters between the two of you in the ratio of 4 : 3, how will you do it?

Using the same procedure would take a long time! There is a simpler way to share the whole with parts in a specified ratio.

You need to divide 42 into groups such that your partner gets 4 groups and you get 3 groups.

? What is the size of each group?

If your partner gets 4 groups and you get 3 groups, the total number of groups is 7. So, the size of each group is 42 ÷ 7 = 6.

Multiplying the number of groups by the size of each group, your partner gets 24 counters and you get 18 counters, when you share 42 counters in the ratio of 4 : 3.

© NCERT not to be republished

Reprint 2026-27



In general, when we want to divide a quantity, say x, in the ratio $m : n$, we do the following:

1. We need to split x into groups such that it can be divided into two parts where the first part has m groups and the second part has n groups.
2. But what is the size of each group? This can be found out by dividing x by the number of groups. The number of groups are $m + n$. So, the size of each group is $\frac{x}{m+n}$.
3. So, the first part has $m \times \frac{x}{m+n}$ objects and the second part has $n \times \frac{x}{m+n}$ objects.

Thus, if we want to divide a quantity x in the ratio of $m : n$, then the parts will be $m \times \frac{x}{m+n}$ and $n \times \frac{x}{m+n}$. We see that

$$m \times \frac{x}{m+n} : n \times \frac{x}{m+n} :: m : n.$$

Example 11: Prashanti and Bhuvan started a food cart business near their school. Prashanti invested ₹75,000 and Bhuvan invested ₹25,000. At the end of the first month, they gained a profit of ₹4,000. They decided that they would share the profit in the same ratio as that of their investment. What is each person's share of the profit?

The ratio of their investment is 75000 : 25000.
Reducing this ratio to its simplest form, we get 3 : 1.
3 + 1 is 4 and dividing the profit of 4000 by 4, we get 1000.
So, Prashanti's share is 3 × 1000 and Bhuvan's share is 1 × 1000.
So, Prashanti would get ₹3,000 and Bhuvan would get ₹1,000 of the profit.

Example 12: A mixture of 40 kg contains sand and cement in the ratio of 3 : 1. How much cement should be added to the mixture to make the ratio of sand to cement 5 : 2?

© NCERT not to be republished

Let us find the quantity of sand and cement in the original mixture.
The ratio is 3 : 1 and the total weight is 40 kg.

So, the weight of sand is $\frac{3}{(3+1)} \times 40 = 30$ kg.

The weight of cement is $\frac{1}{(3+1)} \times 40 = 10$ kg.

The weight of sand is the same in the new mixture. It remains 30. But the new ratio of sand to cement is 5 : 2. So the question is,

$$5 : 2 :: 30 : ?$$

If the ratio is 5 : 2, then the second term is $\frac{2}{5}$ times the first term. Since the new ratio is equivalent to 5 : 2, the second term in the new ratio should also be $\frac{2}{5}$ times of 30.

$$\frac{2}{5} \times 30 = 12.$$

The new mixture should have 12 kg of cement if the ratio of sand to cement is to be 5 : 2.

There is 10 kg of cement already. So, we need to add 2 kg of cement to the original mixture.

Figure it Out

1. Divide ₹4,500 into two parts in the ratio 2 : 3.
2. In a science lab, acid and water are mixed in the ratio of 1 : 5 to make a solution. In a bottle that has 240 mL of the solution, how much acid and water does the solution contain?
3. Blue and yellow paints are mixed in the ratio of 3 : 5 to produce green paint. To produce 40 mL of green paint, how much of these two colours are needed? To make the paint a lighter shade of green, I added 20 mL of yellow to the mixture. What is the new ratio of blue and yellow in the paint?
4. To make soft idlis, you need to mix rice and *urad dal* in the ratio of 2 : 1. If you need 6 cups of this mixture to make idlis tomorrow morning, how many cups of rice and *urad dal* will you need?
5. I have one bucket of orange paint that I made by mixing red and yellow paints in the ratio of 3 : 5. I added another bucket of yellow paint to this mixture. What is the ratio of red paint to yellow paint in the new mixture?

7.6 Unit Conversions

We have noticed earlier that solving problems with proportionality often requires us to convert units from one system to another. Here are

© NCERT not to be republished

a few important unit conversions for your reference.

Length

1 metre = 3.281 feet

Area

1 square metre = 10.764 square feet

1 acre = 43,560 square feet

1 hectare = 10,000 square metres

1 hectare = 2.471 acres

Volume

1 millilitre (mL) = 1 cubic centimetre (cc)

1 litre = 1,000 mL or 1,000 cc

Temperature

Temperature conversion between Fahrenheit and Celsius is a bit more complicated. $0^{\circ}C = 32^{\circ}F$, and

$$\text{Fahrenheit} = \frac{9}{5} \times \text{Celsius} + 32$$

and

$$\text{Celsius} = \frac{5}{9} \times (\text{Fahrenheit} - 32)$$

For example, $25^{\circ}C$ is $77^{\circ}F$.

Figure it Out

1. Anagh mixes 600 mL of orange juice with 900 mL of apple juice to make a fruit drink. Write the ratio of orange juice to apple juice in its simplest form.
2. Last year, we hired 3 buses for the school trip. We had a total of 162 students and teachers who went on that trip and all the buses were full. This year we have 204 students. How many buses will we need? Will all the buses be full?
3. The area of Delhi is 1,484 sq. km and the area of Mumbai is 550 sq. km. The population of Delhi is approximately 30 million and that of Mumbai is 20 million people. Which city is more crowded? Why do you say so?
4. A crane of height 155 cm has its neck and the rest of its body in the ratio 4 : 6. For your height, if your neck and the rest of the body also had this ratio, how tall would your neck be?
5. Let us try an ancient problem from Lilavati. At that time weights were measured in a unit named *palas* and *niskas* was a unit of money. "If $2\frac{1}{2}$ *palas* of saffron

© NCERT not to be republished

costs $\frac{3}{7}$ *niskas*, O expert businessman! tell me quickly what quantity of saffron can be bought for 9 *niskas*?"

6. Harmain is a 1-year-old girl. Her elder brother is 5 years old. What will be Harmain's age when the ratio of her age to her brother's age is 1 : 2?
7. The mass of equal volumes of gold and water are in the ratio 37 : 2. If 1 litre of water is 1 kg in mass, what is the mass of 1 litre of gold?
8. It is good farming practice to apply 10 tonnes of cow manure for 1 acre of land. A farmer is planning to grow tomatoes in a plot of size 200 ft by 500 ft. How much manure should he buy? (Please refer to the section on Unit Conversions earlier in this chapter).
9. A tap takes 15 seconds to fill a mug of water. The volume of the mug is 500 mL. How much time does the same tap take to fill a bucket of water if the bucket has a 10-litre capacity?
10. One acre of land costs ₹15,00,000. What is the cost of 2,400 square feet of the same land?
11. A tractor can plough the same area of a field 4 times faster than a pair of oxen. A farmer wants to plough his 20-acre field. A pair of oxen takes 6 hours to plough an acre of land. How much time would it take if the farmer used a pair of oxen to plough the field? How much time would it take him if he decides to use a tractor instead?
12. The ₹10 coin is an alloy of copper and nickel called 'cupro-nickel'. Copper and nickel are mixed in a 3 : 1 ratio to get this alloy. The mass of the coin is 7.74 grams. If the cost of copper is ₹906 per kg and the cost of nickel is ₹1,341 per kg, what is the cost of these metals in a ₹10 coin?

Try This

SUMMARY

- Ratios in the form of $a : b$ indicate that for every 'a' unit of the first quantity, there are 'b' units of the second quantity. 'a' and 'b' are the terms in the ratio.
- Two ratios—$a : b$ and $c : d$—are **proportional** (written $a : b :: c : d$) if their terms change by the same factor, i.e., if $ad = bc$.
- If x is divided into two parts in the ratio $m : n$, then the quantity of the first part is $m \times \frac{x}{m+n}$ and the quantity of the second part is $n \times \frac{x}{m+n}$.

© NCERT not to be republished

Binairo

Binairo, also known as Takuzu, is a logic puzzle with simple rules. Binairo is generally played on a square grid with no particular size. Some cells start out filled with two symbols: here horizontal and vertical lines. The rest of the cells are empty. The task is to fill cells in such a way that:

1. Each row and each column must contain an equal number of horizontal and vertical lines.
2. More than two horizontal or vertical lines can't be adjacent.
3. Each row is unique. Each column is unique.



Puzzle



Solution

Solve the following Binairo puzzles:







© NCERT not to be republished

Dot Grid

© NCERT not to be republished

Dot Grid

© NCERT not to be republished

1 FRACTIONS IN DISGUISE

0889CH01

1.1 Fractions as Percentages

You might have heard statements like, "Mega Sale — up to 50% off!" or "Hiya scored 83% in her board exams".

Do you know what the symbol '%' means?

This symbol is read as **per cent**.

The word 'per cent' is derived from the Latin phrase '*per centum*', meaning 'by the hundred' or 'out of hundred'.

So, 25 **per cent (25%)** means **25 out of every 100** — like 25 people out of 100, 25 rupees out of 100 rupees, or 25 marks out of 100 marks.

If we say **50% of some quantity *s***, it means

$$50\% = 50 \times \frac{1}{100} \times s \text{ (50 times the unit fraction of } s\text{)}$$
$$= \frac{50}{100} \times s = \frac{1}{2}s.$$

Thus, percentages are simply **fractions where the denominator is 100.** Examples:

$$20\% = \frac{20}{100} = \frac{2}{10} = \frac{1}{5},$$
$$33\% = \frac{33}{100}.$$

We saw that percentages are just fractions. Given any fraction, can we express it as a percentage? Yes, let us see how.

Expressing Fractions as Percentages

Example 1: Surya wants to use a deep orange colour to capture the sunset. He mixes some red paint and yellow paint to make this colour. The red paint makes up $\frac{3}{4}$ of this mixture. What percentage of the colour is made with red?

$\frac{3}{4}$ is 3 out of every 4.

That is, 6 out of every 8 (equivalent fraction).

That is, 30 out of every 40.

That is, 75 out of every 100.

This means 75%.

$$\frac{3}{4} = \frac{6}{8} = \frac{30}{40} = \frac{75}{100}$$

© NCERT not to be republished

Explaining this in a different way: To express $\frac{3}{4}$ as a percentage, we need to find its equivalent fraction with 100 as the denominator. Two ways of going ahead are shown below.

Method 1	Method 2
$\frac{3}{4} = \frac{3 \times 25}{4 \times 25}$	$\frac{3}{4} = \frac{x}{100}$.
$= \frac{75}{100} = 75\%$	$\frac{3}{4} \times 100 = \frac{x}{100} \times 100$
	[multiply both sides by 100]
	$x = \frac{3}{4} \times 100$
	$= 75$.

So, $\frac{3}{4}$ can be expressed as 75%.

Observe the following bar model diagram showing the equivalence between $\frac{3}{4}$ and 75%.



Can you tell what percentage of the colour was made using yellow?

Example 2: Surya won some prize money in a contest. He wants to save $\frac{2}{5}$ of the money to purchase a new canvas. Express this quantity as a percentage.

Try to understand the different methods for solving this problem, as shown below.

Method 1	Method 2
$\frac{2}{5} = \frac{20}{50} = \frac{40}{100}$	$\frac{2}{5} = \frac{x}{100}$.
$= 40\%$.	$x = \frac{2}{5} \times 100 = 40$.

© NCERT not to be republished

Try completing Method 3 by filling the boxes.

Method 3



Several problems in mathematics can be approached and solved in different ways. While the method you came up with may be dear to you, it can be amusing and enriching to know how others thought about it.

A fraction is of a unit, while a percentage is per 100. Therefore, to express a fraction as a percentage, we can just multiply the fraction by 100.

Example 3: Given a percentage, can you express it as a fraction? For example, express 24% as a fraction.

Since a percentage is a fraction, 24% is the same as $\frac{24}{100}$.

We can find other equivalent forms of $\frac{24}{100} = \frac{12}{50} = \frac{6}{25} = \frac{48}{200}$.

In general, we can say that a percentage, z%, can be expressed by any of the fractions that are equivalent to $\frac{z}{100}$.

Figure it Out

1. Express the following fractions as percentages.

   (i) $\frac{3}{5}$ (ii) $\frac{7}{14}$ (iii) $\frac{9}{20}$

   (iv) $\frac{72}{150}$ (v) $\frac{1}{3}$ (vi) $\frac{5}{11}$

2. Nandini has 25 marbles, of which 15 are white. What percentage of her marbles are white?

   (i) 10% (ii) 15% (iii) 25%

   (iv) 60% (v) 40% (vi) None of these

© NCERT not to be republished

3. In a school, 15 of the 80 students come to school by walking. What percentage of the students come by walking?

4. A group of friends is participating in a long-distance run. The positions of each of them after 15 minutes are shown in the following picture. Match (among the given options) what percentage of the race each of them has approximately completed.



5. Pairs of quantities are shown below. Identify and write appropriate symbols '>', '<', '=' in the blanks. Try to do it without calculations.

(i) 50% ____ 5%

(ii) $\frac{5}{10}$ ____ 50%

(iii) $\frac{3}{11}$ _____ 61%

(iv) 30% ____ $\frac{1}{3}$

? Well, if percentages are just a particular type of fraction, why do we need them? Why can't we just continue using fractions?

Let us consider an example.

A biscuit-making factory is experimenting with 2 new varieties of biscuits. Sugar makes up $\frac{9}{34}$ of Variety 1 and $\frac{13}{45}$ of Variety 2. Which variety is more sugary? It may not be clear at first glance and we may have to do some calculations. But, when the same information is presented as — Sugar makes up 26.47% of Variety 1 and 28.88% of Variety 2, it is immediately clear which variety is more sugary.

If we want to have the same denominator, why choose 100 in particular? Why not 10, 50, 1000, or 43? Think.

In principle, we could choose any number as the denominator. But with 100, there are some advantages. Since our number system is base 10, numbers like 10, 100, and 1000 fit easily with decimals. For example, 31% = $\frac{31}{100}$ = 0.31.

Converting between fractions, decimals, and percentages becomes quick and intuitive.

The number 100 is round, and easy to understand and work with. We could say "per 1000" or "per 100,000" (this usage is present in statistics like "per thousand people" or "per lakh"), but 100 hits the sweet spot — it's large enough to give detail, yet simple enough to grasp mentally. Per 10 would be too small for many purposes.

$\frac{9}{34}$ = 26.47 percent (per 100)

$\frac{9}{34}$ = 2.647 per decem (per 10)

$\frac{9}{34}$ = 264.7 per mille (per 1000)

© NCERT not to be republished

Long before the decimal fraction was introduced, the need for it was felt in computations by tenths, twentieths, and hundredths. The idea of 'per hundred' can be found as early as the 4th century BCE in Kautilya's *Arthaśhāstra,* "An interest of a *pana* and a quarter per month per cent is just. Five *panas* per month per cent is commercial interest. Ten *panas* per month per cent prevails among forests. Twenty *panas* per month per cent prevails among sea traders".

Around the same time, the Romans used taxes of $\frac{1}{20}, \frac{1}{100}$ in transactions related to trade and auctions. In the Italian manuscripts of the 15th century, expressions such as '*xx p* cento', '*x p* cento', '*vii p* cento' can be found (equivalent to our 20%, 10%, and 7%).

Percentages Around Us

Percentages are widely used in a variety of contexts. Here are some interesting findings that involve percentages.

The human body, on average, is about 60% water by weight.

Ice cream is about 30 – 50% air by volume.

45% of the world's population watched at least part of the 2022 FIFA World Cup.

Over 80% of the teenagers globally fail to meet the recommendation of at least one hour of daily physical actvity.



About 99.86% of the Solar System's mass is contained in the Sun.

An estimated 52% of the agricultural land worldwide is degraded.

© NCERT not to be republished

1.2 Percentage of Some Quantity

Example 1: Madhu and Madhav each ate biscuits of a different variety. Madhu's biscuits had 25% sugar, while Madhav's had 35% sugar. Can you tell who ate more sugar?

As we just saw, percentages represent fractional quantities or proportions. It would be inappropriate to compare just the percentages when they are referring to different quantities or wholes. That is, if they both had 100 g of biscuits, then clearly Madhav ate more sugar — 35 g (35% of 100 g is 35 g per 100 g) vs. Madhu's 25 g (25% of 100 g is 25 g per 100 g).

Suppose Madhu ate 120 g of biscuits and Madhav ate 95 g of biscuits. Who consumed more sugar? Try to find out.

We know that the weight of sugar is proportional to the weight of the biscuits consumed. Madhu ate 120 g of biscuits having 25% sugar. The amount of sugar he ate is the value in the blank—

$$25 : 100 :: ____ : 120.$$

A few ways of going forward are shown.

25% sugar means — 25 g sugar per 100 g of biscuits, which means 5 g sugar per 20 g biscuits, so 30 g sugar per 120 g biscuits.

The proportional relationship can be written as $\frac{25}{100} = \frac{s}{120}$.

$s = \frac{25}{100} \times 120 = 30$.



Do any of the methods match your thinking? Were you able to understand all the methods?

Now, let us find out how much sugar Madhav ate. He ate 95 g of biscuits with 35% sugar. Sometimes the numbers may not be convenient to calculate using different methods as we did just before.

100 g of the biscuits he ate has 35 g of sugar.

$\frac{35}{100} = \frac{x}{1} \rightarrow x = \frac{35}{100}$

This means, 1 g of the biscuits has $\frac{35}{100}$ g of sugar.

We can say that 95 g of the biscuit will have $\frac{35}{100}$ g × 95 = 33.25 g.

This can also be solved by finding the value of s in the proportional relationship $\frac{35}{100} = \frac{s}{95}$.

Therefore, Madhav ate more sugar.

© NCERT not to be republished

More generally, y% of some value, say 80, is given by $\frac{y}{100} \times 80$.
We can also say that 45% of some value, say z, is given by $\frac{45}{100} \times z$.

Free-hand Computations

We just calculated 25% of 120. Is 25% the same as $\frac{1}{4}$th (a quarter)?

Suppose we want to find 25% of 40. Is it the same as $\frac{1}{4}$th of 40?

Yes, since 25 is $\frac{1}{4}$th (a quarter) of 100 $\left(\frac{25}{100} = \frac{1}{4}\right)$.

Therefore 25% of 40 = $\frac{25}{100} \times 40$ is the same as $\frac{1}{4} \times 40$.

? Try to calculate (without using pen and paper) the indicated percentages of the values shown in the table below. Write your answers in the table.

	100	200	50	80	10	35	287
25%	25						
10%							
20%							
5%							

? How did you find these values? Discuss the methods with the class. Do you find anything interesting in the table?

Math Talk

You may have noticed that 20% of a value is double that of 10% of the same value. This will always happen as 20% (20 parts out of 100) is twice that of 10% (10 parts out of 100).

? Using this understanding, mentally calculate how much 40% of the values in the table above would be.

What relationship do you observe among 20%, 5% and 25% of a value?

It appears that (20% of y) + (5% of y) = 25% of y. We can verify that this property always holds:

$$\left(\frac{20}{100} \times y\right) + \left(\frac{5}{100} \times y\right) = \left(\frac{25}{100} \times y\right).$$

© NCERT not to be republished

Using this observation, mentally calculate how much 15% of the values in the table would be.

Suppose you have to mentally calculate the following percentages of some value: 75%, 90%, 70%, 55%. How would you do it? Discuss.

Math Talk

The FDP Trio — Fractions, Decimals, and Percentages

Example 2: We can find 50% of a value by multiplying $\frac{1}{2}$ with the value. Will multiplying the value by 0.5 also give the answer for 50% of the value?

Yes, since $\frac{1}{2} = 0.5$.

$$50\% = \frac{50}{100} = \frac{1}{2} = \frac{0.5}{1} = 0.5.$$

50% of 24 = 12
0.5 × 24 = 12

Similarly, to find 10% of a quantity, what decimal value should be multiplied?

Complete the following table:

Per cent	50%	100%	25%	75%	10%	1%	5%	43%
Fraction	$\frac{50}{100}$							
Decimal	0.5							

Activity: How Close Can You Get?

Make a pair. Each of you choose a number. Suppose, the numbers chosen are a and b. Share your numbers with each other. Both of you should estimate the percentage equivalent to the fraction $\frac{a}{b}$ (where $a < b$) and announce your answers by a fixed time, say, 5 seconds. The one whose estimate is the closest wins this round. Play this for 10 rounds.

Example 3: The maximum marks in a test are 75. If students score 80% or above in the test, they get an A grade. How much should Zubin score at least to get an A grade?

We can find 80% of 75 in different ways, using our understanding of fraction and decimal multiplication, as well as of proportionality.

© NCERT not to be republished

Fraction Multiplication → $\frac{80}{100} \times 75$

$= \frac{4}{5} \times 75 = 60.$

Decimal Multiplication → $0.8 \times 75 = 60.$

Proportional Reasoning →

Out of 100, the minimum mark is 80.

Out of 75, it is

$$\frac{75 \times 80}{100} = 60.$$



Example 4: To prepare a particular millet *kanji* (porridge), suppose the ratio of millet to water to be mixed for boiling is 2:7. What percentage does the millet constitute in this mixture? If 500 ml of the mixture is to be made, how much millet should be used?

This situation can be modelled as shown in the bar model on the right side.



The ratio of millet to the volume of the mixture is 2:9. In other words, in one unit of the mixture, millet occupies $\frac{2}{9}$ units and water occupies $\frac{7}{9}$ units.

Estimate first what percentage $\frac{2}{9}$ would be.



The percentage (i.e., in 100 such units) of millet in the mixture is

$$\frac{2}{9} \times 100 = 22.22\%.$$

The percentage of water in the mixture will be $100 - 22.22 = 77.78\%$.

A mixture with 22.22% millet means 100 ml mixture will have 22.22 ml millet. Therefore, 500 ml with 22.22% millet will have $5 \times 22.22 = 111.1$ ml of millet.

A given ratio can be converted to a fraction, and then to a percentage.

The practice of estimating first before calculating can improve number sense and help reduce mistakes. Often, we may not need exact values. The ability to make quick estimates is useful at these times.

Note to the Teacher: Incorporate the practice of estimating before calculating or solving as part of the problem-solving process. You may remind and encourage students as needed.

© NCERT not to be republished

Example 5: A cyclist cycles from Delhi to Agra and completes 40% of the journey. If he has covered 92 km, how many more kilometres does he have to travel to reach Agra?

Let us first try to model this situation by a bar model.



Estimate first before solving further.

A few ways of solving this problem are shown below. Does your method match any of the given ones? Do you like any of the other methods?

It is given that 40% of the distance is 92 km. We have to find out how much the rest of the 60% distance is.

Method 1

40% is 92 km, therefore 20% is 46 km.
This makes 60% to be 92 + 46 = 138 km.

Method 2

If 40% is 92, 60% is ?
40 : 92 :: 60: ?

$\frac{40}{92} = \frac{60}{r}$

(r is the remaining distance)

$r = 60 \times \frac{92}{40} = 138.$

Method 3

$\frac{40}{100} = \frac{92}{d}$

(d is the total distance)

$d = 92 \times \frac{100}{40} = 230.$

Remaining distance = 230 km – 92 km = 138 km.

Method 4

If x is the remaining distance then the total distance from Delhi to Agra is $x + 92$. Since, we know that 92 is 40% of this total distance,

$\frac{40}{100} \times (x + 92) = 92.$

$(x + 92) = 92 \times \frac{100}{40}$

$x = 230 - 92 = 138.$

Drawing rough diagrams can help understand the given situation better and make it easier to think further about the problem.

Percentages Greater than 100

Till now, we saw percentages with a value 100 or less than 100. Can there be percentages with a value more than 100? What could it mean when a percentage is greater than 100? Let us explore.

Example 6: Kishanlal recently opened a garment shop. He aims to achieve a daily sales of at least ₹5000. The sales on the first 2 days were ₹2000 and ₹3500. What percentage of his target did he achieve?

© NCERT not to be republished

The percentage target achieved is visualised below.



% of target:

$\frac{2000}{5000} \times 100 = 40\%$

$40\% = \frac{40}{100} = \frac{2}{5} = 0.4$



% of target:

$\frac{3500}{5000} \times 100 = 70\%$

$70\% = \frac{70}{100} = \frac{7}{10} = 0.7$

It is 40% on Day 1 and 70% on Day 2.

Another way of saying it is — he was 60% short of his target on Day 1 and 30% short of his target on Day 2.

? In the next two days, he made ₹5000 and ₹6000 respectively. What percentage of his target are these values?

His target is ₹5000, and he made ₹5000 on Day 3 — this is 100%. On Day 4, he made ₹6000, which is 1000 more than his target.

? What percentage of the target was achieved on Day 4?



% of target:

$\frac{5000}{5000} \times 100 = 100\%$

$100\% = \frac{100}{100} = \frac{1}{1} = 1.0$



% of target:

$\frac{6000}{5000} \times 100 = 120\%$

$120\% = \frac{120}{100} = \frac{6}{5} = 1.2$

1000 is 20% of 5000. Therefore, 6000, (5000 + 1000) is 100% + 20% = 120% of 5000. It can also be computed as $\frac{6000}{5000} \times 100 = \frac{6}{5} \times 100 = 120\%$. This means he achieved 120% of his target, i.e., 20% more than his target.

? On Days 5 and 6 his sales were ₹7800 and ₹9550 respectively. Calculate the percentage of the target achieved on these days.





© NCERT not to be republished

On Day 7, he achieved 150% of his target. On Day 8, he achieved 210% of his target. Find the sales made on these days.

Suppose on some day, he made ₹2500. This can be expressed as "He achieved $\frac{1}{2}$ of his target" or "He achieved 50% of his target" or "He achieved 0.5 of his target". On some other day, he made ₹10,000. We can say "He achieved twice/double/2 times his target" or "He achieved 200% of his target".

Complete the table below. Mark the approximate locations in the following diagram.

Percent	90%	110%	200%	250%	15%	173%	358%	28.9%	305%
Fraction									
Decimal									



Example 7: A farmer harvested 260 kg of wheat last year. This year, they harvested 650 kg of wheat. What percentage of last year's harvest is this year's harvest?

This year's harvest = $\frac{650}{260} \times 100 = 250\%$ of last year's harvest.
250% indicates that it is 2.5 times the original value.

Figure it Out

Estimate first before making any computations to solve the following questions. Try different methods including mental computations.

1. Find the missing numbers. The first problem has been worked out.



© NCERT not to be republished

(iii)

2. Find the value of the following and also draw their bar models.
   (i) 25% of 160 (ii) 16% of 250 (iii) 62% of 360
   (iv) 140% of 40 (v) 1% of 1 hour (vi) 7% of 10 kg
3. Surya made 60 ml of deep orange paint, how much red paint did he use if red paint made up $\frac{3}{4}$ of the deep orange paint?
4. Pairs of quantities are shown below. Identify and write appropriate symbols '>', '<', '=' in the boxes. Visualising or estimating can help. Compute only if necessary or for verification.
   (i) 50% of 510 ☐ 50% of 515 (ii) 37% of 148 ☐ 73% of 148
   (iii) 29% of 43 ☐ 92% of 110 (iv) 30% of 40 ☐ 40% of 50
   (v) 45% of 200 ☐ 10% of 490 (vi) 30% of 80 ☐ 24% of 64
5. Fill in the blanks appropriately:
   (i) 30% of k is 70, 60% of k is _____, 90% of k is _____, 120% of k is _____.
   (ii) 100% of m is 215, 10% of m is _____, 1% of m is _____, 6% of m is _____.
   (iii) 90% of n is 270, 9% of n is _____, 18% of n is _____, 100% of n is _____.
   (iv) Make 2 more such questions and challenge your peers.
6. Fill in the blanks:
   (i) 3 is ____ % of 300.
   (ii) _____ is 40% of 4.
   (iii) 40 is 80% of _____.
7. Is 10% of a day longer than 1% of a week? Create such questions and challenge your peers.
8. Mariam's farm has a peculiar bull. One day she gave the bull 2 units of fodder and the bull ate 1 unit. The next day, she gave the bull 3 units of fodder and the bull ate 2 units. The day after, she gave the bull 4 units and the bull ate 3 units. This continued, and on the 99th day she gave the bull 100 units and the bull ate 99 units. Represent these quantities as percentages. This task can be distributed among the class. What do you observe?

Math Talk

© NCERT not to be republished

9. Workers in a coffee plantation take 18 days to pick coffee berries in 20% of the plantation. How many days will they take to complete the picking work for the entire plantation, assuming the rate of work stays the same? Why is this assumption necessary?

10. The badminton coach has planned the training sessions such that the ratio of warm up : play : cool down is 10% : 80% : 10%. If he wants to conduct a training of 90 minutes. How long should each activity be done?

11. An estimated 90% of the world's population lives in the Northern Hemisphere. Find the (approximate) number of people living in the Northern Hemisphere based on this year's worldwide population.

12. A recipe for the dish, *halwa,* for 4 people has the following ingredients in the given proportions — *Rava*: 40%, Sugar: 40%, and *Ghee*: 20%.

    (i) If you want to make *halwa* for 8 people, what is the proportion of each of the above ingredients?

    (ii) If the total weight of the ingredients is 2 kg, how much *rava,* sugar and *ghee* are present?

1.3 Using Percentages

To Compare Proportions

Example 1: Eesha scored 42 marks out of 50 on an English test and 70 marks out of 80 in a Science test. Since she lost only 8 marks in English but 10 marks in Science, she thinks she has done better at English. Reema does not agree! She argues that since Eesha has scored more marks in Science, she has done better at Science. Vishu thinks we cannot compare the scores because the maximum marks are different. Who do you think is correct?

If the maximum marks are the same, the comparison becomes easier, isn't it? For these kinds of comparisons, we need to convert both values to percentages.

English score as a percentage = $\frac{42}{50} \times 100 = 84\%$

Science score as a percentage = $\frac{70}{80} \times 100 = 87.5\%$.

The Science score (as a percentage) is higher than the English score (as a percentage). So, we can conclude that Eesha has scored better on the Science test.

© NCERT not to be republished

Know Your Contents (KYC)

Example 2: Madhu and Madhav recently learnt about the importance of reading labels on processed food before purchase. They are at a shop to buy badam drink mix. They are looking at two products and wondering which has a larger share of badam. Can you figure it out? Which product uses a smaller proportion of food chemicals?



It is easier to compare the proportions of the ingredients if we convert them into percentages. For example,

DEF's sugar content as a percentage of total weight = $\frac{99}{150} \times 100 = 66\%$.

Complete this table by calculating the percentages to answer the questions:

	Sugar	Milk Solids	Badam Powder	Food Chemicals
DEF	66%			
Zacni				

Check if the percentages of each product add up to 100.

Percentage Increase or Decrease

Percentages are often used to describe the rate of change of quantities. For example,

1. Suppose the price of 1 kg tomatoes 3 years ago was ₹30, and the price now is ₹42. The increase in the price is ₹12.

$$\textit{Percentage increase} = \frac{\textit{amount of increase}}{\textit{original amount or base}} \times 100$$

$$= \frac{12}{30} \times 100 = 40\%.$$

We say the price of tomatoes increased by 40% over the last 3 years.

© NCERT not to be republished

2. The average footfall in this theater before COVID was 160. Now it is just 100. The decrease in the footfall is 60.

$$\text{Percentage decrease} = \frac{\text{amount of decrease}}{\text{original amount or base}} \times 100$$

$$= \frac{60}{160} \times 100 = 37.5\%.$$

We say the footfall in this theater post-COVID has decreased by 37.5%.

Example 3: Do the following two statements mean the same thing?

(i) The population of this state in 1991 is 165% of that in 1961.

(ii) The population of this state has increased by 65% from 1961 to 1991.

Yes, both mean the same. Suppose p is the population of the state in 1961 and q is the population of the state in 1991.

Statement A implies,	Statement B implies,
q = 165% of p	$q = p$ + 65% of p
$q = \frac{165}{100} \times p = 1.65p$	$q = p + 0.65 \times p = 1.65p$

In other words, the population of the state in 1991 is 1.65 times that in 1961.

Profit and Loss

You may have the experience of buying something — snacks, groceries, clothes, toys, etc. Very often, the shopkeeper quotes a price and after some bargaining the customer pays the negotiated amount and buys the item(*s*). We call the price quoted by the shopkeeper the **marked price** (sometimes this can be the MRP of an item). The price the customer pays after a discount is called the **selling price**. Also, the price the shopkeeper paid to purchase that item is called the **cost price**. Let us see how these labels are relative to the context through an example.

The picture below shows the journey of a sweater from the manufacturer to the customer and what the cost price (CP), the marked price (MP), and the selling price (SP) mean in each step.



© NCERT not to be republished

Kishanlal (retailer) buys sweaters from a wholesaler at a price of ₹300 per sweater. The marked price he quotes his customers is ₹480. After bargaining, he sells this sweater at ₹430. Notice that the selling price is greater than the cost price, resulting in a profit of ₹430 – ₹300 = ₹130. If the selling price is less than the cost price, it will result in a loss.

Example 4: Find out the percentage profit Kishanlal made on this sweater.

We shall consider the cost price to be 100% to find out the percentage profit made with reference to the cost price. The following rough diagram describes this situation.



The profit amount is ₹130.

The percentage profit is $\frac{130}{300} \times 100 = 43.3\%$.

Find the profit percentage of the wholesaler and the manufacturer.

Shambhavi owns a stationery shop. She procures 200 page notebooks at ₹36 per book. She sells them with a profit margin of 20%. Find the selling price.

She sells crayon boxes at ₹50 per box with a profit margin of 25%. How much did Shambhavi buy them from the wholesaler?

Example 5: The rice stock in Raghu's provision store is getting old. He had purchased the rice at ₹35 per kg. To clear his stock, he sells 10 kg rice for ₹300. Find out the percentage loss.

The amount Raghu had paid towards buying the 10 kg rice is ₹350. He sold it for ₹300.



The loss is ₹350 – ₹300 = ₹50.

The percentage loss is $\frac{50}{350} \times 100 = 14.28\%$.

Could we have just calculated the loss percentage per kg instead? Would it be the same?

Example 6: Shyamala had procured decorative vases at ₹2650 per piece. One of the pieces was slightly damaged. She decides to sell it at a loss of 18%. How much will she get by selling this piece?

Try making an estimate. Draw a rough diagram depicting the given situation.

© NCERT not to be republished

Two methods of solving this are shown.

With respect to the buying price being 100%, the selling price is 18% less than the buying price. That is, the selling price would be 82%.
82% of 2650 = 0.82 × 2650 = 2173.

The loss amount is 18% of 2650.
That is, $\frac{18}{100} \times 2650 = 477$.
Reducing this from the buying price, 2650 – 477 = 2173.

The sale amount of the damaged vase would be ₹2173.

? Due to heavy rains, Snehal could not transport strawberries to Hyderabad from his farm in Panchgani. He sells some of his stock at ₹80 per kg with a 12% loss. What is the cost price?

You have probably seen percentages mentioned when shops offer discounts! Do you know what 30% off (or 30% discount) means? It means that the shop is willing to reduce the price of the item by 30%.

? A utensil store is offering a 35% discount on the cooker with an MRP ₹1800. What is the selling price? If the cost price was ₹900, what is the percentage profit made after the sale?

Suppose Kishanlal achieved a sales of ₹80,000 last month. Out of this, the amount he spent on buying these goods he sold last month was ₹48,000. The difference amount, ₹80,000 – ₹48,000 = ₹32,000, is called **gross profit.**

After deducting the other expenses he incurred (such as transport cost, employee's salary, electricity bill, etc.) amounting to ₹8,000, the amount remaining is called **net profit**, which is ₹32,000 – ₹8,000 = ₹24,000.

Note: In this chapter, the term profit refers to gross profit.

Manisha sells fertiliser. She buys 50 kg bags at ₹500 per bag. She sells it at ₹750 per bag making a profit of $\frac{250}{500} \times 100 = 50\%$.
Although, with respect to the ₹750 amount she has earned by selling a bag, the profit percentage is $\frac{250}{750} \times 100 = 33.33\%$.

Profit percentage is calculated based on the price the goods bought when we want to know "How much profit did I make compared to what I invested in buying the goods?".



© NCERT not to be republished

Profit percentage is calculated based on the revenue (sales amount) when we want to know "How much (net) profit did I make on my overall revenue?".

Suppose, in a month she made sales of ₹1,50,000. The cost of buying the goods was ₹1,00,000. So, the gross profit is ₹50,000. The monthly expenses amounted to ₹5,000. The net profit is ₹45,000. Out of monthly revenue (₹1,50,000), the net profit percentage is $\frac{45000}{150000} \times 100 = \frac{3}{10} \times 100 = 30\%$.

Taxes

Tax rates, like the GST (Goods and Services Tax) rate or the Income Tax rates, are also specified as percentages. You may have noticed GST mentioned as part of bills. This means that the tax is part of the amount we pay and this amount goes to the government.



XY ELECTRICALS
SALES RECEIPT

Date:			06/07/2025
Item	Qty.	Price.	Amount
CFL Bulb	3	₹150.00	₹450.00
		Sub Total	₹450.00
		CGST 9%	₹40.50
		SGST 9%	₹40.50
TOTAL			₹531.00

THANK YOU

? Check if the calculations are correct in the bill shown.

? You may share any bills you have at home with the class. Observe the different elements present in the bills. Are there any similarities or differences in these bills?

Try This

? Figure it Out

1. If a shopkeeper buys a geometry box for ₹75 and sells it for ₹110, what is his profit margin with respect to the cost?
2. I am a carpenter and I make chairs. The cost of materials for a chair is ₹475 and I want to have a profit margin of 50%. At what price should I sell a chair?
3. The total sales of a company (also called revenue) was ₹2.5 crore last year. They had a healthy profit margin of 25%. What was the total expenditure (costs) of the company last year?
4. A clothing shop offers a 25% discount on all shirts. If the original price of a shirt is ₹300, how much will Anwar have to pay to buy this shirt?
5. The petrol price in 2015 was ₹60 and ₹100 in 2025. What is the percentage increase in the price of petrol?

(i) 50% (ii) 40% (iii) 60%
(iv) 66.66% (v) 140% (vi) 160.66%

© NCERT not to be republished

3. Samson bought a car for ₹4,40,000 after getting a 15% discount from the car dealer. What was the original price of the car?

4. 1600 people voted in an election and the winner got 500 votes. What percent of the total votes did the winner get? Can you guess the minimum number of candidates who stood for the election?

5. The price of 1 kg of rice was ₹38 in 2024. It is ₹42 in 2025. What is the rate of inflation? (Inflation is the percentage increase in prices.)

6. A number increased by 20% becomes 90. What is the number?

7. A milkman sold two buffaloes for ₹80,000 each. On one of them, he made a profit of 5% and on the other a loss of 10%. Find his overall profit or loss.

8. The population of elephants in a national park increased by 5% in the last decade. If the population of the elephants last decade is p, the population now is

   (i) $p \times 0.5$ (ii) $p \times 0.05$ (iii) $p \times 1.5$

   (iv) $p \times 1.05$ (v) $p + 1.50$

9. Which of the following statement(s) mean the same as — "The demand for cameras has fallen by 85% in the last decade"?

   (i) The demand now is 85% of the demand a decade ago.

   (ii) The demand a decade ago was 85% of the demand now.

   (iii) The demand now is 15% of the demand a decade ago.

   (iv) The demand a decade ago was 15% of the demand now.

   (v) The demand a decade ago was 185% of the demand now.

   (vi) The demand now is 185% of the demand a decade ago.

Growth and Compounding

You might have come across statements like, "1 year interest for FD (Fixed Deposit) in the bank @ 6% per annum" or "Savings account with interest @ 2.5% per annum". **Interest** is the extra money paid by institutions like banks or post offices on money deposited (kept) with them. Interest is also paid by people or institutions when they borrow money.

In a Fixed Deposit (FD), you deposit a specific amount of money for a fixed period at a predetermined interest rate. The money remains locked for the chosen duration, and the bank pays you interest on it. You cannot withdraw the amount before the maturity date without incurring a penalty. At the end of the term, you receive both your original deposit and the interest earned.

© NCERT not to be republished

For example, a bank says that the interest rate for fixed deposits is 10% p.a. What do you understand by this statement? What is the 'p.a.' next to the percentage?

'p.a.' is the short form of per annum, which means for every year. The specified interest rate indicates that if you invest ₹6000 as a deposit for a year with the bank, they will give you ₹600 as interest on this deposit. The 10% is the **rate of interest** and the ₹6000 on which the interest is calculated is the **principal**. The amount after 1 year in your bank account will be

$$6000 + (0.10 \times 6000)$$

(principal) + (10% interest on principal)

$$= 6000 + 600 = 6600.$$



In other words, the amount deposited, ₹6000, will become 110% (or increase by 10%),

$$6000 \times 110\% = 6000 \times \frac{110}{100} = 6000 \times 1.1 = 6600.$$

This can also be expressed as

Amount after 1 year = Principal (P) + rate of interest (r) of P

Example 7: If one deposits ₹6000 in the bank, what is the amount after 3 years?

That depends on the choice of FD. There are two possibilities:

1. Option 1: The interest is paid out regularly (for example, every year). The principal amount is returned after the maturity period.

		Interest returned (10% p.a.)	Amount in the FD
Year 1	Beginning		₹6000
	Ending	₹600 returned	₹6000
Year 2	Beginning		₹6000
	Ending	₹600 returned	₹6000
Year 3	Beginning		₹6000
	Ending	₹600 returned	₹6000
Total amount received		₹1800 + ₹6000 = ₹7800	

© NCERT not to be republished

2. Option 2: The interest gained every time (say after each year) is added back to the FD, thus increasing the principal amount for the subsequent period. After the maturity period, the entire amount is returned. This phenomenon is called **compounding.**

		Interest added back (10% p.a.)	Amount in the FD
Year 1	Beginning		₹6000
	Ending	₹600 added back	₹6600
Year 2	Beginning		₹6600
	Ending	₹660 added back	₹7260
Year 3	Beginning		₹7260
	Ending	₹726	₹7986
		₹7986 is returned	
Total amount received		₹7986	

× 0.10 × 1.10 × 0.10 × 1.10 × 0.10 × 1.10

We can see that with compounding, the final amount is more.

Example 8: What percent is the total amount received with respect to the amount deposited in both the options?

This can be calculated by finding $\frac{\textit{total amount received}}{\textit{amount deposited}} \times 100$.

Without Compounding	**With Compounding**
$\frac{7800}{6000} \times 100 = 130\% = 1.3$.	$\frac{7986}{6000} \times 100 = 133.1\% = 1.331$.
In other words, the total amount received = $6000 \times (1 + 0.1 + 0.1 + 0.1)$ = 6000×1.3.	In other words, the total amount received = $6000 \times 1.1 \times 1.1 \times 1.1$. = 6000×1.331
The percentage gain over 3 years is 30%.	The percentage gain over 3 years is 33.1%.

Figure it Out

1. Bank of Yahapur offers an interest of 10% p.a. Compare how much one gets if they deposit ₹20,000 for a period of 2 years with compounding and without compounding annually.

© NCERT not to be republished

2. Bank of Wahapur offers an interest of 5% p.a. Compare how much one gets if one deposits ₹20,000 for a period of 4 years with compounding and without compounding annually.

3. Do you observe anything interesting in the solutions of the two questions above? Share and discuss.

Let us try to generalise the pattern observed in each of the options.

Example 9: What is the amount we get back if we invest ₹6000 at an interest rate of 10% p.a. for '*t*' years?

No Compounding

Here, the interest gained every term is paid back. Therefore, the principal amount for every term shall remain the same, and as a result, the interest gained every term also shall be the same.

The interest gained in 1 term is 6000×0.1
The interest gained in 3 terms is
$6000 \times 0.1 \times 3$
The total amount at the end of an FD of 3 years is
$6000 + (6000 \times 0.1 \times 3)$.

The interest gained in 1 term is $p \times r$
(p is the principal, r is the rate of interest in percentage)
The interest gained in t terms is
$p \times r \times t$
The total amount at the end of an FD of t years is
$p + (p \times r \times t) = p + prt$
$= p\,(1 + rt)$.

With Compounding

Here, the interest gained every term/year is added back to the FD. Therefore, the principal amount increases after every term, and as a result, the interest gained every term also increases proportionately.

The total amount in the FD after Year 1 is
$(6000) \times 1.1$
(principal for Year 1)
The total amount in the FD after Year 2 is
$(6000 \times 1.1) \times 1.1$
(principal for Year 2)
The total amount in the FD after Year 3 is
$(6000 \times 1.1 \times 1.1) \times 1.1$
(principal for Year 3)
The total amount in the FD after t years is
$6000 \times (1.1 \times 1.1 \times 1.1 \ldots\ldots \times 1.1)$
t times
$6000 \times (1.1)^t$.

The total amount in the FD after Year 1 is
$(p) \times (1 + r)$
(principal for Year 1)
The total amount in the FD after Year 2 is
$p \times (1 + r) \times (1 + r)$
(principal for Year 2)
The total amount in the FD after Year 3 is
$p \times (1 + r) \times (1 + r) \times (1 + r)$
(principal for Year 3)
The total amount in the FD after t years is
$p \times (1 + r) \times (1 + r) \times \ldots\ldots \times (1 + r)$
t times
$p \times (1 + r)^t$.

© NCERT not to be republished

Suppose we want to know the expression/formula to find the total interest amount gained at the end of the maturity period. What would be the formula for each of the two options?

Math Talk

Figure it Out

4. Jasmine invests amount 'p' for 4 years at an interest of 6% p.a. Which of the following expression(s) describe the total amount she will get after 4 years when compounding is not done?

   (i) $p \times 6 \times 4$ (ii) $p \times 0.6 \times 4$ (iii) $p \times \frac{0.6}{100} \times 4$

   (iv) $p \times \frac{0.06}{100} \times 4$ (v) $p \times 1.6 \times 4$ (vi) $p \times 1.06 \times 4$

   (vii) $p + (p \times 0.06 \times 4)$

5. The post office offers an interest of 7% p.a. How much interest would one get if one invests ₹50,000 for 3 years without compounding? How much more would one get if it was compounded?

6. Giridhar borrows a loan of ₹12,500 at 12% per annum for 3 years without compounding and Raghava borrows the same amount for the same time period at 10% per annum, compounded annually. Who pays more interest and by how much?

7. Consider an amount ₹1000. If this grows at 10% p.a., how long will it take to double when compounding is done vs. when compounding is not done? Is compounding an example of exponential growth and not-compounding an example of linear growth?

Math Talk

8. The population of a city is rising by about 3% every year. If the current population is 1.5 crore, what is the expected population after 3 years?

9. In a laboratory, the number of bacteria in a certain experiment increases at the rate of 2.5% per hour. Find the number of bacteria at the end of 2 hours if the initial count is 5,06,000.

Decline

Several items or materials lose financial value over time. Suppose someone buys a bike at your home for ₹1,00,000 and after a few years they want to sell it. The value of the bike at that time will be less than ₹1,00,000. It could depend on various factors, including how many years have passed since the purchase, how many kilometres the vehicle has been used for, if there has been any damage, or if any parts have been replaced. This is called **depreciation** — reduction of value due to use and age of the item.

© NCERT not to be republished

Example 10: A TV is bought at a price of ₹21,000. After 1 year, the value of the TV depreciates by 5%. Find the value of the TV after one year.

The amount of reduction in the value is 5% of 21,000 = 0.05 × 21,000
= 1050.
The current value is 21,000 – 1050
= 19,950.

The value of the TV after 1 year will be 95% of the current value
= 95% of 21,000 = 0.95 × 21,000
= 19,950.

The value of the TV after 1 year will be ₹19,950.

Example 11: The population of a village was observed to be reducing by about 10% every decade. If the current population is 1250, what is the expected population after 3 decades?

The population 1 decade later will be 0.9 times the population of the current decade.
Therefore, the population after 1 decade will be 1250 × 0.9.
The population after 2 decades will be 1250 × 0.9 × 0.9.
The population after 3 decades will be 1250 × 0.9 × 0.9 × 0.9
= 911.25.

First decade's decrease = 0.1 × 1250
= 125.
Population after 1 decade
= 1250 – 125 = 1125.
Second decade's decrease
= 0.1 × 1125 = 112.5 ≅ 112.
Population after 2 decades
= 1125 – 112 = 1013
Third decade's population decrease
= 0.1 × 1013 = 101.3 ≅ 101.
Population after 3 decades
= 1013 – 101 = 912.

Rounding off, we can say that the expected population after 3 decades will be around 910.

Tricky Percentages

Would You Rather?

You have won a contest. The organisers offer you two options to choose from:
Option A: You deposit ₹100 and you get back ₹300.
Option B: You deposit ₹1000 and you get back ₹1500.
What is the percentage gain each option gives? You can choose any option only once. Which option would you choose? Why?

Math Talk

© NCERT not to be republished



While comparing percentages, we have to be mindful that we are comparing fractions or proportions and not absolute values.

? A provision store is offering a stock clearance sale. Customers can choose one of the two options — 20% discount or ₹50 discount—for any purchase above ₹150. Which option would you choose if you want to:

(i) buy items worth ₹180

(ii) buy items worth ₹225

(iii) buy items worth ₹300

? **Example 12:** A bakery called Cakely is offering a 30% + 20% discount on all cakes. Another bakery called Cakify is offering a 50% discount on all cakes. Would you rather choose Cakely or Cakify if you want the cheaper cost?

It seems that both the options should give the same benefit. Although mathematically 30% + 20% is the same as 50%, the usage of 30% + 20% in shopping means compounding.

Suppose you want to buy a cake worth ₹200.

Cakely's 30% + 20% →

Applying the 30% discount → the price of cake is ₹200 – ₹60 = ₹140.

Applying the 20% discount on ₹140 → the price of cake is ₹140 – ₹28 = ₹112.

Cakify's 50% →

The 50% discount makes the price of the cake ₹100.

© NCERT not to be republished

A Mishap

Example 13: After Surbhi bought cookware from the wholesaler, she kept a profit margin of 50% on all the products. To clear off the remaining stock, she thought she would offer a 50% discount and come out without any loss.

(i) Do you think she didn't make any loss?

(ii) If she had sold goods (originally) for ₹12,000 after discount, how much loss did she incur? What is the percentage loss?

(iii) What should have been the percentage discount offered so that she sold the goods at the price she had bought (i.e., no profit or loss)?

Let us model the situation first.

Suppose the worth of the products she bought from the wholesaler is x.

The worth corresponding to the selling price (with a 50% margin) is $1.5x$.

A 50% discount on this price will make the worth $0.75x$.



(i) This means the selling price is $\frac{3}{4}$ of the price the goods were bought at, i.e., a 25% loss.

(ii) If she had sold goods worth ₹12,000,

$$0.75x = 12{,}000$$

$$x = 16{,}000.$$

She lost ₹4000.

(iii) To sell the goods at the same price, the discount offered should be

$$1.5x - d \times (1.5x) = x$$

$$d = \frac{1}{3} = 0.33.$$

The discount offered should have been 33.33%.

Ariba and Arun have some marbles. Ariba says, "The number of marbles with me is 120% of the marbles Arun has". What would be an appropriate statement Arun could make comparing the number of marbles he has with Ariba's?

Try This

© NCERT not to be republished

Figure it Out

1. The population of Bengaluru in 2025 is about 250% of its population in 2000. If the population in 2000 was 50 lakhs, what is the population in 2025?

2. The population of the world in 2025 is about 8.2 billion. The populations of some countries in 2025 are given. Match them with their approximate percentage share of the worldwide population. [**Hint:** Writing these numbers in the standard form and estimating can help].

Germany 83 million	India 1.46 billion	Bangladesh 175 million	USA 347 million

13%	8%	18%	10%	1%	35%	2%	2%	0.1%

3. The price of a mobile phone is ₹8,250. A GST of 18% is added to the price. Which of the following gives the final price of the phone including the GST?

   (i) $8250 + 18$
   (ii) $8250 + 1800$
   (iii) $8250 + \frac{18}{100}$
   (iv) 8250×18
   (v) 8250×1.18
   (vi) $8250 + 8250 \times 0.18$
   (vii) 1.8×8250

4. The monthly percentage change in population (compared to the previous month) of mice in a lab is given: Month 1 change was +5%, Month 2 change was –2%, and Month 3 change was –3%. Which of the following statement(s) are true? The initial population is p .

   (i) The population after three months was $p \times 0.05 \times 0.02 \times 0.03$.
   (ii) The population after three months was $p \times 1.05 \times 0.98 \times 0.97$.
   (iii) The population after three months was $p + 0.05 - 0.02 - 0.03$.
   (iv) The population after three months was p.
   (v) The population after three months was more than p.
   (vi) The population after three months was less than p.

5. A shopkeeper initially set the price of a product with a 35% profit margin. Due to poor sales, he decided to offer a 30% discount on the selling price. Will he make a profit or a loss? Give reasons for your answer.

6. What percentage of area is occupied by the region marked ‘E’ in the figure?

© NCERT not to be republished

7. What is 5% of 40? What is 40% of 5?

   What is 25% of 12? What is 12% of 25?
   What is 15% of 60? What is 60% of 15?
   What do you notice?
   Can you make a general statement and justify it using algebra, comparing x% of y and y% of x?



8. A school is organising an excursion for its students. 40% of them are Grade 8 students and the rest are Grade 9 students. Among these Grade 8 students, 60% are girls. [**Hint:** Drawing a rough diagram can help].

   (i) What percentage of the students going to the excursion are Grade 8 girls?

   (ii) If the total number of students going to the excursion is 160, how many of them are Grade 8 girls?

9. A shopkeeper sells pencils at a price such that the selling price of 3 pencils is equal to the cost of 5 pencils. Does he make a profit or a loss? What is his profit or loss percentage?

10. The bus fares were increased by 3% last year and by 4% this year. What is the overall percentage price increase in the last 2 years?

11. If the length of a rectangle is increased by 10% and the area is unchanged, by what percentage (exactly) does the breadth decrease by?

12. The percentage of ingredients in a 65 g chips packet is shown in the picture. Find out the weight each ingredient makes up in this packet.

13. Three shops sell the same items at the same price. The shops offer deals as follows:

    Shop A: "Buy 1 and get 1 free"
    Shop B: "Buy 2 and get 1 free"
    Shop C: "Buy 3 and get 1 free"

    Answer the following:

    (i) If the price of one item is ₹100, what is the effective price per item in each shop? Arrange the shops from cheapest to costliest.

    (ii) For each shop, calculate the percentage discount on the items. [**Hint:** Compare the free items to the total items you receive.]

    (iii) Suppose you need 4 items. Which shop would you choose? Why?

© NCERT not to be republished

14. In a room of 100 people, 99% are left-handed. How many left-handed people have to leave the room to bring that percentage down to 98%?

Try This

15. Look at the following graph.

Ability to use computer by age and gender (2023)

The ability to use computers is highest among those in their twenties and teenagers.



Source: NSS Round 79, Comprehensive Annual Modular Survey, National Statistics Office

Data For India

Based on the graph, which of the following statement(s) are valid?

(i) People in their twenties are the most computer-literate among all age groups.

(ii) Women lag behind in the ability to use computers across age groups.

(iii) There are more people in their twenties than teenagers.

(iv) More than a quarter of people in their thirties can use computers.

(v) Less than 1 in 10 aged 60 and above can use computers.

(vi) Half of the people in their twenties can use computers.

© NCERT not to be republished

SUMMARY

- Percentages are widely used in our daily life.
- Percentages are fractions with denominator 100. Percentages are denoted using the symbol '%', pronounced 'per cent'. $x\% = \frac{x}{100}$.
- Fractions can be converted to percentages and vice versa. Decimals too can be converted to percentages and vice versa. For example, $\frac{4}{10} = 0.4 = 40\%$.



- We have learnt to find the exact number when a certain percentage of the total quantity is given.
- When parts of a quantity are given to us as ratios, we have seen how to convert them to percentages.
- The increase or decrease in a certain quantity can also be expressed as a percentage.
- The profits or losses incurred in transactions, and tax rates, can be expressed in terms of percentages.
- We have seen how a quantity or a number grows when compounded. Interest rates are a common example of compounding. If p is the principal, r is the rate of interest, and t is the number of terms, then the total amount after the maturity period is

Without compounding,	With compounding,
$p\,(1 + rt)$	$p \times (1 + r) \times (1 + r) \times \cdots \times (1 + r) = p\,(1 + r)^t$
p remains the principal for all the terms.	Principal for term 1 Principal for term 2 Principal for term 3 ⋮ Principal for term t

- A situation or a problem can often be solved by describing it using a rough diagram. We have learnt to estimate and do mental computations to solve problems related to percentages.

© NCERT not to be republished

Peaceful Knights

Place 8 knights on the chess board so that no knight attacks another. A knight moves in an 'L-shape'. It can move either (a) two steps vertically and one step horizontally, or (b) two steps horizontally and one step vertically. Possible moves of a knight are shown below.





© NCERT not to be republished

2 THE BAUDHĀYANA-PYTHAGORAS THEOREM

0889CH02

2.1 Doubling a Square

In Baudhāyana's *Śulba-Sūtra* (c. 800 BCE), Baudhāyana considers the following question:

? How can one construct a square having double the area of a given square?



A first guess might be to simply double the length of each side of the square. Will this new square have double the area of the original square?

It's not hard to see that the new square will have area 2 × 2 = 4 times the area of the original square:



So how can one make a square that has double the area? Baudhāyana in his *Śulba-Sūtra* (Verse 1.9) gave an elegant answer to this question:

> The diagonal of a square produces a square of double the area of the original square.

As Baudhāyana says, the key is to construct a square on the diagonal of the original square:

© NCERT not to be republished



? Why does the new dotted square have double the area of the original square?



In many of the constructions in the *Śulba-Sūtra*, it is desirable to construct, where needed, what Baudhāyana calls 'east-west' and 'north-south' lines, i.e., horizontal and vertical lines that are perpendicular to each other. Can you draw some horizontal and vertical lines to see why the new square has double the area of the original square? You could draw some horizontal and vertical lines as shown on the right.

? Why should the extension of the vertical and horizontal sides of the original square pass through the vertices of the dotted square?

Math Talk

[**Hint:** From the diagonal property of a square, the line that bisects an angle passes through the opposite vertex. Argue why the vertical and horizontal sides of the original square bisect the two angles of the dotted square.]

So, the new square has double the area of the original square, because the original square is made up of two small triangles, while the new square is made up of four small triangles.

? Moreover, all these small triangles are congruent to each other. Can you explain why?

Adding some more horizontal and vertical lines can make the situation even clearer:



© NCERT not to be republished

So we can make the following sequence of squares:



Each square has double the area of the previous one, as they are made up of 2, 4, and 8 small triangles, respectively.

Doubling a Square Using Paper

? Cut out two identical squares of paper. Draw, label, and cut as follows:



Square 1



Identical Square 2

Now place the pieces 5, 6, 7, and 8 around Square 1 to get a square with double the area.

© NCERT not to be republished

2.2 Halving a Square

? Now suppose we are given a square, and we want to construct a square whose area is half that of the original square. How would you do it?



One way to do it is to reverse the construction of the previous section. We draw a tilted smaller square inside the larger one:



? Why is the smaller inside square half the area of the larger square? Again, adding some east-west and north-south lines can explain it:



Halving a Square Using Paper

? Cut out a square from a piece of paper. Now make a square whose area is half the area of the first square.

? Will the square having half the sidelength have half the area? Why not? How many such squares will fill the original square?

Fold the square paper inward, as shown, such that the crease lines pass through the midpoints of the sides. PQRS is the required square with half the area.



© NCERT not to be republished

? Why is PQRS a square? Why is its area half that of the original paper?

Explain by connecting QS and PR, finding the different angles formed, and then using tringle congruence.

2.3 Hypotenuse of an Isosceles Right Triangle

Recall that in a right triangle, the side opposite to the right angle is called the **hypotenuse.**

? Find the hypotenuse of this isosceles right triangle.



We know that a square of side 1 unit is made of two such isosceles right triangles. We also know that the square constructed on the diagonal of this square has twice the area of the original square.



We do not yet know the length of the hypotenuse, but we know the area of the square REST on it!

$$\text{Area of REST} = 2 \times \text{Area of PEAR}$$

$$= 2 \times 1 = 2 \text{ sq. units.}$$

We know the relation between the side and the area of a square. If c is the hypotenuse ER, then

$$\text{Area of REST} = c \times c = c^2.$$

$$\text{So, } c^2 = 2.$$

$$\text{Therefore, } c = \sqrt{2}.$$

Thus, the hypotenuse is of length $\sqrt{2}$ units.





© NCERT not to be republished

In the rest of this chapter, we will assume that all the lengths are of a fixed unit unless specified otherwise.

? What is the value of $\sqrt{2}$?

Decimal Representation of $\sqrt{2}$

The decimal representation of $\sqrt{2}$ can be found using the following argument.

? Is $\sqrt{2}$ less than or greater than 1?

A square of sidelength 1 unit has an area of 1 sq. unit. A square of sidelength $\sqrt{2}$ has an area of 2 sq. units. So, 1 is less than $\sqrt{2}$.
In other words, $1^2 = 1$, and $\sqrt{2}^2 = 2$.

Therefore, $1 < \sqrt{2}$.

? Is $\sqrt{2}$ less than or greater than 2?

A square of sidelength 2 units has an area of 4 sq. units. A square of sidelength $\sqrt{2}$ has an area of 2 sq. units. So, 2 is greater than $\sqrt{2}$.
In other words, $\sqrt{2}^2 = 2$, and $2^2 = 4$.

Therefore, $\sqrt{2} < 2$.

Thus, $1 < \sqrt{2} < 2$.

We call 1 a lower bound on $\sqrt{2}$ and 2 an upper bound.

? Can we find closer bounds for $\sqrt{2}$?

$1.1^2 = 1.21$
$1.2^2 = 1.44$
$1.3^2 = 1.69$
$1.4^2 = 1.96$
$1.5^2 = 2.25$
So, $1.4 < \sqrt{2} < 1.5$

$1.41^2 = 1.9881$
$1.42^2 = 2.0164$
So, $1.41 < \sqrt{2} < 1.42$

$1.411^2 = 1.990921$
$1.412^2 = 1.993744$
$1.413^2 = 1.996569$
$1.414^2 = 1.999396$
$1.415^2 = 2.002225$
So, $1.414 < \sqrt{2} < 1.415$

? Will we ever get a number with a terminating decimal representation whose square is 2?

If there is such a terminating decimal starting with 1.414... whose square is 2, then it must have a non-zero last digit. If this is the case, then the decimal representation of its square will also have a non-zero last digit after the decimal point. For example, if $\sqrt{2}$ is of the form 1.414...4, then its square will be of the form—

□ . □ □ ... □ 6

© NCERT not to be republished

So a terminating decimal cannot have 2 or 2.000... as its square.

Thus, the decimal expansion of $\sqrt{2}$ must go on forever, i.e., it has a non-terminating decimal representation.

Try This

? Can $\sqrt{2}$ be expressed as a fraction $\frac{m}{n}$, where m and n are counting numbers?

If $\sqrt{2}$ could be expressed as $\frac{m}{n}$, then we would have

$$\sqrt{2} = \frac{m}{n}$$

$$2 = \frac{m^2}{n^2}$$

$$2n^2 = m^2.$$

Recall that in the prime factorization of a square number, each prime occurs an even number of times. So in the equation $2n^2 = m^2$, the prime 2 would occur an odd number of times on the left side and an even number of times on the right side. This is impossible. Thus $\sqrt{2}$ cannot be expressed as a fraction $\frac{m}{n}$.

This beautiful proof that $\sqrt{2}$ cannot be expressed as $\frac{m}{n}$ where m, n are counting numbers was given by Euclid in his book *Elements* (c. 300 BCE). We will discuss it in more detail in a later class.

Thus the number $\sqrt{2}$ cannot be expressed as a terminating decimal or a fraction. But we can think of it as a certain non-terminating decimal: $\sqrt{2}$ = 1.41421356...

? Figure it Out

Math Talk

1. Earlier, we saw a method to create a square with double the area of a given square paper. There is another method to do this in which two identical square papers are cut in the following way.



Can you arrange these pieces to create a square with double the area of either square?

2. The length of the two equal sides of an isosceles right triangle is given. Find the length of the hypotenuse. Find bounds on the length of the hypotenuse such that they have at least one digit after the decimal point.

(i) 3 (ii) 4 (iii) 6 (iv) 8 (v) 9

© NCERT not to be republished

3. The hypotenuse of an isosceles right triangle is 10. What are its other two sidelengths? [**Hint:** Find the area of the square composed of two such right triangles.]

General Solution

The relation between the areas of a square and the square on its diagonal can be used to find a general relation between the hypotenuse and the other two sides of an isosceles right triangle.



Let a be the length of the equal sides and c the length of the hypotenuse.

Area of SQVU = 2 × Area of PQRS

So, $c^2 = 2a^2$.

This formula can be used to find c when a is known, or to find a when c is known.

Example 1: Find the hypotenuse of an isosceles right triangle whose equal sides have length 12.

We have $a = 12$. Using the formula, we get

$$c = \sqrt{2 \times 12^2} = \sqrt{288}.$$

We have $16^2 = 256$, and $17^2 = 289$.

So, $\sqrt{288}$ lies between 16 and 17.

The length of the hypotenuse of an isosceles right triangle, whose length of the equal sides is 12 units, is between 16 and 17 units.

Example 2: If the hypotenuse of an isosceles right triangle is $\sqrt{72}$, find its other two sides.

We have $c = \sqrt{72}$. Using the formula, we get

$$c^2 = 2a^2$$

© NCERT not to be republished

$$\text{So, } (\sqrt{72})^2 = 2a^2$$

$$72 = 2a^2.$$

$$\text{Thus, } a^2 = \frac{72}{2} = 36.$$

$$\text{So, } a = \sqrt{36} = 6.$$

Therefore, each of the other two sides has length 6.
Use this formula to check your answers in the Figure it Out on page 39.

2.4 Combining Two Different Squares

We have seen in the previous sections how to combine two copies of the same square to make a larger square whose area is the sum of the areas of the two smaller squares.



The sidelength of the larger square is the length of the diagonal of either of the smaller squares.

? What if we wish to combine two squares of 'different' sizes to make a large square whose area is the sum of the two smaller squares?

In his *Śulba-Sūtra* (Verse 1.12), Baudhāyana also gives a truly remarkable solution to this more general problem of combining two different sized squares. He writes:

> The area of the square produced by the diagonal is the sum of the areas of the squares produced by the two sides.

© NCERT not to be republished

That is, to combine two different squares, make a right-angled triangle whose perpendicular sides are the sidelengths of the two squares. The square whose sidelength is the hypotenuse of this right-angled triangle has an area that is the sum of the areas of the original two squares.



? Why does Baudhāyana's method work?

? Can you see why the method works in the case where the two squares are the same size? Does it agree with the method we used earlier to combine two same sized squares into a bigger square?

Subsequently in his *Śulba-Sūtra* (Verse 2.1), Baudhāyana provides another verse that helps in explaining why the method works in general:

To combine different squares, mark a rectangular portion of the larger square using a side of the smaller square. The diagonal of this rectangle is the side of a square that has area equal to the sum of the areas of the smaller squares.

Let us follow Baudhayan's instructions.

- Join the two squares.



© NCERT not to be republished

- Mark a rectangular portion of the larger square using a side of the smaller one, and draw its diagonal. By doing this, we get a right triangle with perpendicular sides a and b.

1.



- Make a 4-sided figure over the hypotenuse by drawing three more of such right triangles:

2.



3.



© NCERT not to be republished

4.



- The 4-sided figure obtained (T + U + V) is in fact a square with an area equal to the sum of the areas of the two smaller squares!

? Why?

- As T, U, X and W are all congruent, the sides of this new 4-sided figure all have the same length. Notice the angles.



? Explain why all the angles of this new 4-sided figure are right angles and so it is a square.

Notice that this new square has as its sidelength, the hypotenuse of the right triangle of sides *a* and *b*.

- Baudhāyana's assertion is now clear:

The area of the square on the hypotenuse = the sum of the areas of T, U, and V = the sum of the areas of V, W, and X = the sum of the areas of the two given squares.

© NCERT not to be republished



Combining Two Squares Using Paper

Cut out and join two different sized squares as follows:



Now make two cuts to make three pieces:



Rearrange the three pieces into a larger square:



You have now combined two smaller squares into a larger square!

Now make a right triangle using the two smaller squares. Draw a square on the hypotenuse.

© NCERT not to be republished



Cover the square on the hypotenuse using your pieces.



This shows that if a right triangle has shorter sides of length a and b, and hypotenuse of length c, then the areas of the two smaller squares, a^2 and b^2, add up to the area of the larger square, c^2 :

$$a^2 + b^2 = c^2.$$

This is the famous and fundamental theorem of Baudhāyana on right-angled triangles:

Baudhāyana's Theorem on Right-angled triangles: If a right-angled triangle has sidelengths a, b, and c, where c is the length of the hypotenuse, then $a^2 + b^2 = c^2$.

© NCERT not to be republished

Baudhāyana was the first person in history to state this theorem in this generality and essentially modern form. The theorem is also known as the Pythagorean Theorem, after the Greek philosopher-mathematician Pythagoras (*c*. 500 BCE) who also admired and studied this theorem, and lived a couple hundred years after Baudhāyana. It is also often called the transitional name 'Baudhāyana-Pythagoras Theorem' so that everyone knows what theorem is being referred to.

Using Baudhāyana's Theorem

Make a right-angled triangle in your notebook whose shorter sidelengths are 3 cm and 4 cm. Now, measure the length of the hypotenuse. It should read about 5cm.



In fact, we could have used Baudhāyana's Theorem to predict that the hypotenuse is exactly 5cm! Let $a = 3$ and $b = 4$, the lengths in cm of the two shorter sides. Then, by Baudhāyana's Theorem, the length c of the hypotenuse satisfies the equation,

$$a^2 + b^2 = c^2$$
$$3^2 + 4^2 = c^2$$
$$9 + 16 = c^2$$
$$25 = c^2$$

So, $c = 5$ cm.

Figure it Out

1. If a right-angled triangle has shorter sides of lengths 5 cm and 12 cm, then what is the length of its hypotenuse? First draw the right-angled triangle with these sidelengths and measure the hypotenuse, then check your answer using Baudhāyana's Theorem.

2. If a right-angled triangle has a short side of length 8 cm and hypotenuse of length 17 cm, what is the length of the third side? Again, try drawing the triangle and measuring, and then check your answer using Baudhāyana's Theorem.

3. Using the constructions you have now seen, how would you construct a square whose area is triple the area of a given square? Five times the area of a given square? (Baudhāyana's *Śulba-Sūtra,* Verse 1.10)

4. Let a, b and c denote the length of the sides of a right triangle, with c being the length of the hypotenuse. Find the missing sidelength in each of the following cases:

   (i) $a = 5, b = 7$ (ii) $a = 8, b = 12$ (iii) $a = 9, c = 15$

   (iv) $a = 7, b = 12$ (v) $a = 1.5, b = 3.5$

© NCERT not to be republished

2.5 Right–Triangles Having Integer Sidelengths

In his *Śulba-Sūtra* (Verse 1.13) Baudhāyana lists a number of integer triples (a, b, c) that form the sidelengths of a right-triangle and therefore satisfy $a^2 + b^2 = c^2$. These include (3, 4, 5), (5, 12, 13) (8, 15, 17), (7, 24, 25), (12, 35, 37), and (15, 36, 39).

For this reason, such triples (a, b, c) that form the sidelengths of a right triangle (equivalently, satisfy $a^2 + b^2 = c^2$) are called **Baudhāyana triples.** They are also called **Baudhāyana-Pythagoras triples, Pythagorean triples,** and **right-angled triangle triples.**

Math Talk

? List down all the Baudhāyana triples with numbers less than or equal to 20.

? Is there an unending sequence of Baudhāyana triples?

Mathematicians have answered this question and have found a method to generate all such triples! Let us take a few steps in this direction.

We have seen that (3, 4, 5) is a Baudhāyana triple.

? Is (30, 40, 50) a Baudhāyana triple?

Is (300, 400, 500) a Baudhāyana triple?

The list of Baudhāyana triples having numbers less than or equal to 20 contains the following triples —

(3, 4, 5), (6, 8, 10), (9, 12, 15), (12, 16, 20).

? Do you see any pattern among them?

All these triples can be obtained by multiplying each term of (3, 4, 5) by a certain positive integer.

? Can we form a conjecture on Baudhāyana triples based on this observation?

Conjecture: $(3k, 4k, 5k)$ is a Baudhāyana triple, where k is any positive integer.

? Is this true?

We have to check if $(3k)^2 + (4k)^2 = (5k)^2$.

We have $(3k)^2 + (4k)^2 = 9k^2 + 16k^2 = 25k^2$, which is equal to $(5k)^2$.

So, $(3k, 4k, 5k)$ is indeed a Baudhāyana triple.

This shows that there are infinitely many Baudhāyana triples.

Can we further generalise the conjecture?

© NCERT not to be republished

? If (a, b, c) is a Baudhāyana triple, then (ka, kb, kc) is also a Baudhāyana triple where k is any positive integer. Is this statement true?

This statement can be shown to be true in the same way. Since (a, b, c) is a Baudhāyana triple, we have $a^2 + b^2 = c^2$. We need to check whether $(ka)^2 + (kb)^2 = (kc)^2$.

$$(ka)^2 = ka \times ka = k^2 a^2, \text{ and } (kb)^2 = kb \times kb = k^2 b^2.$$

$$\text{So, } (ka)^2 + (kb)^2 = k^2 a^2 + k^2 b^2.$$

Taking out the common factor, we have

$$(ka)^2+(kb)^2 = k^2 (a^2 + b^2).$$

Since $a^2 + b^2 = c^2$, we have

$$(ka)^2 + (kb)^2 = k^2 c^2 = (kc)^2.$$

Thus, (ka, kb, kc) is a Baudhāyana triple if (a, b, c) is a Baudhāyana triple. We call (ka, kb, kc) a **scaled version** of (a, b, c).

A Baudhāyana triple that does not have any common factor greater than 1 is called a **primitive Baudhāyana triple**. So, (3, 4, 5) is primitive, whereas (9,12,15) is not.

? Is (5, 12, 13) a primitive Baudhāyana triple? What are the other primitive Baudhāyana triples with numbers less than or equal to 20?

? Generate 5 scaled versions of each of these primitive triples. Are these scaled versions primitive?

? If (a, b, c) is non-primitive, and the integers have f — greater than 1 — as a common factor, then is $\left(\frac{a}{f}, \frac{b}{f}, \frac{c}{f}\right)$ a Baudhāyana triple? Check this statement for (9, 12, 15). Justify this statement.

If we can find all the primitive triples, we can find all the Baudhāyana triples.

? How do we generate more primitive triples?

We know the relation between the sum of consecutive odd numbers and square numbers.

$$1 = 1^2$$
$$1 + 3 = 2^2$$
$$1 + 3 + 5 = 3^2$$

The sum of the first n odd numbers is n^2. Let us express this algebraically.

? For this, we need to know the nth odd number. What is it?

The nth odd number is $2n - 1$. So,

$$\underbrace{1 + 3 + 5 + \cdots + (2n - 3)}_{\text{Sum of first } (n-1) \text{ odd numbers}} + (2n - 1) = n^2$$

© NCERT not to be republished

What is the sum of the first $(n-1)$ odd numbers?

Thus,

$$(n-1)^2 + (2n-1) = n^2.$$

Note that this equation could also have been directly obtained by expanding $(n-1)^2$ and adding $2n-1$ to it.

If the nth odd number, $2n-1$, is also a square number, then we have a sum of two square numbers equal to another square number. We will use this idea to generate Baudhāyana triples.

1. 9 is an odd square. It is the 5th odd number ($9 = 2 \times 5 - 1$). So, we have

$$1 + 3 + 5 + 7 + 9 = 5^2$$

$$4^2 + 3^2 = 5^2$$

Could we have obtained this triple using the equation $(n-1)^2 + (2n-1) = n^2$?

Since we took the 5th odd number, the value of n is 5. Substituting $n = 5$ into the equation, we get

$$(5-1)^2 + 9 = 5^2$$

$$4^2 + 3^2 = 5^2.$$

2. 25 is an odd square. It is the 13th odd number ($25 = 2 \times 13 - 1$). So,

$1 + 3 + 5 + \cdots + 23 + 25 = 13^2$ $12^2 + 5^2 = 13^2$	We have $n = 13$. Substituting this value in the equation, we get $(13-1)^2 + 25 = 13^2$ $12^2 + 5^2 = 13^2$

Figure it Out

1. Find 5 more Baudhāyana triples using this idea.
2. Does this method yield non-primitive Baudhāyana triples? [**Hint:** Observe that among the triples generated, one of the smaller sidelengths is one less than the hypotenuse.]
3. Are there primitive triples that cannot be obtained through this method? If yes, give examples.

Math Talk

2.6 A Long-Standing Open Problem

The study of Baudhāyana triples inspired the great French mathematician Fermat — who lived during the 17th century — to make a general statement about the sum of powers of positive integers.

© NCERT not to be republished

We have seen that there are an infinite number of square numbers that can be written as a sum of two square numbers. This made Fermat wonder if there is a perfect cube that can be written as a sum of two perfect cubes, a fourth power that can be written as a sum of two fourth powers, and so on. In other words, he wondered if there is a solution to the equation

$$x^n + y^n = z^n,$$

where x, y, and z are natural numbers, and $n > 2$.

In the margin of a book that dealt with properties and patterns of positive integers (like that of Baudhāyana triples), Fermat wrote that amongst the unending sequence of numbers, one cannot find a single perfect cube that is a sum of two perfect cubes, a fourth power that is a sum of two fourth powers, and so on. So, the equation has no solution for powers greater than 2. In addition to stating this, Fermat wrote,

"I have found a truly marvellous proof of this statement, but the margin is too small to contain it".

No one could ever find Fermat's proof of this statement, which is called **Fermat's Last Theorem.**

After his death, many great mathematicians tried their hand at proving this theorem. There followed more than 300 years of failed attempts in proving it.

In 1963, a 10-year-old boy named Andrew Wiles read a book (*The Last Problem* by Eric Bell) about Fermat's Last Theorem and its history. Despite reading about the failures of so many great mathematicians, this young boy resolved to prove this theorem.

He eventually did prove this theorem in 1994!

© NCERT not to be republished

2.7 Further Applications of the Baudhāyana-Pythagoras Theorem

The Baudhāyana-Pythagoras theorem is one of the fundamental theorems of geometry. Let us see some of its applications.

A Problem from Bhāskarāchārya's Līlāvatī

The following is a translation of a problem from Bhāskarāchārya's (Bhāskara II) *Līlāvatī*. Try to visualise what you read.

"In a lake surrounded by *chakra* and *krauñcha* birds, there is a lotus flower peeping out of the water, with the tip of its stem 1 unit above the water. On being swayed by a gentle breeze, the tip touches the water 3 units away from its original position. Quickly tell the depth of the lake."



At first glance, it seems like there is insufficient data to find the solution. But the solution exists!

Let x be the length of the stem inside the water. This is the required depth of the lake. Since the stem of the lotus is sticking 1 unit above the water, the total length of the stem is $x + 1$.

We can make a (very reasonable) assumption that the lotus stem is perpendicular to the surface of the water in the first position. With this assumption, we get a right triangle of sides 3, x and $x + 1$. As this satisfies the Baudhāyana-Pythagoras theorem, we have

$$3^2 + x^2 = (x + 1)^2$$

$$9 + x^2 = x^2 + 2x + 1.$$

Subtracting x^2 from both sides, we get

$$9 = 2x + 1.$$

$$x = 4.$$

Thus, the depth of the lake is 4 units.

Figure it Out

1. Find the diagonal of a square with sidelength 5 cm.
2. Find the missing sidelengths in the following right triangles:

© NCERT not to be republished



3. Find the sidelength of a rhombus whose diagonals are of length 24 units and 70 units.

4. Is the hypotenuse the longest side of a right triangle? Justify your answer.

5. True or False—Every Baudhāyana triple is either a primitive triple or a scaled version of a primitive triple.

6. Give 5 examples of rectangles whose sidelengths and diagonals are all integers.

7. Construct a square whose area is equal to the difference of the areas of squares of sidelengths 5 units and 7 units.

8. (i) Using the dots of a grid as the vertices, can you create a square that has an area of (a) 2 sq. units, (b) 3 sq. units, (c) 4 sq.units, and (d) 5 sq. unit?

   (ii) Suppose the grid extends indefinitely. What are the possible integer-valued areas of squares you can create in this manner?



Math Talk

Try This

© NCERT not to be republished

9. Find the area of an equilateral triangle with sidelength 6 units. [**Hint:** Show that an altitude bisects the opposite side. Use this to find the height.]

Try This

SUMMARY

- The Baudhāyana-Pythagoras Theorem is one of the most fundamental theorems in geometry. It expresses the relationship among the three sides of a right-angled triangle.
- If a, b, c, are the sidelengths of a right-angled triangle, where c is the length of hypotenuse, then $a^2 + b^2 = c^2$.
- In an isosceles triangle with sidelengths a, a, c, we have the relation $a^2 + a^2 = 2a^2 = c^2$, i.e., $c = a\sqrt{2}$.
- The number $\sqrt{2}$ lies between 1.414 and 1.415. However, it cannot be expressed as a terminating decimal. It also cannot be expressed as a fraction $\frac{m}{n}$ with m, n positive integers.
- A triple (a, b, c) of positive integers satisfying $a^2 + b^2 = c^2$ is called a Baudhāyana-Pythagoras triple. Examples include (3, 4, 5), (6, 8, 10), and (5, 12, 13). Infinitely many such triples can be constructed.
- The equation $a^n + b^n = c^n$ has no solution in positive integers when $n > 2$. This is known as 'Fermat's Last Theorem'. It was proven by Andrew Wiles in 1994.

© NCERT not to be republished

IT'S PUZZLE TIME!

Find the Colours!

There are 3 closed boxes—one containing only red balls, the second containing only blue balls and the third containing only green balls. The boxes are labelled RED, BLUE and GREEN such that 'no' box has the correct label. We need to find which label goes with which box. How can this be done if we are allowed to open only one box?

3 PROPORTIONAL REASONING–2

0889CH03

3.1 Proportionality—A Quick Recap

In an earlier chapter, we explored proportional relationships between quantities and we used the ratio notation to represent such relationships. When two or more related quantities change by the same factor, we call that relationship a proportional relationship. For example, *idli* batter is made by mixing rice and *urad dal.* The proportion of these two can have regional variations. One of the proportions used is: for 2 cups of rice, we add 1 cup of *urad dal*. We represent this relationship using the ratio notation 2 : 1.

? Viswanath made *idlis* by mixing 6 cups of rice with 3 cups of *urad dal*, while Puneet made *idlis* by mixing 4 cups of rice with 2 cups of *urad dal*. If cooked in the same way, would their *idlis* taste the same?

Viswanath's mixture can be represented as 6 : 3 and Puneet's mixture as 4 : 2.

Recall that, to verify that these two ratios are proportional, we can use the cross-multiplication method:



The two products are the same (12). So, the two ratios are proportional. It is likely that the *idlis* would taste the same, if all the other ingredients are proportional too!

In general, we can say that two ratios $a : b$ and $c : d$ are proportional if

$$a \times d = b \times c, \text{ or}$$

$$\frac{a}{c} = \frac{b}{d}.$$

© NCERT not to be republished

3.2 Ratios in Maps



Have you noticed that in many maps there is a ratio given, usually in the lower right corner of the map? It usually contains 1 and a very large number, such as 1 : 60,00,000. What does RF 1 : 60,00,000 mean? What does it indicate? Can you guess?

A Representative Fraction (RF) is an expression that shows the ratio between a distance on the map and the corresponding actual distance on the ground.

For example, if the ratio on a map is 1 : 60,00,000, that means a distance of 1 cm on the map is equivalent to a geographical distance of 60,00,000 cm. Remember, this is geographical distance and not road distance!

Convert 60,00,000 cm to kilometres.

It is 60 km. Verify this.

Using the map above, can you find the geographical distance between Bengaluru and Chennai? Also, find the geographical distance between Mangaluru and Chennai.

[**Hint:** Use a ruler to find the distance between the cities on the map. Then, use the ratio given on the map to find the actual geographical distance.]

© NCERT not to be republished

? Try to find the distances between the same two pairs of cities with different maps that have different scales (ratios). Do they all give the same geographical distance, approximately?

Note to the Teacher: Bring maps and atlases to the classroom and encourage students to observe the scale given as a ratio (usually in the lower right corner) on the map. Use the maps and atlases in the library and ask students to find the geographical distances between two locations on the map that are of local interest. Ask them to verify with each other if they get similar distances and to find the reasons if the distances are very different.

Map Making Activity: Guide students to make a sketch of their classroom with an accurate scale (ratio of 1: 50). They should mark the location of various objects in the classroom like the teacher's desk, blackboard, fans and lights, according to scale. Students can use appropriate symbols to represent different objects like fans, lights, tables, chairs, and so on.

3.3 Ratios with More than 2 Terms

Viswanath is experimenting with a spice mix powder. He makes the powder by grinding 8 spoons of coriander seeds, 4 red chillies, 2 spoons of *toor dal*, and 1 spoon of fenugreek (*methi*) seeds. For his spice mix powder, the ratio of coriander seeds to red chillies to *toor dal* to fenugreek seeds is

8 : 4 : 2 : 1.

Notice that the ratio has 4 terms. Ratios can have many terms if each of the quantities change by the same factor to maintain the proportional relationship.

? Puneet has only 2 red chillies in his kitchen. But he wants to make spice mix powder that tastes the same as Viswanath's spice mix powder. How much of the other ingredients should Puneet use to make his spice mix powder?

For Puneet's spice mix powder to be similar to Viswanath's, the ratio of all the ingredients should be the same as Viswanath's spice mix powder. Puneet has only 2 red chillies. He has half the number of chillies that Viswanath used in his mixture. So, the quantity of the other ingredients should also be reduced to half.

Thus, Puneet should add 4 spoons of coriander seeds, 2 red chillies, 1 spoon of *toor dal*, and half a spoon of fenugreek seeds. The ratio is

4 : 2 : 1 : 0.5.

© NCERT not to be republished

Both the ratios are proportional to each other. We denote this by

$$8 : 4 : 2 : 1 :: 4 : 2 : 1 : 0.5.$$

In general, when two ratios with multiple terms are proportional

$$a : b : c : d :: p : q : r : s$$

then,

$$\frac{a}{p} = \frac{b}{q} = \frac{c}{r} = \frac{d}{s}.$$

Example 1: To make a special shade of purple, paint must be mixed in the ratio, Red : Blue : White :: 2 : 3 : 5. If Yasmin has 10 litres of white paint, how many litres of red and blue paint should she add to get the same shade of purple?

In the ratio 2 : 3 : 5, the white paint corresponds to 5 parts.

If 5 parts is 10 litres, 1 part is 10 ÷ 5 = 2 litres.

Red = 2 parts = 2 × 2 = 4 litres.

Blue = 3 parts = 3 × 2 = 6 litres.

So, the purple paint will have 4 litres of red, 6 litres of blue, and 10 litres of white paint.

What is the total volume of this purple paint?

The total volume of purple paint is 4 + 6 + 10 = 20 litres.

Example 2: Cement concrete is a mixture of cement, sand, and gravel, and is widely used in construction. The ratio of the components in the mixture varies depending on how strong the structure needs to be. For structures that need greater strength like pillars, beams, and roofs, the ratio is 1 : 1.5 : 3, and the construction is also reinforced with steel rods. Using this ratio, if we have 3 bags of cement, how many bags of concrete mixture can we make?

The concrete mixture is in the ratio

Bags of cement : bags of sand : bags of gravel :: 1 : 1.5 : 3.

If we have 3 bags of cement, we have to multiply the other terms by 3. So, the ratio is

cement : sand : gravel :: 3 : 4.5 : 9.

In total, we have 3 + 4.5 + 9 = 16.5 bags of concrete.

3.4 Dividing a Whole in a Given Ratio

In an earlier chapter, we learnt how to divide a whole in a ratio, e.g., 12 in the ratio 2 : 1. To do this, we add the terms (2 + 1 = 3), and divide the whole by this sum (12 ÷ 3 = 4). We multiply each term by this quotient : 2 × 4 = 8 and 1 × 4 = 4 . So, 12 divided in the ratio 2 : 1 is 8 : 4.

© NCERT not to be republished

We can extend this to ratios with multiple terms.

Let us look at the earlier example of making a concrete mixture. We need to mix cement, sand, and gravel in the ratio of 1 : 1.5 : 3 to get the concrete.

Example 3: For some construction, 110 units of concrete are needed. How many units of cement, sand, and gravel are needed if these are to be mixed in the ratio 1 : 1.5 : 3?

For 1 unit of cement, we need to add 1.5 units of sand and 3 units of gravel. Together, they add up to 5.5 units of concrete. We need to do this 20 times (110 ÷ 5.5 = 20) to get 110 units of concrete. So each term has to be multiplied by 20.

1 × 20 = 20 units of cement,
1.5 × 20 = 30 units of sand, and
3 × 20 = 60 units of gravel.



So, we need 20 units of cement, 30 units of sand, and 60 units of gravel to make the concrete.

When we divide a quantity x in the ratio $a : b : c : \cdots$, the terms in the ratio are—

$x \times \frac{a}{(a+b+c+\cdots)}$, $x \times \frac{b}{(a+b+c+\cdots)}$, $x \times \frac{c}{(a+b+c+\cdots)}$, and so on.

Example 4: You get a particular shade of purple paint by mixing red, blue, and white paint in the ratio 2 : 3 : 5. If you need 50 ml of purple paint, how many ml of red, blue, and white paint will you mix together?

$$\text{Red paint} = 50 \times \frac{2}{(2+3+5)} = 50 \times \frac{2}{10} = 10 \text{ ml.}$$

$$\text{Blue paint} = 50 \times \frac{3}{(2+3+5)} = 50 \times \frac{3}{10} = 15 \text{ ml.}$$

$$\text{White paint} = 50 \times \frac{5}{(2+3+5)} = 50 \times \frac{5}{10} = 25 \text{ ml.}$$

© NCERT not to be republished

Example 5: Construct a triangle with angles in the ratio 1 : 3 : 5.

We know that the sum of the angles in a triangle is 180°. So the angles are

$\angle A = 180° \times \frac{1}{(1+3+5)} = 180° \times \frac{1}{9} = 20°.$

$\angle B = 180° \times \frac{3}{(1+3+5)} = 180° \times \frac{3}{9} = 60°.$

$\angle C = 180° \times \frac{5}{(1+3+5)} = 180° \times \frac{5}{9} = 100°.$



Figure it Out

1. A cricket coach schedules practice sessions that include different activities in a specific ratio — time for warm-up/cool-down : time for batting : time for bowling : time for fielding :: 3 : 4 : 3 : 5. If each session is 150 minutes long, how much time is spent on each activity?
2. A school library has books in different languages in the following ratio — no. of Odiya books : no. of Hindi books : no. of English books :: 3 : 2 : 1. If the library has 288 Odiya books, how many Hindi and English books does it have?
3. I have 100 coins in the ratio — no. of ₹10 coins : no. of ₹5 coins : no. of ₹2 coins : no. of ₹1 coins :: 4 : 3 : 2 : 1. How much money do I have in coins?
4. Construct a triangle with sidelengths in the ratio 3 : 4 : 5. Will all the triangles drawn with this ratio of sidelengths be congruent to each other? Why or why not?
5. Can you construct a triangle with sidelengths in the ratio 1 : 3 : 5? Why or why not?

Math Talk

3.5 A Slice of the Pie

Have you seen pie charts like the one shown in the figure? Pie charts show different proportions of a whole. This one shows the proportions of students that have scored each grade in an assessment. These kinds of visualisations help us quickly interpret data.

Let us try to create this pie chart. Here is a table showing the grades scored by students:



Grade	A	B	C	D	E
Students	12	10	8	6	4

© NCERT not to be republished

How do we mark the different slices of the pie chart?

To mark a slice in the pie chart, the angle corresponding to a grade should be proportional to the number of students who have scored that grade. The total angle in a circle is 360°. So, we need to divide 360 in the ratio of 12 : 10 : 8 : 6 : 4.

Can we reduce this ratio to its simplest form?

We can use the same procedure we used to reduce a ratio with two terms to its simplest form. We divide all the terms by their HCF to get the simplest form.

In this example, 2 is the HCF of the terms. We get the simplest form by dividing all the terms by 2. The ratio becomes 6 : 5 : 4 : 3 : 2.

So, the angles are:

$$\text{Grade A} = \frac{6}{(6+5+4+3+2)} \times 360° = \frac{6}{20} \times 360° = 6 \times 18 = 108°.$$

$$\text{Grade B} = \frac{5}{(6+5+4+3+2)} \times 360° = 5 \times 18 = 90°.$$

$$\text{Grade C} = 4 \times 18 = 72°.$$

$$\text{Grade D} = 3 \times 18 = 54°.$$

$$\text{Grade E} = 2 \times 18 = 36°.$$

Now let us construct a pie chart using these angles.

Step 1: Draw a circle and mark the radius AB as shown below:	Step 2: To draw the slice to represent the proportion of students who got an A grade, measure 108° from the segment AB on A (anti-clockwise), and mark the new radius AC.
	

© NCERT not to be republished

Step 3: Measure 90° from AC and draw AD.



Step 4: Measure 72° from AD and draw AE.



Steps 5,6: Similarly, we can complete the rest of the pie chart.



Step 7: You can colour and label the different slices of the pie chart appropriately.



© NCERT not to be republished

Figure it Out

1. A group of 360 people were asked to vote for their favourite season from the three seasons—rainy, winter and summer. 90 liked the summer season, 120 liked the rainy season, and the rest liked the winter. Draw a pie chart to show this information.

2. Draw a pie chart based on the following information about viewers' favourite type of TV channel: Entertainment—50%, Sports—25%, News—15%, Information—10%.

3. Prepare a pie chart that shows the favourite subjects of the students in your class. You can collect the data of the number of students for

each subject shown in the table (each student should choose only one subject). Then write these numbers in the table and construct a pie chart:

Subject	Language	Arts Education	Vocational Education	Social Science	Physical Education	Maths	Science
Number of Students							

3.6 Inverse Proportions

Do you recall the rule of three? When two ratios are proportional, i.e., when

$a : b :: c : d$, then $d = \frac{bc}{a}$. We call such proportions **direct proportions**. We use this understanding to find the value of the fourth quantity (d), when the value of three quantities (a, b, and c) are given.

Example 1: If 5 workers can move 4500 bricks in a day, how many workers are needed to move 18000 bricks in a day?

This can be represented as a statement of proportionality — $4500 : 18000 :: 5 : x$. We can find the value of x by

$$x = \frac{18000 \times 5}{4500} = 20$$

Thus, the number of workers needed are 20.

Example 2: Puneeth's father went from Lucknow to Kanpur in 3 hours by riding his motorcycle at a speed of 30 km/h. If he takes a car instead and drives at 60 km/h, how long will it take him to reach Kanpur?

Can we represent this problem with the following statement of proportionality — $30 : 60 :: 3 : x$? Will the travel time increase or decrease as the speed of the motorcycle increases?

Math Talk

The following table shows the time taken to travel from Lucknow to Kanpur using different modes of transport:

	Walk	Bicycle	Motorcycle	Car
Speed (km/h)	5	15	30	60
Time (in hours)	18	6	3	1.5

From this table, we notice that when the speed **increases**, the time taken to travel the same distance **decreases**.

© NCERT not to be republished

? Does it decrease by the same rate (or factor)?

Going by bicycle is 3 times faster than walking (15 ÷ 5). The speed has increased 3 times. The travel time has decreased 3 times too (18 ÷ 6). The speed has increased by the same factor by which the travel time has decreased.

? Check if this is the case for the other modes of transport.

Since both quantities, speed and time, change by the same factor, they are proportional. But they change in opposite directions, or inversely. Such proportions are called **inverse proportions**.

From the table, we can see that the product of speed and time are the same for all modes of transport, namely 90 km.

Two quantities x and y vary in inverse proportion if there exists a relation of the type $xy = k$, where k is a constant.

In the previous example, if x represents the speed and y represents the time taken, then k is the distance between Lucknow and Kanpur, which remains constant.



Thus, if quantities x and y are inversely proportional, and x_1 and x_2 are values of x that have corresponding y values y_1 and y_2, then

$$x_1y_1 = x_2y_2 = k \text{ (some constant).}$$

From these we can see that $\frac{x_1}{x_2} = \frac{y_2}{y_1}$.

Let us check if this is true for other modes of transport, such as walking and by car. Let us use x to represent speed and y to represent time.

$$x_1 = 5,\ x_2 = 60,\ y_1 = 18,\ y_2 = 1.5.$$

$$\frac{x_1}{x_2} = \frac{5}{60} = 0.083333...$$

What is the value of $\frac{1.5}{18}\left(\frac{y_2}{y_1}\right)$? It is 0.083333... too!

© NCERT not to be republished

Figure it Out

1. Which of these are in inverse proportion?

(i)

x	40	80	25	16
y	20	10	32	50

(ii)

x	40	80	25	16
y	20	10	12.5	8

(iii)

x	30	90	150	10
y	15	5	3	45

2. Fill in the empty cells if x and y are in inverse proportion.

x	16	12		36
y	9		48	

Example 3: 20 workers take 4 days to complete laying a road. How many days will 10 workers take to complete laying the same length of road?

If we decrease the number of workers, then the number of days to complete the work will increase by the same factor. So these quantities are inversely proportional. So, $x_1y_1 = x_2y_2$.

Thus, $20 \times 4 = 10 \times y_2$

$$y_2 = \frac{20 \times 4}{10} = 8.$$

It will take 8 days for 10 workers to complete the work.

We notice that when the number of workers halved, the number of days to complete the work doubled. Quantities are inversely proportional if, when one quantity changes by a factor n, the other quantity changes by the inverse $\frac{1}{n}$.

© NCERT not to be republished

Example 4: 2 pumps can fill a tank in 18 hours. How much time will it take to fill the tank if we add 2 more pumps of the same kind?

If we add 2 more pumps, we will have 4 pumps. Let us denote the time taken to fill the tank with 4 pumps by x. If we increase the number of pumps by n, then the time taken to fill the tank will decrease by the same factor n, so the quantities are inversely proportional. Since the quantities are inversely proportional, the product remains constant. So,

$$2 \times 18 = 4 \times x.$$

$$x = \frac{2 \times 18}{4} = 9.$$

It will take 9 hours to fill the tank.

Example 5: A school has food provisions to feed 80 students for 15 days. If 20 more students join the school, for how many days will the provisions last?

More students → fewer days the provisions will last. The quantities are inversely proportional. If x is the number of days,

$$80 \times 15 = 100 \times x.$$

$$x = \frac{80 \times 15}{100} = 12.$$

The provisions will last for only 12 days.

Example 6: If Ram takes 1 hour to cut a given quantity of vegetables and Shyam takes 1.5 hours to cut the same quantity of vegetables, how much time will they take to cut the vegetables if they do it together?

Consider the work done to cut the given quantity of vegetables as 1 unit of work. Let us figure out the work done by each person in 1 hour.

- Ram finishes the work in 1 hour, so in 1 hour he does 1 unit of work.
- Shyam finishes the work in 1.5 hours, so in 1 hour he does $\frac{1}{1.5} = \frac{2}{3}$ units of work.

So, the work done by both in 1 hour is $1 + \frac{2}{3} = \frac{5}{3}$ units of work.

Therefore, to complete $\frac{5}{3}$ units of work, it takes them 1 hour if they work together. How much time will it take them to complete 1 unit of work?

Math Talk

Is the quantity of work and time taken to complete it directly or inversely proportional?

It is directly proportional. So, this can be represented as

$\frac{5}{3} : 1 :: 1 : x$ where x is the time taken.

© NCERT not to be republished

Since it is a direct proportion, we know that

$$\frac{5}{3} \times x = 1 \times 1$$

$$x = \frac{1 \times 1}{\frac{5}{3}} = \frac{1}{\frac{5}{3}} = \frac{3}{5}.$$

If they cut the vegetables together, they will finish in $\frac{3}{5}$ hours.

Figure it Out

1. Which of the following pairs of quantities are in inverse proportion?
   (i) The number of taps filling a water tank and the time taken to fill it.
   (ii) The number of painters hired and the days needed to paint a wall of fixed size.
   (iii) The distance a car can travel and the amount of petrol in the tank.
   (iv) The speed of a cyclist and the time taken to cover a fixed route.
   (v) The length of cloth bought and the price paid at a fixed rate per metre.
   (vi) The number of pages in a book and the time required to read it at a fixed reading speed.
2. If 24 pencils cost ₹120, how much will 20 such pencils cost?
3. A tank on a building has enough water to supply 20 families living there for 6 days. If 10 more families move in there, how long will the water last? What assumptions do you need to make to work out this problem?

Math Talk

4. Fill in the average number of hours each living being sleeps in a day by looking at the charts. Select the appropriate hours from this list : 15, 2.5, 20, 8, 3.5, 13, 10.5, 18.



© NCERT not to be republished

5. The pie chart on the right shows the result of a survey carried out to find the modes of transport used by children to go to school. Study the pie chart and answer the following questions.



   (i) What is the most common mode of transport?

   (ii) What fraction of children travel by car?

   (iii) If 18 children travel by car, how many children took part in the survey? How many children use taxis to travel to school?

   (iv) By which two modes of transport are equal numbers of children travelling?

6. Three workers can paint a fence in 4 days. If one more worker joins the team, how many days will it take them to finish the work? What are the assumptions you need to make?

7. It takes 6 hours to fill 2 tanks of the same size with a pump. How long will it take to fill 5 such tanks with the same pump?

8. A given set of chairs are arranged in 25 rows, with 12 chairs in each row. If the chairs are rearranged with 20 chairs in each row, how many rows does this new arrangement have?

9. A school has 8 periods a day, each of 45 minutes duration. How long is each period, if the school has 9 periods a day, assuming that the number of school hours per day stays the same?

10. A small pump can fill a tank in 3 hours, while a large pump can fill the same tank in 2 hours. If both pumps are used together, how long will the tank take to fill?



11. A factory requires 42 machines to produce a given number of toys in 63 days. How many machines are required to produce the same number of toys in 54 days?



12. A car takes 2 hours to reach a destination, travelling at a speed of 60 km/h. How long will the car take if it travels at a speed of 80 km/h?

© NCERT not to be republished

SUMMARY

- Ratios in the form $a : b : c : d : \cdots$ indicate that for every a units of the first quantity, there are b units of the second quantity, c units of the third quantity, and so on.
- If x is divided into many parts in the ratio $p : q : r : s : \cdots$, then the quantity of the first part is $x \times \frac{p}{(p + q + r + s + \cdots)}$, the quantity of the second part is $x \times \frac{q}{(p + q + r + s + \cdots)}$, and so on.
- Two quantities are directly proportional when they both change by the same factor, and their quotient remains the same. For example, if x and y are two quantities that are directly proportional, and $(x_1, x_2, x_3, \ldots)$ and $(y_1, y_2, y_3, \ldots)$ are the corresponding values of x and y, then $\frac{x_1}{y_1} = \frac{x_2}{y_2} = \frac{x_3}{y_3} = \cdots = k$, where k is a constant.
- Quantities are inversely proportional if, when one quantity changes by a factor n, the other quantity changes by the inverse $\frac{1}{n}$. For example, if x and y are two quantities that are inversely proportional, and $(x_1, x_2, x_3, \ldots)$ and $(y_1, y_2, y_3, \ldots)$ are the corresponding values of x and y, then $x_1y_1 = x_2y_2 = x_3y_3 = \cdots = n$, where n is a constant.

© NCERT not to be republished

4 EXPLORING SOME GEOMETRIC THEMES

0889CH04

In this chapter, we will explore two geometric themes. We will study fractals which are self-similar shapes. They exhibit the same or similar pattern over and over again — but at smaller and smaller scales. We will then look at different ways of visualising solids.

4.1 Fractals

One of the most beautiful examples of a fractal that also occurs in nature is the fern. The fern is seen to have smaller copies of itself as its leaves, and these in turn have even smaller copies of themselves in their sub-leaves, and so on!

Similar phenomena of self-similarity occur in trees (where a trunk has limbs, and a limb has branches, and the branches have branchlets, and so on), clouds, coastlines, mountains, lightning, and many other objects in nature.

Other mathematical fractals can also be very beautiful. We will explore some of them here.

Sierpinski Carpet

The Polish mathematician Sierpinski discovered a type of fractal known as the **Sierpinski Carpet**. It is made by taking a square, breaking it into 9 smaller squares, and then removing the central square (see the figure below); the same procedure is then repeated on the remaining 8 squares, and so on. One then sees the same pattern at smaller and smaller scales.



Step 0 Step 1 Step 2

© NCERT not to be republished



Sierpinski Carpet

? Draw the initial few steps (at least till Step 2) of the shape sequence that leads to the Sierpinski Carpet.

By its construction, each step in the sequence has

(i) squares of the same size that remain in the figure, and the size of these squares becomes smaller and smaller as the step number increases, and

(ii) square holes that are formed by removing square pieces.

? Do you see any pattern in the number of holes and squares that remain at each step?

Let R_n represent the number of remaining squares at the nth step, and H_n represent the number of holes at the nth step.

Let us understand how these numbers grow by analysing how the holes and squares that remain are generated from the previous step.

Every square that remains at a given step, say Step n, gives rise to 8 squares that remain at the $(n + 1)$th step. Thus, we have

$$R_{n+1} = 8\,R_n.$$

? Can this be used to get a formula for R_n?

We have

$$R_0 = 1$$
$$R_1 = 8 \times 1 = 8$$
$$R_2 = 8 \times 8 = 8^2.$$

In general, $R_n = 8^n$.

? Similarly, how do we find the number of holes at a given step?

Every square that remains at the nth step gives rise to a hole in the $(n + 1)$th step. All the holes present at the nth step remain in the $(n + 1)$th step as well. Thus,

$$H_{n+1} = H_n + R_n.$$

So we have

$$R_0 = 1 \qquad H_0 = 0$$
$$R_1 = 8 \qquad H_1 = 1$$
$$R_2 = 8^2 \qquad H_2 = 1 + 8$$
$$R_3 = 8^3 \qquad H_3 = 1 + 8 + 8^2$$
$$\vdots$$

© NCERT not to be republished

Sierpinski Gasket

Sierpinski came up with another fractal made in a similar way. An equilateral triangle is broken up into 4 identical equilateral triangles by joining the midpoints of the bigger triangle, and then the central triangle is removed. This procedure is repeated on the 3 remaining triangles, and so on.



Step 0 Step 1 Step 2 . . .



Sierpinski Triangle

? Show that by joining the midpoints of an equilateral triangle, we divide it into 4 identical equilateral triangles.

[**Hint:** Note that the corner triangles are isosceles.]

This fractal is called the **Sierpinski Triangle/Gasket**.

? Figure it Out

1. Draw the initial few steps (at least till Step 2) of the shape sequence that leads to the Sierpinski Triangle.
2. Find the number of holes, and the triangles that remain at each step of the shape sequence that leads to the Sierpinski Triangle.
3. Find the area of the region remaining at the *n*th step in each of the shape sequences that lead to the Sierpinski fractals. Take the area of the starting square/triangle to be 1 sq. unit.

© NCERT not to be republished

Koch Snowflake

The Koch Snowflake is another fractal, named after the Swedish mathematician Von Koch, who first described it in 1904. We have already encountered this fractal in Grade 6, *Ganita Prakash*.



Step 0 Step 1 Step 2 . . .



Koch Snowflake

To generate it, we start with an equilateral triangle. Each side is

(i) divided into 3 equal parts, and

(ii) an equilateral triangle is raised over the middle part, and then the middle part is removed.

Effectively, each side gets replaced by a 'bump' - shaped structure ⌒. This procedure is repeated on the sides of the new resulting shape, and so on.

Figure it Out

1. Draw the initial few steps (at least till Step 2) of the shape sequence that leads to the Koch Snowflake.
2. Find the number of sides in the *n*th step of the shape sequence that leads to the Koch Snowflake.
3. Find the perimeter of the shape at the *n*th step of the sequence. Take the starting equilateral triangle to have a sidelength of 1 unit.

© NCERT not to be republished

Fractals in Art

Fractals have also long been used in human-made art! Perhaps the oldest such fractals appear in the temples of India. An example occurs in the Kandariya Mahadev Temple in Khajuraho, Madhya Pradesh which was completed in around 1025 C.E.; there one sees a tall temple structure, which is made up of smaller copies of the full structure, on which there are even smaller copies of the same structure, and so on. Fractal-like patterns also occur in temples in Madurai, Hampi, Rameswaram, Varanasi, among many others.

Kandariya Mahadev Temple

Fractals are also common in traditional African cultures. For example, patterns on Nigerian Fulani wedding blankets often exhibit fractal structures.

Nigerian Fulani Wedding Blanket

© not to be republished

In the blanket shown in the figure, there are diamond shaped patterns, inside of which there are smaller diamond shaped patterns, and so on.

The modern maestro of fractal art is undoubtedly the Dutch artist M.C. Escher. We have already seen that some of his prints explore the mathematical theme of tiling. One famous example involving fractals is his work 'Smaller and Smaller', which exhibits the identical pattern of lizards but at smaller and smaller scales. Here is a print inspired by Escher's 'Smaller and Smaller'.

4.2 Visualising Solids

Build it in Your Imagination

? We will start this section by practising visualisation. For each prompt, feel free to talk to your partner, gesture, draw it in the air — but do not actually draw on paper!

My method is different. I do not rush into actual work. When I get an idea I start at once building it up in my imagination. I change the construction, make improvements, and operate the device entirely in my mind.

— Nikolas Tesla (1856 – 1943), the great Serbian-American engineer and inventor, who made fundamental contributions to electrical engineering and other fields.



1. Picture your name, then read off the letters backwards. Make sure to do this by sight, not by sound — really see your name! Now try with your friend's name.

© NCERT not to be republished

2. Cut off the four corners of an imaginary square, with each cut going between midpoints of adjacent edges. What shape is left over? How can you reassemble the four corners to make another square?

3. Mark the sides of an equilateral triangle into thirds. Cut off each corner of the triangle, as far as the marks. What shape do you get?

4. Mark the sides of a square into thirds and cut off each of its corners as far as the marks. What shape is left?

When we see a solid object, we are really seeing its **profile** from a specific viewpoint. Depending on our viewpoint, the **outline** of this profile can vary dramatically!



Perhaps you've noticed interesting profiles of objects yourself, while taking a photograph or observing the shadow of an object? Or, maybe you've seen a cartoon like the following, in which a character bursts through a wall and leaves a hole shaped like their outline!

© NCERT not to be republished

In previous classes, you've seen solids that are much simpler than an elephant or cat, such as cubes, spheres, cylinders, and cones. What would the profiles of these look like, from different viewpoints?

? Can you describe a solid and a viewpoint that would result in each of the following cases? If it helps, you can imagine the solid passing through a wall like Tom did, and leaving a hole of the appropriate shape.

5. A solid whose profile has a square outline
6. A solid whose profile has a circular outline
7. A solid whose profile has a triangular outline

? As we saw with the elephant, a given solid might have very different profiles from different viewpoints. Can you visualise solids that have the following contrasting profiles?

Spend some time on this, and if you are finding it difficult to visualise, you may look around and use objects that are around you, or that you will make in the next section. Feel free to consider viewpoints from any direction, including directly above the object.

8. A solid with a rectangular profile from one viewpoint and a circular profile from another viewpoint
9. A solid with a circular profile from one viewpoint and a triangular one from another viewpoint
10. A solid with a rectangular profile from one viewpoint and a triangular one from another viewpoint
11. A solid with a trapezium shaped profile from one viewpoint and a circular one from another viewpoint
12. A solid with a pentagonal profile from one viewpoint and a rectangular one from another viewpoint

? Are there unique solids for each of the conditions, or can you come up with multiple possibilities?

Making Solids

Many basic solid shapes such as a cuboid, parallelopiped, cylinder, cone, prism, and pyramid can be made using foldable flat materials like paper, cardboard, and even metallic sheets! This is one of the methods for manufacturing hollow solids.

© NCERT not to be republished



Cuboid



Parallelopiped



Cylinder



Cone

Triangular prism



Triangular pyramid

While discussing solids that contain plane surfaces in their boundaries, the notion of faces, edges and vertices serves a useful purpose.





Faces are the plane/flat surfaces of a solid that form its boundary. **Edges** are the line segments that form the sides of the faces, and **vertices** are the points at which the edges meet. For example, a cuboid or cube has 6 faces, 12 edges and 8 vertices.

© NCERT not to be republished

There are multiple types of prisms and pyramids, whose names depend on the shapes of their faces.



Triangular Prism



Pentagonal Prism



Hexagonal Prism

Prism: A prism, in general, has two congruent polygons as opposite faces, with edges connecting the corresponding vertices of these polygons. All the other faces are parallelograms. Based on the shape of the congruent polygons, prisms may be called triangular prisms, pentagonal prisms, and so on.

Pyramids: A pyramid, in general, has a polygonal base and a point outside it, and edges connect the point with each of the vertices of the base. Based on the shape of the base, pyramids may be called triangular pyramids, square pyramids, pentagonal pyramids, and so on. A triangular pyramid is also known as a **tetrahedron**.



Triangular Pyramid



Pentagonal Pyramid



Hexagonal Pyramid

? If the congruent polygons of a prism have 10 sides, how many faces, edges and vertices does the prism have? What if the polygons have n sides?

? If the base of a pyramid has 10 sides, how many faces, edges and vertices does the pyramid have? What if the base is an n-sided polygon?

Now we will see how to make different solids using a foldable flat surface such as paper, cardboard, etc.

The basic idea is to create a shape on a flat surface that can be folded into the solid. Such a shape is called a **net**. In other words, a net is obtained by 'unfolding' a solid onto a plane.

© NCERT not to be republished

What is a net of a cube?

Fig. 4.1 is a net of a cube.



Fig. 4.1

Visualise how it can be folded to form a cube.

Practical Aspects of Using a Net

To make an actual cube from its net, certain practical aspects have to be kept in mind. One is that the material used must have sufficient sturdiness for the cube to stand. The second aspect is that there should be some mechanism for attaching the faces together. If cardboard or a similar material is used, cello tape is one way to join the adjacent faces. For less sturdy materials, such as chart paper, it is useful to have extra 'flaps' on some of the faces that can be stuck to the adjacent faces. You might have observed this strategy in packaging boxes.



(i) (ii) (iii)

However, when we talk about the net of a solid, we consider only the shape formed by unfolding the solid, and not the other supporting flaps that we may use to actually make the solid.

Apart from using a net, there are other ways to make a cube from paper.

There are multiple possible nets one can use to build a cube.

Figure it Out

1. Which of the following are the nets of a cube? First, try to answer by visualisation. Then, you may use cutouts and try.



(i) (ii) (iii)

© NCERT not to be republished



(iv)



(v)



(vi)

2. A cube has 11 possible net structures in total. In this count, two nets are considered the same if one can be obtained from the other by a rotation or a flip. For example, the following nets are all considered the same —



Find all the 11 nets of a cube.

Try This

3. Draw a net of a cuboid having sidelengths:

   (i) 5 cm, 3 cm, and 1 cm

   (ii) 6 cm, 3 cm, and 2 cm

Let us find out the nets of other solids.

A tetrahedron whose faces are equilateral triangles is called a regular **tetrahedron**.

? What is a net of a regular tetrahedron? Which of the following are nets of a regular tetrahedron?



? Are there any other possible nets?

A regular tetrahedron has only 2 possible nets.

? Draw a net with appropriate measurements that can be folded into a regular tetrahedron. Verify if it works by making an actual cutout.

Math Talk

? Draw a net with appropriate measurements that can be folded into a square pyramid. Verify if it works by making an actual cutout.

© NCERT not to be republished

? What is the net of a cylinder?

If the circular faces of a cylinder are unfolded, and if a cut is made along the height of the cylinder, as shown in the figure below, then we get



? What are the sidelengths of the rectangle obtained?

? How will the net of a cone look?



? If the cone is slit open along the line l and then unrolled, what will we get?

Observe that all the points on the boundary of the base circle are at equal distances from 'O'. So after unrolling the cone, the boundary of the net will be a portion of a circle with centre O.



? What surface do you construct by using the above net, in which O is not the centre of the boundary circle? Make a physical model to help you answer this question!

Math Talk

? Draw a net with appropriate measurements that can be folded into a triangular prism. Verify that it works by making an actual cutout.

© NCERT not to be republished

Here is a solid called the **octahedron**, made by joining two square pyramids at their square bases.



Octahedron

Can you visualise its net? This is one of its nets.



? Taking all the triangles in the net to be equilateral, make a cutout of the net and fold it to form an octahedron.

Math Talk

As in the case of cubes, an octahedron too has 11 different nets.

So far, we have seen solids whose faces are all equilateral triangles (regular tetrahedrons), and all squares (cubes). Does there exist a solid whose faces are all pentagons? Interestingly, the answer is yes!

This solid is called a **dodecahedron**. This solid too can be made from a net! Mathematicians have been even able to determine exactly how many nets a dodecahedron has — 43,380.



Dodecahedron

© NCERT not to be republished

? **Net of a sphere?** Experiment and see if you can make a paper cutout that can perfectly wrap around a ball without leaving any wrinkles, gaps or overlaps.

Shortest Paths on a Cube

Let us consider an interesting problem related to the discussion so far. We know that on a plane, the shortest path between two points is the straight line between them. Now, what is the shortest path between two points on the surface of a cuboid, if we are allowed to travel only along its surface?

Let us imagine a hungry ant living on the surface of a cuboid. To its good fortune, there is a laddu on the surface.



? What is the shortest path for the ant to reach the laddu?

Math Talk

? What about in the following case?



? If we think that a certain path is the shortest, how can we be sure that it truly is, among all the infinite possibilities?

? For example, are either of these the shortest path?



© NCERT not to be republished

[**Hint:** Draw the net and see how these paths appear on the net.]



? What does this show?

A path on the surface of the cuboid can be transformed to a path of the same length on the net. Conversely, every path on the net transforms to a path of the same length on the cuboid.

In the first case, the path marked on the cuboid is the shortest since it transforms to a straight line between the ant and laddu on the net, which is the shortest path between them.

In the second case, the path marked on the cuboid does not transform to a straight line path on the net, and hence is not the shortest path for the ant to take.



The red path is the shortest

Thus, by using a net, we convert the problem of finding the shortest path on a cuboid to the problem of finding the shortest path on the net.

Have we now completely analysed the problem of finding the shortest path between two points on a cuboid?

© NCERT not to be republished

? Find the shortest path between the ant and the laddu in the following case:



If we unfold the cuboid as before, we get



Notice the line segment between the ant and laddu going outside the net! Obviously, this does not correspond to any path on the cuboid.

? So what do we do now?

If the net is unfolded in the following way, then we get a path on the cuboid.



The shortest path

Thus, the way a cuboid is unfolded matters!

© NCERT not to be republished

Now we will look at a trickier case.

Try This

? What is the length of the shortest path between the ant and the laddu?



Here are some of the ways of unfolding the cuboid.



In the second case, the distance d between the ant and the laddu can be calculated using the Baudhayana Theorem, since we have a right triangle here.

$$d^2 = 24^2 + 32^2$$

$$d = \sqrt{1600} = 40 \text{ cm}$$

We see that in each of these unfoldings, the lengths of the line segments between the ant and the laddu are different! So we have to carefully list all the possible different unfoldings to find the answer!

Representation of Solids on a Plane Surface

Drawing is one of the oldest human activities. People have been doing it for thousands of years for both aesthetic as well as practical and engineering purposes. Regarding the latter, making a drawing of an object is a useful way to record or convey information about it. Visual representation also helps us in thinking about the objects being represented. Such needs often arise in engineering — while constructing buildings, designing machines, etc. Further, engineering drawings need

© NCERT not to be republished

to be detailed enough so that one can physically construct the objects they depict.

We will now explore some ways of drawing solids on a plane.

Projections

The net of a solid (when it exists) is one way of representing a solid on the plane. But it can be difficult to visualise the solid from the net, without physically cutting out the net and folding it up.

Another way to represent a solid is by looking at the **projections** of all its points on a plane. This idea is closely related to the profile of a solid from a specific viewpoint, which we discussed earlier. Let us see how this technique works.



O is the projection of P

Consider a point P in space, and a plane M. Imagine a line from P intersecting the plane M at a point O.

We say that OP is **perpendicular to the plane** if for any line OX on the plane, ∠POX = 90°. In this case, we say that point O is the **projection** of point P on the plane. The projections of all the points of an object together form the **projection of the object on the plane**.

? Let us visualise the projection of a line.



Fig. 4.2

© NCERT not to be republished

What happens to the length of a line in its projection?

Let us consider projections in Fig. 4.3. For example let l be the actual length of the line and p be the length of its projection.

Draw AE ⊥ BC. AECD is a rectangle (why?). So, AE = DC = p. Also, ∠AEB = 90°.



Fig. 4.3

Can you now compare the lengths p and l?

When is the length of the projected line equal to its actual length?

What do you think are the different possible projections of a square that we get based on its orientation?

Math Talk

What do you think is the projection of a parallelogram under different orientations?

Can this ever be a quadrilateral that is not a parallelogram? As a starting point, you could think about the projection of a pair of parallel lines.

What can you say about the projection of an n-sided regular polygon?

[**Hint:** Projection of a polygon is composed of the projections of its sides.]

Math Talk

Let us consider projections of solids now.

How would the projections of a cube and a cone look?



Fig. 4.4



Fig. 4.5

© NCERT not to be republished

If an object were to pass perpendicularly through a plane and form a hole, the shape of the hole would be the same as the shape of the projection of the object.

? See Figures 4.2 – 4.5. In each case, see if you can visualise another object that gives the same projection.



Fig. 4.6

Different lines and different cuboids giving the same projections

We see that a given projection is not made by a unique object.

© NCERT not to be republished

? Find another object that makes the same projection as that of a given cone.

For this reason, we often take three mutually perpendicular projections of an object. As shown in the figure, we consider a plane in front of the object called the **vertical plane**, a plane below the object called the **horizontal plane** and a plane to the side of the object called the **side plane**.



We give names to the projections on these three planes based on the directions from which the object is viewed. The projection on the vertical plane is called the **front view**, on the horizontal plane the **top view** and on the side plane the **side view**. These projections formalise the notion of profiles that we explored in an earlier section.

? Let us see what these projections are for the objects shown in Fig. 4.6, when the planes shown are taken to be vertical planes.

Projections of the different lines in Fig. 4.6 —

© NCERT not to be republished



Projections of the different cuboids in Fig. 4.6 —



© NCERT not to be republished

Figure it Out

1. Observe the front view, top view and side view of the different lines in Fig. 4.6. Is there any relation between their lengths?
2. Find the front view, top view and side view of each of the following solids, fixing its orientation with respect to the vertical, horizontal and side planes: cube, cuboid, parallelepiped, cylinder, cone, prism, and pyramid. If needed, see the next problem for clues.

Math Talk

3. Match each of the following objects with its projections.



© NCERT not to be republished

Shadows

Place an object in front of a plane, such as a wall of your room. Shine a torch light on the object in a direction perpendicular to the wall.



? What do you see?

We will see that the shape of the shadow on a plane is quite similar to the shape of the projection on that plane! However the shadow may be scaled up, stretched, or even distorted slightly, depending on how the object is held.

? Observe what happens to the size of the shadow as you vary the distance between your torch and your object.

? Why does this happen?

Try This

Now, imagine your torch is extremely powerful and will continue casting a shadow of the object on the wall, no matter how far back you move it.

If this imaginary torch always points in a direction perpendicular to the wall, then, as the distance between the torch and the object increases, the shadow of the object will become indistinguishable from the projection of the object to the wall plane!

Although this experiment may sound fanciful, you have encountered one such extremely powerful and distant torch before ... namely, the Sun! Indeed, when sunlight is perpendicular to a plane, the shadows it casts on that plane are indistinguishable from projections!

Earlier we asked what the projection of a parallelogram might look like. You can now physically answer this question by making a cutout of a parallelogram and viewing its shadows under sunlight. No matter how you orient the parallelogram, you will see that the shadow remains a parallelogram!

More generally, the projection of a pair of parallel lines will always remain parallel.

© NCERT not to be republished

This property is useful for drawing projections of objects.

Figure it Out

1. Draw the top view, front view and the side view of each of the following combinations of identical cubes.













2. Imagine eight identical cubes, glued together along faces to form the letter ' '.

   (i) This looks like a ' ' from the front. What does it look like from the side? From the top?

   (ii) Glue additional cubes to make a shape that looks like ' ' from the front and ' ' from the top.

   (iii) Now, can you glue even more cubes to make it look like ' ' from the front, ' ' from the top, and ' ' from the side?

   (iv) Can you think of other letter combinations to make with a single combination of cubes in this manner?

Math Talk

© NCERT not to be republished

3. Which solid corresponds to the given top view, front view, and side view?

Front View



Top View



Side View





(i)



(ii)



(iii)



(iv)



(v)



(vi)



(vii)



4. Using identical cubes, make a solid that gives the following projections.

(i)



Top View

(ii)



Front View

(iii)



Side View

(iv)



Top View

(v)

Front View

(vi)



Side View

(vii)



Top View

(viii)



Front View

(ix)



Side View

© NCERT not to be republished

5. Find the number of cubes in this stack of identical cubes.



6. What are the different shapes the projection of a cube can make under different orientations?

Math Talk

Isometric Projections

In general we lose information when projecting a solid to a plane. But depending on the orientation of the solid, we can sometimes recover much of the information we've lost.

Let us consider an orientation of a cube in which the lengths of the projections of all the edges of the cube are equal. Such a projection is called the **isometric** projection of the cube. 'Isometric' means 'equal measure' in Greek.

Imagine balancing a cube perfectly on one of its corner vertices, and then projecting it down to the floor plane. This projection is isometric and appears as shown.



? Construct a model of a cube and use your hands to keep it balanced on one corner vertex. Can you try to understand why all the projected edges have equal length?

Math Talk

The isometric representation of a cube is a regular hexagon. If the cube is made of glass, then all the edges would be visible.



This structure is the basis for **isometric** drawing! Tile the plane with hexagons and we get an **isometric grid**.

© NCERT not to be republished



Isometric grids are widely used in engineering. They make it easy to draw projections of solids and to measure lengths along all the 3 primary directions — length, depth and height, as shown in Fig. 4.7.



Fig. 4.7

Drawing on Isometric Grids

? Have you played Tetris? There are five basic shapes in Tetris, corresponding to the different ways of arranging four squares.



Fig. 4.8

© NCERT not to be republished

? Imagine these are cubes, not squares. Draw each of these on your isometric paper (you can find it at the end of the book).

As seen in Fig. 4.7, there are three principal axes of the solid shape, which we will call the depth axis, length axis, and height axis.

The edges of the grid appear in three different orientations: /, \ and |. We will associate height to | , depth to / , and length to \.



While drawing on the grid, it may be useful to draw edge by edge, counting the number of units you want to go along a given axis.

For example, you can draw a 1 × 1 × 1 cube as follows. How would you draw a 2 × 2 × 2 cube? Feel free to add shading, if it helps you visualise the solid.



The first tetris shape is a row of four cubes joined face-to-face. In order to draw this solid, you will need to choose an orientation for the row of four cubes.

Let's draw it oriented along the depth axis. You could draw it cube-by-cube, but in that case you may need to erase the lines that get hidden by additional cubes. (If you don't have an eraser, you can also draw faint lines initially, and then darken the visible ones later.)



© NCERT not to be republished

You could also draw it all at once, by counting edges as you go:



Similarly, you could draw the shape oriented along the height axis or the length axis.



In your drawing, moving in the vertical direction on the isometric paper corresponds to moving along the height axis of the solid. Similarly, moving along the \ or / direction on the paper corresponds to moving along the length or depth axis respectively of the solid.

? Why is this correspondence between directions on isometric paper and axes of the solid so effective for communicating the shape of the solid?

Earlier we observed that parallel lines project to parallel lines. This geometric fact ensures that the three families of parallel edges on the solid (corresponding to height, the length, and depth) project to three families of parallel edges on the isometric paper: |, /, and \. Moreover, the isometric nature of the projection ensures that the projections of unit distances along the three axes are equal.

Can you try drawing the other tetris shapes on isometric paper?

? Figure it Out

1. In addition to the 5 ways shown in Fig. 4.8, are there any additional ways of gluing four cubes together along faces? Can you visualise and draw these as well?

Math Talk

© NCERT not to be republished

2. Draw the following figures on the isometric grid.



[**Hint:** It may be useful to determine whether the edge to be currently drawn — say, along the height — goes from down to up or up to down. Accordingly, draw the line segment on the grid either in the direction of the height axis or opposite to it.]

3. Is there anything strange about the path of this ball? Recreate it on the isometric grid.

Math Talk



[**Hint:** Consider a portion of this figure that is physically realisable and identify the 3 primary directions.]

4. Observe this triangle.



(i) Would it be possible to build a model out of actual cubes? What are the front, top, and side profiles of this impossible triangle?

© NCERT not to be republished

(ii) Recreate this on an isometric grid.

(iii) Why does the illusion work?

Math Talk

SUMMARY

- Fractals are self-similar geometric objects found in nature and in art.
- The Sierpinski Carpet, Sierpinski Gasket, and Koch Snowflake are some examples of mathematical fractals. They can be obtained by repeatedly applying certain geometric operations that generate a sequence of shapes approaching the fractal.
- Cuboids, tetrahedrons, cylinders, cones, prisms, pyramids, and octahedrons are some of the solids that can be obtained by folding suitable **nets**.
- The shortest path between two points on the surface of a cuboid can be found by using a suitable net of the cuboid.
- Any object can be represented on a plane surface by using its **projections** on plane surfaces. For this purpose, we generally use the **front view** (projection on the **vertical plane**), **top view** (projection on the **horizontal plane**), and **side view** (projection on the **side plane**) of the object.
- A cube can be oriented such that the lengths of all its edges in the projection are equal. Such a projection is called the **isometric projection**. Isometric projections of different solids can be drawn using isometric grid paper.

© NCERT not to be republished

5 TALES BY DOTS AND LINES

0889CH05

5.1 The Balancing Act

Last year, we learnt about the mean and median. Recall that the mean of some data is the sum of all the values divided by the number of values in the data. The median is the middle value when the data is sorted.

We shall try to understand the mean and median from a different perspective and see how the mean behaves with changing data.

? Consider any 2 numbers. Find their average/arithmetic mean. Repeat this by taking other pairs. What do you observe?

For example, let the two numbers be 3 and 7. Their average is $\frac{3+7}{2} = 5$. Taking another pair of numbers, say 8 and 9, their average is $\frac{8+9}{2} = 8.5$. Visualising these as dot plots we get



Notice that the mean is exactly halfway between the two numbers.

We have learnt earlier that the arithmetic mean is a measure of central tendency and represents the 'centre' of the data. Let us see how the mean represents the 'centre' in the case of 3 numbers.

? Calculate and mark the mean of each collection of data below.



© NCERT not to be republished

Math Talk

? Can you explain how the mean is the centre of each collection?

? Mark the mean for the collections below.



Math Talk

? Can you explain how the mean is the centre of each collection?

Is the mean the midpoint of the two endpoints/extremes of the data? It is not always so. Instead, the total distances are equal on both the sides of the mean. This is illustrated through the following dot plots.



? Verify that this holds for all the collections of data shown earlier.

? Can there be more than one such 'centre'? In other words, is there any other value such that the sum of the distances to the values lower than it and the values higher than it will still be equal?

? In the case of the collection 10, 10, 11, and 17 whose mean is 12, suppose there is a different centre larger than 12.

Clearly, all the distances on the LHS will increase and the distances on the RHS will decrease. Thus, it is no longer the 'centre'. Similarly, for any value smaller than 12, the distances on the LHS will decrease while those on the RHS will increase.

© NCERT not to be republished

Both these cases are illustrated in the following diagram. Therefore, there is only one centre.



? Will including a new value in the data increase or decrease the mean?

When a new value greater than the mean is included, the mean increases to maintain the balance between the sum of distances on the LHS and RHS, as illustrated below.



Similarly, if a value smaller than the mean is included, then the new mean will be less than before.

? What happens to the mean when an existing value is removed? When will the mean increase, decrease, or stay the same?

Math Talk

? What happens to the mean if a value equal to the mean is included or removed?

Try to explain this using the fair-share interpretation of mean that we studied last year.

Unchanging Mean!

We saw earlier how the mean varies when a value is included or removed.

© NCERT not to be republished

Explore if it is possible to include or remove 2 values such that the mean is unchanged.

You may use the following data to experiment with.



How about including or removing 3 values without changing the mean? Is it possible?

Can we include 2 values less than the mean and 1 value greater than the mean, so that the mean remains the same?

One of the possibilities is shown here.



Try to include 2 values greater than the mean and 1 value less than the mean, so that the mean stays the same.

Relatively Unchanged!

We saw what happens to the mean when values are included or removed from the collection. What happens to the mean if every value in the collection increases by some fixed number?

Consider the data: 8, 3, 10, 13, 4, 6, 7, 7, 8, 8, 5. Calculate its mean.

Now, consider this data with every value increased by 10: 18, 13, 20, 23, 14, 16, 17, 17, 18, 18, 15. What is its mean? Is there a quicker way to find out?

[**Hint:** Observe the following dot plots corresponding to the two data collections.]



© NCERT not to be republished

The mean of the new collection also increases by 10. Notice that the relative position of the mean stays the same.



We get the following dot plot if we reduce every value by 1.



This can be explained using algebra —

Suppose there are n values in the collection. Let these values be represented by $x_1, x_2, x_3, \ldots x_n$. Their average is given by —

$$\frac{x_1 + x_2 + x_3 + \ldots + x_n}{n} = a.$$

When a fixed number, for example, 3 is added to every value in the collection, the new average becomes —

$$\frac{(x_1 + 3) + (x_2 + 3) + (x_3 + 3) + \ldots + (x_n + 3)}{n}$$

$$= \frac{x_1 + x_2 + x_3 + \ldots + x_n + 3n}{n}$$

$$= \frac{x_1 + x_2 + x_3 + \ldots + x_n}{n} + \frac{3n}{n}$$

$$= a + 3.$$

That is, the new average is 3 more than the previous average.

Try This

? Try to explain, using algebra, what the average is when a fixed number, e.g., 2 is subtracted from every value in the collection.

? Try to explain this using the fair-share interpretation of average that you learnt last year.

? What happens to the average if every value in the collection is doubled?

You may have guessed that the average also doubles. The following is an example with the data we saw earlier —



© NCERT not to be republished



Mean = 14.36

We can see that the average has doubled.

Let us prove it using algebra.

Suppose there are n values in the collection. Let these values be represented by $x_1, x_2, x_3, \ldots x_n$. Their average is —

$$\frac{x_1 + x_2 + x_3 + \ldots + x_n}{n} = a.$$

When a fixed number, for example, 5 is multiplied to every value in the collection, the new average becomes —

$$\frac{(5x_1) + (5x_2) + (5x_3) + \ldots + (5x_n)}{n}$$

$$= \frac{(x_1 + x_2 + x_3 + \ldots + x_n) \times 5}{n} \text{ (using the distributive property)}$$

$$= \frac{(x_1 + x_2 + x_3 + \ldots + x_n)}{n} \times 5.$$

$$= 5a.$$

That is, the new average is 5 times more than the previous average.

Tinkering with Median

We know that the median is the middle value in the sorted data — there are an equal number of values less than it and greater than it.

? Will including a new value to the data increase or decrease the median?

Let us consider the following data. The median of this data is 8.



Median = 8





Median = 9.5

© NCERT not to be republished

Suppose we include a value 11. The new value included is greater than the (earlier) median — the median can no longer be 8 as there are more values greater than it. Therefore, the median will also increase. The median, now, will be the average of the two middle values 8 and 11, which is 9.5.

We can similarly argue that when a value less than the median is included, the median will decrease.

Finding the Unknown

? Coach Balwan noted down the weights of the *kushti* players (wrestlers) and the mean as shown. But one value that was written down got smudged. Can you find out the missing value?

Average weight of the players = $\frac{\textit{Sum of weight of all players}}{\textit{Number of players}}$.

Let the unknown weight be w kg.

$$= \frac{42 + 40 + 39 + 33 + 48 + 38 + 42 + 35 + 32 + w}{10} = 39.2.$$

Simplifying this we get,

$$349 + w = 392,$$

$$w = 392 - 349 = 43.$$

The missing value is 43 kg.

? Venkayya keeps track of the coconut harvest in his farm. He calculates the average harvest per tree as 25.6. His son verifies the counts and finds that one tree's harvest count is incorrectly noted as 3 more than the actual number. Can you find the correct average if the number of trees is 15?

The average harvest per tree = $\frac{\textit{Total number of coconuts harvested}}{\textit{Number of trees}}$.

The data of harvest per tree is not given.

? Can we still find out the number of coconuts harvested?

Let the initial number of coconuts harvested be z. Based on what is given,

$$25.6 = \frac{z}{15},$$

Simplifying,

$$z = 25.6 \times 15 = 384.$$

The initial count of coconuts harvested is 384.

We know that one tree's count is 3 more than the actual. Therefore, the actual total harvest count is 384 – 3 = 381.

The correct average harvest is $\frac{381}{15} = 25.4$.

© NCERT not to be republished

Mean and Median with Frequencies

What is the average family size of students in your class? How would you find this out?

We can collect the data of how many family members each student has, add them up, and divide it by the number of students. The family size data of students in a class is shown in the table here.

Number	Frequency
3	3
4	11
5	9
6	7
7	3
8	1
9	1
10	1

What is the average family size of this class?

Some of you may have thought, "Easy! It will be $\frac{3+4+5+6+7+8+9+10}{8} = \frac{52}{8} = 6.5$."

Remember that finding the average involves adding all the values in the data. The number 3 occurs three times, the number 4 occurs eleven times, and so on. Do these reflect in your calculation?

We know that the average = $\frac{\textit{Sum of all the values in the data}}{\textit{Number of value in the data}}$.

Accounting for the frequencies of each value, the average will be

$$= \frac{(3\times 3)+(4\times 11)+(5\times 9)+(6\times 7)+(7\times 3)+(8\times 1)+(9\times 1)+(10\times 1)}{3+11+9+7+3+1+1+1}$$

$$= \frac{9+44+45+42+21+8+9+10}{36}$$

$$= \frac{188}{36} = 5.22.$$

The average family size of this class is 5.22.



What is the median family size of this class?

We know that there are 36 values in the data. The median would be the average of the 18th and 19th value in the sequence when the data is ordered.

Do we need to write all the 36 numbers in order? Is there a quicker way to find out?

We can make use of the table where the frequencies are listed. We successively add the frequencies starting from the smallest value until we reach 18 and 19.

Number	3	4	5	6	7	8	9	10
Frequency	3	11	9	7	3	1	1	1

Adding the frequencies of 3 and 4, we get 3 + 11 = 14. This means the value in the 14th position when the data is sorted is 4. Adding the frequencies of 3, 4, and 5, we get 3 + 11 + 9 = 23. This means the value in the 23rd position when the data is sorted is 5. We can see that all the values from positions 15 to 23 are 5. Therefore, the median of this data is 5.

© NCERT not to be republished

Spreadsheets

Sudhakar has collected the mid-term exam marks obtained by his Grade 8 students in the following table:

Name	Odia	Telugu	English	Maths	Social Science	Science
Ratna	25	39	29	36	34	37
Nagesh	41	43	48	39	40	39
Ashwin	29	31	33	34	30	28
Farooq	47	46	38	42	49	44
Mrinal	33	35	28	32	30	36
Gowri	27	29	34	31	32	30
Pankaj	16	19	22	17	18	20
Jaya	31	38	40	50	43	46
Ganesh	39	37	35	38	36	40
Shravan	12	17	21	20	14	18
Aishwarya	48	45	46	47	44	43
Hari	25	28	24	21	23	26
Trupti	29	36	30	33	27	33
Veeresh	23	25	28	31	19	22
Vidhya	34	36	37	40	32	34
Sanskruti	35	42	41	46	38	40
Shanker	42	45	39	36	31	39
Vyshnavi	37	32	29	33	31	35
Govind	15	18	12	20	20	18
Shiva	29	24	32	34	28	30
Tarun	41	44	39	43	37	42
Jyothi	29	30	33	28	34	29

© NCERT not to be republished

Sudhakar has to calculate the total marks scored by each student. He is also interested in knowing the average marks scored in each subject. But there are so many numbers! He will have to spend too much time and effort to complete this task. Of course, he can use a calculator to speed up the task.

Is there any way to further quicken this process?

One way is to use a computer. Computers have different applications/ tools that can be used to perform tasks. One such application is a spreadsheet—it is like a digital notebook with rows and columns of small boxes called **cells**. In each cell, we can type text or numbers. The picture below shows a snapshot of a spreadsheet where Sudhakar has entered the marks data of his class. Try to get access to a computer before proceeding.

	A	B	C	D	E	F	G	H
1	Name	Odia(R1)	Telugu(R2)	English(R3)	Maths	Social	Science	Total
2	Ratna	25	39	29	36	34	37	
3	Nagesh	41	43	48	39	40	39	
4	Ashwin	29	31	33	34	30	28	
5	Farooq	47	46	38	42	49	44	
6	Mrinal	33	35	28	32	30	36	
7	Gowri	27	29	34	31	32	30	
8	Pankaj	16	19	22	17	18	20	

Before learning how to calculate the average marks per subject and the total marks scored by each student, let us first understand the structure of spreadsheets and how to read them.

? Can you tell which cell has the marks obtained by Farooq in Mathematics?

Cells are named and referred to using the column headers labelled A, B, C, … , and row headers labelled 1, 2, 3, … Farooq's score in Mathematics is in cell E5.

? Can you tell what data is in column B7?

? In which subjects has Ashwin scored more than 30 marks?

How can we use spreadsheets to quickly calculate totals and averages? In addition to text and numbers, we can also enter formulae in a cell. We can write a formula that computes the sum or average of a row, or column of cells.

We can describe a row of cells by an expression of the form Start:End, indicating the first and last cell in the row. For instance, Nagesh's marks are described by the expression B3:G3, while Gowri's marks in Odiya, Telugu and English are described by the expression B7:D7. We can use similar expressions to describe columns. For instance, D2:D6 describes the marks in English for the first five students.

We can then write a formula to compute the sum or the average of a row or column. For instance =SUM(B3:G3) calculates the total marks for Nagesh across all subjects, while =AVERAGE(B7:D7) calculates Gowri's average marks across Odia, Telugu and English.

© NCERT not to be republished

H3 | =SUM(B3:G3)

	A	B	C	D	E	F	G	H
1	Name	Odia(R1)	Telugu(R2)	English(R3)	Maths	Social	Science	Total
2	Ratna	25	39	29	36	34	37	250 ×
3	Nagesh	41	43	48	39	40	39	=SUM(B3:G3)
4	Ashwin	29	31	33	34	30	28	
5	Farooq	47	46	38	42	49	44	
6	Mrinal	33	35	28	32	30	36	
7	Gowri	27	29	34	31	32	30	
8	Pankaj	16	19	22	17	18	20	

? What formula would you type to find out the class average marks in Science?

? Find out if the class average marks in Odia is greater than the class average marks in Telugu.

? Show the average marks in other subjects after the last row by typing the appropriate formulae.

Try these out on a computer. You can download the tabular data from this QR code.

? Get the total scores of each student by typing the appropriate formulae.

Note to the Teacher: You can use any spreadsheet software application such as Microsoft Excel, Google Sheets, LibreOffice Calc, etc. If there are not sufficient computers for each student, students can share a computer in groups. If that's not possible, the computer screen can be projected for the whole class if there is only one computer available.

? Figure it Out

Math Talk

1. Find the mean of the following data and share your observations:
   (i) The first 50 natural numbers.
   (ii) The first 50 odd numbers.
   (iii) The first 50 multiples of 4.
2. The dot plot below shows a collection of data and its average; but one dot is missing. Mark the missing value so that the mean is 9 (as shown below).



© NCERT not to be republished

3. Sudhakar, the class teacher, asks Shreyas to measure the heights of all 24 students in his class and calculate the average height. Shreyas informs the teacher that the average height is 150.2 cm. Sudhakar discovers that the students were wearing uniform shoes when the measurements were taken and the shoes add 1 cm to the height.

   (i) Should the teacher get all the heights measured again without the shoes to find the correct average height? Or is there a simpler way?

   (ii) What is the correct average height of the class?

   (a) 174.2 cm (b) 126.2 cm (c) 150.2 cm

   (d) 149.2 cm (e) 151.2 cm (f) None of the above

   (g) Insufficient information

4. The three dot plots below show the lengths, in minutes, of songs of different albums. Which of these has a mean of 5.57 minutes? Explain how you arrived at the answer.



5. Find the median of 8, 10, 19, 23, 26, 34, 40, 41, 41, 48, 51, 55, 70, 84, 91, 92.

Math Talk

   (i) If we include one value to the data (in the given list) without affecting the median, what could that value be?

   (ii) If we include two values to the data without affecting the median what could the two values be?

   (iii) If we remove one value from the data without affecting the median what could the value be?

© NCERT not to be republished

6. Examine the statements below and justify if the statement is always true, sometimes true, or never true.
   (i) Removing a value less than the median will decrease the median.
   (ii) Including a value less than the mean will decrease the mean.
   (iii) Including any 4 values will not affect the median.
   (iv) Including 4 values less than the median will increase the median.

7. The mean of the numbers 8, 13, 10, 4, 5, 20, y, 10 is 10.375. Find the value of y.

8. The mean of a set of data with 15 values is 134. Find the sum of the data.

9. Consider the data: 12, 47, 8, 73, 18, 35, 39, 8, 29, 25, p. Which of the following number(s) could be p if the median of this data is 29?
   (i) 10 (ii) 25 (iii) 40 (iv) 100
   (v) 29 (vi) 47 (vii) 30

10. The number of times students rode their cycles in a week is shown in the dot plot below. Four students rode their cycles twice in that week.



   (i) Find the average number of times students rode their cycles.
   (ii) Find the median number of times students rode their cycles.
   (iii) Which of the following statements are valid? Why?
      (a) Everyone used their cycle at least once.
      (b) Almost everyone used their cycle a few times.
      (c) There are some students who cycled more than once on some days.
      (d) Exactly 5 students have used their cycles more than once on some days.

© NCERT not to be republished

(e) The following week, if all of them cycled 1 more time than they did the previous week, what would be the average and median of the next week's data?

11. A dart-throwing competition was organised in a school. The number of throws participants took to hit the bull's eye (the centre circle) is given in the table below. Describe the data using its minimum, maximum, mean and median.

No. of trials	1	2	3	4	5	6	7	8	9	10
No. of students	1	0	0	1	4	9	12	15	10	10

5.2 Visualising and Interpreting Data

So far we have learnt how to read and make pictographs, bar graphs, clustered-bar graphs, and dot plots. We now examine some more ways of visualising data.

Line Graphs

Temperature

The following figure is a clustered-column graph that shows the monthly maximum temperature in Kerala and Punjab in 2023.



? Now, observe the following graph. Do both these graphs represent the same information?

© NCERT not to be republished



We call such a graph made up of lines a **line graph**. Line graphs are generally used to visualise data across time.

? How do we get the maximum temperature over a month in a state?

There could be a few weather stations across the state that regularly track the local temperature. We can get the monthly maximum temperature by looking at the maximum value among all the values recorded across the state.

When we try to understand how the data is collected or produced, we gain a clearer idea of its scope and can interpret it more meaningfully. It also helps us identify any limitations, such as bias or missing information, and decide how confidently we can draw conclusions from the data.

To identify and interpret the information presented, let us follow a two-step process.

Step 1: Identify what is given

? Notice how the graph is organised, what scale is used, and what patterns the data shows.

- The data for each month for a city is marked and connected by lines to show the change over time. Kerala's data is shown using blue circle marks connected by blue lines and Punjab's data is shown in red.

The different shape markers help in easily distinguishing if the graph is printed in greyscale/black-and-white, or for people who find it difficult to distinguish colour.

© NCERT not to be republished

- The horizontal line shows the months of the year. The vertical line shows the temperature in °C.



Step 2: Infer and interpret from what is given

? Analyse and interpret each of the observations you made. Share appropriate summary/conclusion statements.

- In Punjab, the monthly maximum temperature increases from January to June, reaching a high of 38°C. Then, it reduces to just under 35°C in July, stays mostly flat till September, and then falls continuously till December, reaching about 23°C. January has the lowest among the monthly maximum temperature of about 19°C.
- Kerala's trend is different — it stays mostly flat throughout the year. The peak is around 33°C in April and the lowest point is around 29°C in July. Notice that the monthly maximum temperatures in Kerala are similar both in summer and winter!
- In short, the temperature in Punjab varies more, reaching colder and warmer temperatures than in Kerala.



This can trigger questions in different directions, some of which can be answered using data. Here are some directions to think about —

- Why are the trends so distinct in these two states? What factors determine a region's temperature?
- You might be curious to look at the trends of a few other states. Are there other types of trends that states exhibit?
- Which states show trends similar to Punjab's? Is there anything common between these states?

© NCERT not to be republished

- What would a plot of the monthly minimum temperatures for these states look like?

? What thoughts or questions occur to you?

Math Talk

Space Jam: A Traffic Problem in the Future?

Take a look at the line graph below showing the annual number of objects launched into space.



Source: United Nations Office for Outer Space Affairs (2025)

? What could be the possible method used to derive this data? Discuss.

Math Talk

Step 1: Identify what is given

? Notice how the graph is organised, what scale is used, and what patterns the data shows.

Step 2: Infer from and interpret what is given

? Analyse and interpret each of the observations you made. Once all interpretations are made, summarising/concluding statements can be made.

- In 2024, the worldwide count is around 2800, whereas in 2023, it was around 2900. We can say that 2023 saw the highest number of objects launched into space worldwide (assuming the trend before 2012 was decreasing).
- The counts of the three countries don't add up to the worldwide count. Therefore, we can infer that the counts of other countries are not shown in this visualisation.

© NCERT not to be republished

- For the USA, the increase from 2022 to 2023 is more than from 2023 to 2024. We can say this by looking at how steep the line segments are — the steeper the line is, the greater the increase.

? Which of the following statements are valid inferences?

- From 2012 till 2024, the worldwide count of space object launches increased every year.
- USA is a major contributor in the years 2022 – 24, launching about $\frac{3}{4}$th of the worldwide count.
- Nepal did not launch any object in the period 2012 – 24.
- The combined count of object launches by China and Russia in 2024 is about 400.

? Identify two consecutive years where the worldwide count increased by 2 times or more.

Imagine the same data being shown as a clustered column graph. There would be 13 clusters — one for each year — and within each cluster, 4 columns, making a total of 52 bars! Such a graph would look crowded and difficult to read, making it hard to interpret the trends clearly.

A line graph, on the other hand, is better suited for illustrating changes over time. By connecting data points with line segments, it provides a clear visual representation of trends and variations, allowing the reader to easily track how a parameter evolves across different years.

Catch the (Pattern in) Rain

The following graphs show monthly average rainfall data of a few cities.



© NCERT not to be republished



Source: weather-and-climate.com

? What could be the possible method to compile this data?

This data shows the monthly average rainfall in 6 cities. This means rainfall data is collected over a few years in every city. The total rainfall in a month, say June, across years is averaged to get the monthly average rainfall in June in a city.

? Mark these cities on a map of India. What is common to how they are grouped in the graphs? Share your observations and inferences about the graphs.

Math Talk

Kovalam, Udupi, and Mumbai are along the west coast. Rameswaram, Chennai, and Puri are along the east coast. It appears that regions along the west coast receive more rain.

? Identify the peak months and low months of rainfall for each city.

Udupi, Mumbai, and Kovalam have peak rainfall during June – August. Rameswaram gets most of its rain during October – December. Chennai starts getting rain from June onwards, which peaks in November, and continues till December. Puri, although on the east coast, gets its peak rainfall during July – September. January – March are dry months, with low rainfall, for all the cities. Rameswaram receives very little rain from January – September.

? Read about the south-west monsoon and north-east monsoon and which regions come under the influence of these and when.

© NCERT not to be republished

Figure it Out

1. The average number of customers visiting a shop and the average number of customers actually purchasing items over different days of the week is shown in the table below. Visualise this data on a line graph.

	Mon	Tue	Wed	Thu	Fri	Sat	Sun
Visiting	16	19	10	14	20	22	35
Purchasing	10	8	7	11	12	16	26

2. The average number of days of rainfall in each month for a few cities is shown in the table below:

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Mangaluru	0.1	0	0.1	1.8	6.2	24.1	27.7	24.5	14	8.8	3.9	0.9
New Delhi												
Port Blair	2.4	1.3	0.9	3.3	15.5	18.7	17.3	18.8	16.8	14.1	11.3	5.4
Rameswaram	2.6	1.3	1.9	3.4	2.5	0.4	1	1	1.9	8.1	10.4	7.8

(i) What could be the possible method to compile this data?

(ii) Mark the data for Mangaluru, Port Blair, and Rameswaram in the line graph shown below. You can round off the values to the nearest integer.



Source: weather-and-climate.com

© NCERT not to be republished

(iii) Based on the line for New Delhi in the graph fill the data in the table.

(iv) Which city among these receives the most number of days of rainfall per year? Which city gets the least number of days of rainfall per year?

(v) Looking at the table, when is the rainy season in New Delhi and Rameswaram?

2. The following line graph shows the number of births in every month in India over a time period:



Source: Nambiar et al (Forthcoming) – "Seasonal variations in births in India"

(i) What are your observations?

(ii) What was the approximate number of births in July 2017?

(iii) What time period does the graph capture?

(iv) Compare the number of births in the month of January in the years 2018, 2019, and 2020.

(v) Estimate the number of births in the year 2019.

Infographics

In Grade 6, we saw an example of how infographics can be used to communicate information and insights more clearly and quickly in a visually appealing way. Take a look at the following infographic. Are you able to understand the information presented here?

© NCERT not to be republished



This infographic compares the preference between rice and wheat in different states. The colour scale at the top right indicates how to interpret the different shades in terms of preferences.

The difference between the per capita consumption of rice and wheat is mapped to values between –100 and +100. A value of +100 doesn't mean that the state doesn't consume wheat at all. It means that this state prefers mostly rice and the difference between per capita rice and wheat consumption is the highest. Isn't it interesting how there is a clear geographical split in preferences of rice vs. wheat shown by the red line?

? Share your observations. Based on this infographic, answer the following:

(i) The value of Karnataka is hidden. Can you guess what it could be?

(ii) Which are the top 5 states where rice is the most popular?

(iii) Which are the top 5 states where wheat is the most popular?

(iv) List a few states where the preference between rice and wheat is more or less balanced.

© NCERT not to be republished



What can a Strip Say?

Manoj has an interesting hobby. He makes note of what he does throughout the day. He records his activities by colouring a strip of paper with 48 boxes, marking time in 30 minute intervals from midnight to midnight.

He has recorded five types of activities for three different days of the week on three coloured strips, shown to the right.



(i) Sleeping

(ii) Eating

(iii) Meeting friends, hobbies, media, time with family

(iv) Attending classes, studying and homework

(v) Showering and getting dressed, yoga or exercise

(vi) Travelling

? Look at the three coloured strips carefully.

(i) What activity does each colour stand for?

(ii) The three strips correspond to the days Friday – Sunday in some order. Which day do you think each strip represents?

(iii) On one of these days, he went out with friends to watch a long movie. When do you think this happened?

(iv) At what time does his school break for lunch?

(v) What more can the strips tell us?

© NCERT not to be republished

What would your strip for a weekday look like? How similar or different is it to Manoj's?

Try This

What would a strip of your typical day during your vacation look like? How similar/different would it look?

Math Talk

What would a strip for any of the adults in your family look like? Make a strip of a day for any adult at home. Compare your strip with theirs. What do you find interesting?

Data Story: Sleepy-Deepy

Do you remember the sleep time pie chart from the Proportionality chapter?

Isn't it amusing that there are animals that sleep as little as 2 hours per day and animals that sleep as much as 20 hours per day? How about insects — have you seen any insect sleep/rest? Humans typically sleep for about 7 – 9 hours a day. The sleep duration can vary greatly among people. The amount of sleep people need depends on age, living conditions, lifestyle (food they consume, the activities they engage in, etc.) among other factors. You may have observed that babies sleep longer than adults.

The line graphs below show typical sleep durations of Indians across ages 6 to 75. The second picture is a zoomed-in version of the first picture.

Night sleep across ages



Night sleep across ages



Source: National Time Use Survey 2024

© NCERT not to be republished

Share your observations on this graph. What do you find interesting?

Unlike the earlier graphs that were made up of a few connected line segments, this line graph looks like a smooth curve because it contains 80 data points that are placed very close to each other. Representing the same data using a column graph would require 70 columns, making the graph look cluttered and heavy. A line graph is a better choice here. It is light and captures the pattern well.

From the graph we can see that the average sleep time for 6-year olds is about 9.5 hours per day. The daily sleep time decreases as we grow through teenage years and step into adulthood, touching about 8 hours a day between ages 30 and 50. After 50, the daily sleep time increases, reaching about 8.5 hours.

You might wonder — why do newborns and infants sleep for so long? Do people in different countries sleep differently? Do animals also exhibit such patterns in sleep durations across age?

Figure it Out

1. Mean Grids:



   (i) Fill the grid with 9 distinct numbers such that the average along each row, column, and diagonal is 10.

   (ii) Can we fill the grid by changing a few numbers and still get 10 as the average in all directions?

2. Give two examples of data that satisfy each of the following conditions:

   (i) 3 numbers whose mean is 8.

   (ii) 4 numbers whose median is 15.5.

   (iii) 5 numbers whose mean is 13.6.

   (iv) 6 numbers whose mean = median.

   (v) 6 numbers whose mean > median.

3. Fill in the blanks such that the median of the collection is 13: 5, 21, 14, _____, _____, _____. How many possibilities exist if only counting numbers are allowed?

4. Fill in the blanks such that the mean of the collection is 6.5: 3, 11, ____, ____, 15, 6. How many possibilities exist if only counting numbers are allowed?

5. Check whether each of the statements below is true. Justify your reasoning. Use algebra, if necessary, to justify.

   (i) The average of two even numbers is even.

   (ii) The average of any two multiples of 5 will be a multiple of 5.

   (iii) The average of any 5 multiples of 5 will also be a multiple of 5.

© NCERT not to be republished

6. There were 2 new admissions to Sudhakar's class just a couple of days after the class average height was found to be 150.2 cm.

   (i) Which of the following statements are correct? Why?

   (a) The average height of the class will increase as there are 2 new values.

   (b) The average height of the class will remain the same.

   (c) The heights of the new students have to be measured to find out the new average height.

   (d) The heights of everyone in the class has to be measured again to calculate the new average height.

   (ii) The heights of the two new joinees are 149 cm and 152 cm. Which of the following statements about the class' average height are correct? Why?

   (a) The average will remain the same.

   (b) The average will increase.

   (c) The average will decrease.

   (d) The information is not sufficient to make a claim about the average.

   (iii) Which of the following statements about the new class average height are correct? Why?

   (a) The median will remain the same.

   (b) The median will increase.

   (c) The median will decrease.

   (d) The information is not sufficient to make a claim about median.

7. Is 17 the average of the data shown in the dot plot below? Share the method you used to answer this question.

Math Talk



8. The weights of people in a group were measured every month. The average weight for the previous month was 65.3 kg and the median weight was 67 kg. The data for this month showed that

Math Talk

© NCERT not to be republished

one person has lost 2 kg and two have gained 1 kg. What can we say about the change in mean weight and median weight this month?

9. The following table shows the retail price (in ₹) of iodised salt in the month of January in a few states over 10 years. For your calculations and plotting you may round off values to the nearest counting number.

	Andaman and Nicobar Islands	Assam	Gujarat	Mizoram	Uttar Pradesh	West Bengal
2016	16	6	16.5	20	16.15	9.47
2017	12	12	14.75	20	16.97	11.65
2018	12	12	14.75	22	16.18	11.63
2019	12	12	14.75	22	18.24	11.43
2020	13.88	12	13	20	18.96	11.11
2021	18.22	15	14.45	22	20.63	12.79
2022	18.73	14	14.28	25	21.3	16.14
2023	20.63	12.02	14.54	27.65	25.39	18.43
2024	19.73	13.72	14.8	29.03	26.9	21.66
2025	20.99	12.35	19.2	29.8	24.81	23.99

(i) Choose data from any 3 states you find interesting and present it through a line graph using an appropriate scale.

(ii) What do you find interesting in this data? Share your observations.

(iii) Compare the price variation in Gujarat and Uttar Pradesh.

(iv) In which state has the price increased the most from 2016 to 2025?

(v) What are you curious to explore further?

© NCERT not to be republished

10. Referring to the graph below, which of the following statements are valid? Why?



(i) In 1983, the majority in rural areas used kerosene as a primary lighting source while the majority in urban areas used electricity.

(ii) The use of kerosene as a primary lighting source has decreased over time in both rural and urban areas.

(iii) In the year 2000, 10% of the urban households used electricity as a primary lighting source.

(iv) In 2023, there were no power cuts.

11. Answer the following questions based on the line graph.

(i) How long do children aged 10 in urban areas spend each day on hobbies and games?

(ii) At what age is the average time spent daily on hobbies and games by rural kids 1.5 hours?

(a) 8 years

(b) 10 years

(c) 12 years

(d) 14 years

(e) 18 years



© NCERT not to be republished

(iii) Are the following statements correct?

(a) The average time spent daily on hobbies and games by kids aged 15 is twice that of kids aged 10.

(b) All rural kids aged 15 spend at least 1 hour on hobbies and games everyday.

12. Individual project: Make your own activity strip for different days of the week.

(i) Do you eat and sleep at regular times every day? Typically how long do you spend outdoors?

(ii) Calculate the average time spent per activity. Represent this average day using a strip.

(iii) Similarly, track the activities of any adult at home. Compare your data with theirs.

Try This

13. Small group project: Make a group of 3 – 4 members. Do at least one of the following:

(i) Track daily sleep time of all your family members for a week. Daily sleep time includes night sleep, naps, and any sleep during the day.

(a) Represent this on strips.

(b) Put together the data of all your group members. Calculate the average and median sleep time of children, adults, elderly.

(c) Share your findings and observations.

(ii) When do schools start and end? On a weekday, Manoj's school starts at 9:30 am and ends at 4:30 pm, i.e., 7 hours which include class time and breaks. Collect information on the daily timings of different schools for Grade 8, including class time and break time (the schools can be anywhere in the country. You can ask your neighbours, relatives, parents and friends to find out). Analyse and present the data collected.

14. The following graphs show the sunrise and sunset times across the year at 4 locations in India. Observe how the graphs are organised. Are you able to identify which lines indicate the sunrise and which indicate the sunset?

© NCERT not to be republished



Answer the following questions based on the graphs:

(i) At which place does the sun rise the earliest in January? What is the approximate day length at this place in January?

(ii) Which place has the longest day length over the year?

(iii) Share your observations—what do you find interesting? What are you curious to find out?

15. We all know the typical sunrise and sunset timings. Do you know when the moon rises and sets? Does it follow a regular pattern like the sun? Let's find out. The following graph shows the moonrise and moonset time over a month:

Try This

(i) Find out on what dates *amavasya* (new moon) and *purnima* (full moon) were in this month.

(ii) What do you notice? What do you wonder?



© NCERT not to be republished

SUMMARY

- Last year we looked at mean as a fair-share. Here, we learnt how the sum of the distances of the values to its left and right are the same.
- We saw that when values greater than the mean are inserted, the mean increases. When values less than the mean are inserted, the mean decreases. Similar phenomena can be observed with the median.
- Line graphs can be used to visualise change over time.
- We saw that examining data can lead to new questions and directions to probe further.

© NCERT not to be republished

Game of Hex

Hex is a two-player strategy game played on a rhombus-shaped board made of hexagonal cells, usually of size 11 × 11. Each player is assigned a colour and two opposite sides of the board. Players take turns placing a piece of their colour on any empty cell. Once placed, pieces can not be moved or removed. The objective is to create an unbroken chain of one's own pieces connecting the two assigned sides. The first player to complete such a connection wins the game. The pictures below show two possible gameplays where blue wins in the first and red wins in the second board.

Here is an empty board. You can use pencils to play each round and erase the marks to play a fresh round.



© NCERT not to be republished

6 ALGEBRA PLAY

0889CH06

6.1 Algebra Play

Over the last two years, we have used algebra to model different situations. We have learned how to solve algebraic equations and find the values of unknown letter-numbers. Let's now have some fun with algebra. We shall investigate tricks and puzzles, and explain why they work using algebra. We will also see how to invent new tricks and puzzles to entertain others.

6.2 Thinking about 'Think of a Number' Tricks

In Grade 7, we learned about 'Think of a Number' tricks, like this one.

1. Think of a number.
2. Double it.
3. Add four.
4. Divide by two.
5. Subtract the original number you thought of.

? I predict you get 2. Am I right? Try it out with different starting numbers. Do you always end up with the same value, 2? Why?

We saw that we can understand such tricks through algebra.

1. Think of a number: x
2. Double it: $2x$
3. Add four: $2x + 4$
4. Divide by 2: $x + 2$
5. Subtract the original number you thought of: $x + 2 - x = 2$

Therefore, no matter what the starting number is, the end result will always be 2!

© NCERT not to be republished

? How would you change this game to make the final answer 3? What about 5?

? Can you come up with more complicated steps that always lead to the same final value?

Let us now look at a different trick of this type.

? How did Shubham figure out the date chosen by Mukta?

- Let the month be M and the day be D.
- Multiply M by 5: $5M$

© NCERT not to be republished

- Add 6: $5M + 6$
- Multiply by 4: $20M + 24$
- Add 9: $20M + 33$
- Multiply by 5: $100M + 165$
- Add the day: $100M + 165 + D$

Mukta's answer was 291.

- $291 = 100M + 165 + D$
- $291 - 165 = 100M + D$
- $126 = 100M + D$

Since D is a day within a month, it is atmost 31 and requires only 2 digits. So the last 2 digits are D and what comes before that is M. In this case, M is 1 and D is 26, i.e., the 26th of January.

? Mukta thinks of another date, follows the same steps, and reports her answer as 1390. What date did Mukta start with this time?

- Subtracting 165 from 1390, we get 1225.
- This means that the date she thought of was 25th December.

? Find the dates if the final answers are the following:

(i) 1269

(ii) 394

(iii) 296

You can try this trick with your friends. Ask them to choose the starting date as their birthday.

? Can you change the steps in this trick and still find the original date? Instead of subtracting 165 from the final answer, you might have to subtract some other number.

Math Talk

? Try to devise your own 'Think of a Number' trick.

Math Talk

6.3 Number Pyramids

In a number pyramid, each number is the sum of the two numbers directly below it (see the figure).



© NCERT not to be republished

? Use the same rule to fill these pyramids:



? How do we fill this pyramid?













? What about filling in the numbers in this pyramid? Where do we start?



© NCERT not to be republished

Let us fill the empty boxes with letter-numbers.



From the rules for filling up pyramids, we get the following equations.

- $a + b = 60$
- $12 + c = a$
- $c + 8 = b$

From this, we see that,

- $(12 + c) + (c + 8) = a + b = 60$

Hence,

- $20 + 2c = 60$
- $2c = 60 - 20 = 40$
- $c = 20$.

Once we know c, we can find a and b, and complete the pyramid.



? Fill the following pyramids:







? What is the relationship between the numbers in the bottom row and the number at the top?

Let us start with the simplest pyramid.



© NCERT not to be republished

What about a pyramid with three rows?

Using letter numbers for the bottom row, we can write an expression for the top row.



Figure it Out

1. Without building the entire pyramid, find the number in the topmost row given the bottom row in each of these cases.

4	13	8

7	11	3

10	14	25

2. Write an expression for the topmost row of a pyramid with 4 rows in terms of the values in the bottom row.

3. Without building the entire pyramid, find the number in the topmost row given the bottom row in each of these cases.

8	19	21	13

7	18	19	6

9	7	5	11

Recall the Virahāṅka-Fibonacci number sequence 1, 2, 3, 5, ... where each number is the sum of the two numbers before it.

4. If the first three Virahāṅka-Fibonacci numbers are written in the bottom row of a number pyramid with three rows, fill in the rest of the pyramid. What numbers appear in the grid? What is the number at the top? Are they all Virahāṅka-Fibonacci numbers?

5. What can you say about the numbers in the pyramid and the number at the top in the following cases?

   (i) The first four Virahāṅka-Fibonacci numbers are written in the bottom row of a four row pyramid.

   (ii) The first 29 Virahāṅka-Fibonacci numbers are written in the bottom row of a 29 row pyramid.

6. If the bottom row of an n row pyramid contains the first n Virahāṅka-Fibonacci numbers, what can we say about the numbers in the pyramid? What can we say about the number at the top?

© NCERT not to be republished

6.4 Fun with Grids

Calendar Magic

A page from a calendar is given below. Your friend picks a 2 × 2 grid from this calendar, adds the 4 numbers in this grid and tells you the sum.

AUGUST 2025						
SUN	MON	TUE	WED	THU	FRI	SAT
					1	2
3	4	5	6	7	8	9
10	11	12	13	14	15	16
17	18	19	20	21	22	23
24	25	26	27	28	29	30
31						

6	7
13	14

6 + 7 + 13 + 14 = 40

? Can we find the 4 numbers in the grid from just knowing this sum?

Let us use algebra. Consider a 2 × 2 grid. Let a represent the top left number. What are the other numbers in terms of a?

a	$a + 1$
$a + 7$	$a + 8$

Adding all four numbers, the sum is $a + (a + 1) + (a + 7) + (a + 8) = 4a + 16$.

? Suppose you are told that the sum is 36. Can you find the 4 numbers in the grid?

- $4a + 16 = 36$
- $4a = 20$ (subtracting 16 from both sides)
- $a = 5$ (dividing both sides by 4)

Now that we have found a, we know that the other three numbers are $a + 1$, $a + 7$ and $a + 8$. Therefore, the grid must be the following:

5	6
12	13

© NCERT not to be republished

? Create your own calendar trick. For instance, choose a grid of a different size and shape.

Math Talk

AUGUST 2025						
SUN	MON	TUE	WED	THU	FRI	SAT
					1	2
3	4	5	6	7	8	9
10	11	12	13	14	15	16
17	18	19	20	21	22	23
24	25	26	27	28	29	30
31						



2	3	4	5	6	7	8	9	10
12	13	14	15	16	17	18	19	20
22	23	24	25	26	27	28	29	30
32	33	34	35	36	37	38	39	40
42	43	44	45	46	47	48	49	50

Algebra Grids

In the following grid, shapes represent numbers. In each row, the last column is the sum of the values to its left. How do we find the values of the shapes?



■ + ■ + ■ = 27

So, ■ = 9

Now, ● + ● + ■ = 19

● + ● + 9 = 19

2 × ● + 9 = 19

● = 5

? In the following grids, find the values of the shapes and fill in the empty squares:





6.5 The Largest Product

? Fill the digits 2, 3, and 5 in □□ × □, using each digit once. What is the largest product possible?

© NCERT not to be republished

Let us approach this problem systematically. There are six ways to place three digits:

- We can fill the first box with 2, 3 or 5.
- For each of these choices, we have 2 ways of filling the remaining 2 digits.
- The six options are 23 × 5, 25 × 3, 32 × 5, 35 × 2, 52 × 3, 53 × 2.

? How do we find the largest product among these six options?

We can group them in pairs where the multiplier is the same.

- 35 × 2 and 53 × 2
- 25 × 3 and 52 × 3
- 23 × 5 and 32 × 5

In each pair, the one with the larger multiplicand generates the larger product, so we can reduce the comparison to these three expressions.

- 53 × 2
- 52 × 3
- 32 × 5

It is clear that 52 × 3 is bigger than 53 × 2, so we only need to compare 52 × 3 and 32 × 5. Let us expand these.

- 32 × 5 = (3 × 10 × 5) + (2 × 5)
- 52 × 3 = (5 × 10 × 3) + (2 × 3)

The first terms in both expressions are the same. The second term shows that 32 × 5 is larger, and hence the largest of the six possible products we can form with 2, 3 and 5.

? In this case, we used the largest digit as the multiplier. The other two digits were arranged in decreasing order to form the multiplicand. Will this always be the case? Let us find out using algebra.

Suppose p, q, and r are the three digits such that $p < q < r$.

As before, we have six possible products, which we group by the multiplier:

- $qr \times p$, $rq \times p$
- $pr \times q$, $rp \times q$
- $pq \times r$, $qp \times r$

In each pair, the multiplicand with the larger tens digit forms the larger product. So we have three products to compare:

- $rq \times p$
- $rp \times q$
- $qp \times r$

© NCERT not to be republished

Since $q > p$, we can see that $rp \times q$ is bigger than $rq \times p$. This leaves us with a comparison between $qp \times r$ and $rp \times q$. If we expand these, we get

- $qp \times r = (10 \times q \times r) + (p \times r)$
- $rp \times q = (10 \times r \times q) + (p \times q)$

Once again, the first term is the same in both expressions. Since $r > q$ the second term of the first expression is larger, so the largest product is $qp \times r$. This matches our earlier observation that the largest digit should be the multiplier and the other two digits should be arranged in decreasing order to form the multiplicand.

Figure it Out

1. Fill the digits 1, 3, and 7 in $\square\square \times \square$ to make the largest product possible.
2. Fill the digits 3, 5, and 9 in $\square\square \times \square$ to make the largest product possible.

6.6 Decoding Divisibility Tricks

It is now Mukta's turn to show a mathematics trick to Shubham.

© NCERT not to be republished

If we choose other 2-digit numbers, and follow the steps, will there always be no remainder?

Let's try to understand how Mukta's trick works.

Suppose the two-digit number is ab. When it is reversed, the new number is ba.

- If $b > a$, then $ba > ab$. So, the difference is

  $(10b + a) - (10a + b)$

  $= 10b - b - 10a + a$

  $= 9b - 9a = 9\,(b - a)$.

The difference is divisible by 9.

Can you work out what happens if $a > b$?

Figure it Out

1. In the trick given above, what is the quotient when you divide by 9? Is there a relationship between the two numbers and the quotient?

2. In the trick given above, instead of finding the difference of the two 2-digit numbers, find their sum. What will happen? For example:
   - We start with 31. After reversing we get 13. Adding 31 and 13, we get 44.
   - We start with 28. After reversing we get 82. Adding 28 and 82, we get 110.
   - We start with 12. After reversing we get 21. Adding 12 and 21, we get 33.

   Observe that all these numbers are divisible by 11. Is this always true? Can we justify this claim using algebra?

3. Consider any 3-digit number, say abc ($100a + 10b + c$). Make two other 3-digit numbers from these digits by cycling these digits around, yielding bca and cab. Now add the three numbers. Using algebra, justify that the sum is always divisible by 37. Will it also always be divisible by 3? [**Hint:** Look at some multiples of 37.]

Math Talk

4. Consider any 3-digit number, say abc. Make it a 6-digit number by repeating the digits, that is $abcabc$. Divide this number by 7, then by 11, and finally by 13. What do you get? Try this with other numbers. Figure out why it works. [**Hint:** Multiply 7, 11 and 13.]

5. There are 3 shrines, each with a magical pond in the front. If anyone dips flowers into these magical ponds, the number of flowers doubles. A person has some flowers. He dips them all in the first pond and then places some flowers in shrine 1. Next, he dips the remaining flowers in the second pond and places

© NCERT not to be republished

some flowers in shrine 2. Finally, he dips the remaining flowers in the third pond and then places them all in shrine 3. If he placed an equal number of flowers in each shrine, how many flowers did he start with? How many flowers did he place in each shrine?

6. A farm has some horses and hens. The total number of heads of these animals is 55 and the total number of legs is 150. How many horses and how many hens are on the farm?

   Can you solve this without letter-numbers?

   Math Talk

   [**Hint:** If all the 55 animals were hens, then how many legs would there be? Using the difference between this number and 150, can you find the number of horses?]

7. A mother is 5 times her daughter's age. In 6 years' time, the mother will be 3 times her daughter's age. How old is the daughter now?

8. Two friends, Gauri and Naina, are cowherds. One day, they pass each other on the road with their cows. Gauri says to Naina, "You have twice as many cows as I do". Naina says, "That's true, but if I gave you three of my cows, we would each have the same number of cows". How many cows do Gauri and Naina have?

9. I run a small dosa cart and my expenses are as follows:
   - Rent for the dosa cart is ₹5000 per day.
   - The cost of making one dosa (including all the ingredients and fuel) is ₹10.

   (i) If I can sell 100 dosas a day, what should be the selling price of my dosa to make a profit of ₹2000?

   (ii) If my customers are willing to pay only ₹50 for a dosa, how many dosas should I aim to sell in a day to make a profit of ₹2000?

10. Evaluate the following sequence of fractions:

    $\frac{1}{3}, \frac{(1+3)}{(5+7)}, \frac{(1+3+5)}{(7+9+11)}$

    What do you observe? Can you explain why this happens?

    [**Hint:** Recall what you know about the sum of the first n odd numbers.]

© NCERT not to be republished

11. **Karim and the Genie**

Karim was taking a nap under a tree. He had a dream about a magical lamp and a genie. He heard a voice saying, "I have come to serve you, Oh master". He woke up and to his surprise, it was a genie!

"Do you want to make money?", asked the genie. Karim nodded dumbly in bewilderment. The genie continued, "Do you see the banyan tree over there? All you have to do is go around it once. The money in your pocket will double".

Karim immediately started towards the tree, only to be stopped by the genie. "One moment!", said the genie. "Since I am bringing you great riches, you should share some of your gains with me. You must give me 8 coins each time you go around the tree."

Thinking that was a trifling amount, Karim readily agreed.

He went around the tree once. Just as the genie had said, the number of coins in his pocket doubled! He gave 8 coins to the genie. He made another round. Again the number of coins doubled. He gave 8 more coins to the genie. He went around the tree for the third time. The number of coins doubled again, but to his horror, he was left with only 8 coins, exactly the number of coins he owed the genie!

As Karim began to wonder how the genie tricked him, the genie let out a loud laugh and disappeared.

(i) How many coins did Karim initially have?

(ii) For what cost per round should Karim agree to the deal, if he wants to increase the number of coins he has?

(iii) Through its magical powers, the genie knows the number of coins that Karim has. How should the genie set the cost per round so that it gets all of Karim's coins?

Math Talk

SUMMARY

- Algebra is very useful in modeling and understanding numerical scenarios. Because of this, it occurs in almost all areas of mathematics, science and beyond.
- Algebra is an indispensable tool in justifying mathematical statements.
- We applied algebra to analyse 'Think of a Number' tricks, number pyramids, grids, ways of forming numbers using given digits to maximise certain products, divisibility tricks, and various other problems.

© NCERT not to be republished

7 AREA

0889CH07

7.1 Rectangle and Squares

? How many different ways can you divide a square into 4 parts of equal area?

One can actually think of infinitely many such ways! Consider a division, such as —



and alter each part as follows.



In each part, the area is compressed along one edge and expanded along another edge. If both the compression and expansion are of the same magnitude, then all 4 parts still have the same area!

? Try to think of different creative ways to divide a square into 4 parts of equal area.

Math Talk

© NCERT not to be republished

You might have seen the rangoli art form, in which regions of different shapes are beautifully coloured using rangoli powder.

? Which of these rectangles requires more rangoli powder to be coloured, if the colouring is done evenly?



We can answer this by counting the number of non-overlapping unit squares (squares of sidelength 1 cm in this case) that can be packed into each of the rectangles.

Clearly, the rectangle having sidelengths 7 cm and 4 cm contains 7 × 4 = 28 unit squares, and the rectangle having sidelengths 8 cm and 3 cm contains 8 × 3 = 24 unit squares.

Thus, the rectangle of sidelengths 7 cm and 4 cm requires more powder to be coloured.

Recall that we measure the area of a region by finding the number of unit squares (which can also be a fraction) whose area equals that of the given region.

We have seen that the number of unit squares contained in a rectangle is given by the product of its length and width —

Area of a rectangle = length × width.

The areas of the rectangles as seen in the previous problem are generally written as 28 sq. cm and 24 sq. cm, or as 28 cm^2 and 24 cm^2.

© NCERT not to be republished

What is the area of each triangle in this rectangle?



We have seen that the diagonal of a rectangle divides it into two congruent triangles. So, the area of each triangle is half the area of the rectangle.

In terms of unit squares, half the area fills exactly half the number of unit squares.

So the area of each triangle is $\frac{1}{2} \times 7 \times 4 = 14$ cm^2.

Why Can't Perimeter be a Measure of Area?

Why do we count the number of unit squares to assign measures for area? Couldn't we have just used the perimeter of a region, i.e., the length of its boundary as a measure of its area?

If two regions have the same perimeter, can't we conclude that they have the same area? Or, if one region has a larger perimeter than another region, can't we conclude that it also has a larger area?

The perimeter of a region is not indicative of its area. The reason is that regions can have the same perimeter but different areas, and vice versa. We can even find two regions, Region 1 and Region 2, such that

Perimeter of Region 1 > Perimeter of Region 2, but

Area of Region 1 < Area of Region 2.

Find two rectangles that are examples of such regions. If needed, use a grid paper (given at the end of the book) for this.

Also give an example of two regions of other shapes, where the region with the larger perimeter has the smaller area! This property should be visually clear in your example.

Math Talk

Figure it Out

1. Identify the missing sidelengths.

(i)



(ii)



© NCERT not to be republished

2. The figure shows a path (the shaded portion) laid around a rectangular park EFGH.



(i) What measurements do you need to find the area of the path? Once you identify the lengths to be measured, assign possible values of your choice to these measurements and find the area of the path. Give a formula for the area.

An example of a formula — *Area of a rectangle = length × width.*

[**Hint:** There is a relation between the areas of EFGH, the path, and ABCD.]

(ii) If the width of the path along each side is given, can you find its area? If not, what other measurements do you need? Assign values of your choice to these measurements and find the area of the path. Give a formula for the area using these measurements.

[**Hint:** Break the path into rectangles.]

(iii) Does the area of the path change when the outer rectangle is moved while keeping the inner rectangular park EFGH inside it, as shown?



3. The figure shows a plot with sides 14m and 12m, and with a crosspath. What other measurements do you need to find the area of the crosspath? Once you identify the lengths to be measured, assign some possible values of your choice and find the area of the path. Give a formula for the area based on the measurements you choose.

Math Talk



© NCERT not to be republished

4. Find the area of the spiral tube shown in the figure. The tube has the same width throughout.



[**Hint:** There are different ways of finding the area. Here is one method.]



What should be the length of the straight tube if it is to have the same area as the bent tube on the left?

5. In this figure, if the sidelength of the square is doubled, what is the increase in the areas of the regions 1, 2 and 3? Give reasons.



6. Divide a square into 4 parts by drawing two perpendicular lines inside the square as shown in the figure.



Rearrange the pieces to get a larger square, with a hole inside.

You can try this activity by constructing the square using cardboard, thick chart paper, or similar materials.

Math Talk

© NCERT not to be republished

Triangles

? In the given figure, which triangle has a greater area: ΔXDC or ΔYDC, if both the rectangles are identical?



? In the given figure, which triangle has a greater area: ΔXDC or ΔYBC, if both the rectangles are identical?



In each case, by dropping the altitudes from X and Y, it becomes clear that each triangle has exactly half the area of the rectangle ABCD.

? Find the area of Δ XDC.



Fig. 7.1

? To find the area of a triangle, what measurements do we need?

We need the sidelengths of the outer rectangle, as in Fig. 7.1.

? How do we get the outer rectangle from the given triangle?



© NCERT not to be republished

BCDE is a rectangle (how?). Let us take its sidelengths to be height and base.
Then,



$$Area\ (\Delta ABC) = \frac{1}{2} \times base \times height$$

Since BXAE is a rectangle (how?), the height of the rectangle is the same as the height of the triangle.

Thus, if the height and the base of a triangle are known, we can find its area.



$$Area\ of\ a\ triangle = \frac{1}{2} \times base \times height.$$

? Will this formula hold for the kind of triangle, around which we cannot draw a rectangle with BC as the base?



Here is one way to look at it. The area of ΔABC is the difference of the areas of ΔADC and ΔADB, each of which can be enclosed in a rectangle, as in Fig. 7.1.

$$\text{Area } (\Delta ABC) = \frac{1}{2} \times h \times DC - \frac{1}{2} \times h \times DB$$

$$= \frac{1}{2} \times h\ (DC - DB)$$

$$= \frac{1}{2} \times h \times BC$$

Thus, the area formula holds for all types of triangles.

© NCERT not to be republished

Some Applications of the Area Formula



? Find BY.

BY can be found using the formula for the area of a triangle.

What is Area (ΔABC)?

$$\text{Area } (\Delta ABC) = \frac{1}{2} \times AX \times BC = \frac{15}{2} \text{ sq. units.}$$

The area of the triangle can also be written as

$$\text{Area } (\Delta ABC) = \frac{1}{2} \times BY \times AC = \frac{1}{2} \times 4 \times BY = 2\,BY.$$

Thus,

$$2\,BY = \frac{15}{2}.$$

$$\text{So, } BY = \frac{15}{4} = 3.75 \text{ units.}$$

? Are the 4 triangles obtained by drawing the diagonals of a rectangle (regions 1 – 4 in the figure) of equal areas?



Clearly, the triangles 1 – 4 are not four congruent triangles.

To compare their areas, let us consider any two adjacent triangles, say 1 and 2.



Since the area of a triangle depends on its height and the base, let us consider suitable height-base pairs in each of the triangles. If OD and OB are taken as the bases, then we see that both triangles have the same altitude!

We also have OB = OD, since the diagonals of a rectangle bisect each other. So, the triangles 1 and 2 have equal areas.

Arguing this way, we can show that all four triangles have equal areas.

From this problem, we can make the following general statement.

In a triangle, the line joining a vertex to the midpoint of its opposite side divides the triangle into two triangles of equal areas.



Triangles 1 and 2 have equal areas as they have the same measures for height and base

© NCERT not to be republished

Triangles between Parallel Lines with a Common Base



? Line $l \| BC$. Consider the different triangles that have BC as their base, and with their third vertex lying anywhere on l.

(i) Which of these triangles has the maximum area, and which has the minimum area?

(ii) Which of these triangles has the maximum perimeter, and which has the minimum perimeter?

Here, we will only show how to find the triangle with the minimum perimeter, and leave the other questions as exercises.

Intuition might suggest that the triangle with the minimum perimeter can be obtained by constructing the perpendicular bisector of BC.

But how do we justify that this triangle has the least perimeter among all the triangles?



Firstly, note that in all these triangles, BC is a common side. Therefore, it is enough to consider the sum of the other two sides.

Let us imagine the line l as a mirror. Then we get a reflection of all the points and lines below it.

While studying the properties of a plane mirror, we experimentally observed that the distance of the image behind the mirror is the same as the distance of the object (that creates the image) in front of the mirror. This law can be used to locate the reflections of the points lying below the line l.

© NCERT not to be republished

? What can we say about the lengths of AB and its reflection AB′?

Since ΔAXB ≅ ΔAXB′, AB = AB′.

Similarly, AC = AC′.

Therefore, the length of the path B → A → C is the same as the length of the path B → A → C′.





This is true no matter where point A is on line *l*.

So, finding point A that gives the shortest possible path B →A →C is the same as finding a point A that gives the shortest possible path B →A →C′.

But the solution to the latter problem is clear — choose A on the straight line BC′, since BC′ is the shortest possible path from B to C′.

Therefore, this triangle ΔABC has the minimum perimeter.



? Analyse whether A lies on the perpendicular bisector of BC.

Math Talk

? Figure it Out

1. Find the areas of the following triangles:



(i)



(ii)



(iii)

© NCERT not to be republished

2. Find the length of the altitude BY.



3. Find the area of ΔSUB, given that it is isosceles, SE is perpendicular to UB, and the area of ΔSEB is 24 sq. units.



In the *Śulba-Sūtras*, which are ancient Indian geometric texts that deal with the construction of altars, we can find many interesting problems on the topic of areas. When altars are built, they must have the exact prescribed shape and area. This gives rise to problems of the kind where one has to transform a given shape into another of the same area. The *Śulba-Sūtras* give solutions to many such problems.

Such problems are also posed and solved in Euclid's Elements. Here are two problems of this kind.

4. [*Śulba-Sūtras*] Give a method to transform a rectangle into a triangle of equal area.

5. [*Śulba-Sūtras*] Give a method to transform a triangle into a rectangle of equal area.

6. ABCD, BCEF, and BFGH are identical squares.

   (i) If the area of the red region is 49 sq. units, then what is the area of the blue region?

   (ii) In another version of this figure, if the total area enclosed by the blue and red regions is 180 sq. units, then what is the area of each square?

Math Talk



© NCERT not to be republished

7. If M and N are the midpoints of XY and XZ, what fraction of the area of ΔXYZ is the area of ΔXMN? [**Hint:** Join NY]

Try This



8. Gopal needs to carry water from the river to his water tank. He starts from his house. What is the shortest path he can take from his house to the river and then to the water tank? Roughly recreate the map in your notebook and trace the shortest path.

Math Talk



Area of any Polygon

? How do we find the area of this quadrilateral? What measurements do we need for this?



If we join BD, the quadrilateral ABCD gets divided into two triangles. By finding their areas, we can find the area of ABCD.

? How do we find the area of this pentagon?



? Can any polygon be divided into triangles?

It can be seen that any polygon can be divided into triangles. Thus, by knowing how to compute the area of a triangle, we can find the area of any polygon.

© NCERT not to be republished

Figure it Out

1. Find the area of the quadrilateral ABCD given that AC = 22 cm, BM = 3 cm, DN = 3 cm, BM is perpendicular to AC, and DN is perpendicular to AC.



2. Find the area of the shaded region given that ABCD is a rectangle.



3. What measurements would you need to find the area of a regular hexagon?

Math Talk

4. What fraction of the total area of the rectangle is the area of the blue region?

Math Talk



5. Give a method to obtain a quadrilateral whose area is half that of a given quadrilateral.

Math Talk

One can derive special formulae to find the areas of a parallelogram, rhombus and trapezium.

© NCERT not to be republished

Parallelogram

We can derive a special formula for the area of a parallelogram by converting it into a rectangle of equal area.

? Give a method to convert a parallelogram into a rectangle of equal area.

You can try this using a cut-out of a parallelogram.

Construct AX perpendicular to CD — represented in short as $AX \perp CD$. We call this a **height** of the parallelogram. Cut the parallelogram into ΔAXD and trapezium ABCX.



? Can ΔAXD and ABCX fit together, as shown in the figure, to get a rectangle?

One simple way to check this is to identify the triangle that can complete ABCX to a rectangle, and then check if this triangle is congruent to ΔAXD.



Observe that $\angle X = 90°$, and so $\angle A = 90°$, since $AB \parallel XC$. We need another right angle to get a rectangle (what about the fourth angle?). To get the third right angle, extend XC to the right and then construct a line perpendicular to XC that passes through B. The ΔBYC completes ABCX to a rectangle. Is ΔAXD congruent to it?

BY = AX (since ABYX is a rectangle)
$\angle BYC = \angle AXD = 90°$
BC = AD (since ABCD is a parallelogram)

So, by the RHS congruency criterion, $\Delta BYC \cong \Delta AXD$. Thus, ΔAXD will fit exactly over the region occupied by ΔBYC, and convert the parallelogram into a rectangle.

The process of cutting a figure into pieces and rearranging them to get a different figure of equal area is called **dissection.**

© NCERT not to be republished

How do we find the area of a parallelogram by dissecting it into a rectangle?



We have

Area of the parallelogram ABCD = Area of the rectangle ABYX.

Area of the rectangle ABYX = AX × XY.

AX is the height of the parallelogram.

Is there a relation between XY and DC?

Since DX = CY, we get DC = XY by adding the common part XC to DX and CY. Since DC is the base of the parallelogram, we get

Area of the parallelogram = base × height.

Can the area of the parallelogram be determined by taking another side as the base and its corresponding height?



Can the parallelogram be cut along CZ and rearranged to form a rectangle?

It can be seen that this is indeed possible, and so any side and its corresponding height can be used to find the area of a parallelogram.

Figure it Out

1. Observe the parallelograms in the figure below.

   (i) What can we say about the areas of all these parallelograms?

   (ii) What can we say about their perimeters? Which figure appears to have the maximum perimeter, and which has the minimum perimeter?



© NCERT not to be republished

2. Find the areas of the following parallelograms:



(i)



(ii)



(iii)



(iv)

3. Find QN.



4. Consider a rectangle and a parallelogram of the same sidelengths: 5 cm and 4 cm. Which has the greater area? [**Hint:** Imagine constructing them on the same base.]



5. Give a method to obtain a rectangle whose area is twice that of a given triangle. What are the different methods that you can think of?

© NCERT not to be republished

6. [*Śulba-Sūtras*] Give a method to obtain a rectangle of the same area as a given triangle.

7. [*Śulba-Sūtras*] An isosceles triangle can be converted into a rectangle by dissection in a simpler way. Can you find out how to do it?



[**Hint:** Show that triangles ΔADB and ΔADC can be made into halves of a rectangle. Figure out how they should be assembled to get a rectangle. Use cut-outs if necessary.]

8. [*Śulba-Sūtras*] Give a method to convert a rectangle into an isosceles triangle by dissection.

9. Which has greater area — an equilateral triangle or a square of the same sidelength as the triangle? Which has greater area — two identical equilateral triangles together or a square of the same sidelength as the triangle? Give reasons.

Rhombus

Since a rhombus is a parallelogram, the area formula for a parallelogram holds for a rhombus as well. However, the additional properties of a rhombus give us another method to transform a rhombus into a rectangle of the same area by dissection. This method occurs in one of the *Śulba-Sūtras*.

? Try working this out!





© NCERT not to be republished



Since ABCD is a rhombus, all its sides have equal length, and the diagonals are perpendicular bisectors of each other. Therefore, ΔABD and ΔCBD are isosceles triangles. Each of them can be transformed into a rectangle of equal area, and the two rectangles can then be joined to form a single rectangle. This rectangle, say WXYZ, has the same area as the rhombus ABCD.

? What are the sidelengths of the rectangle WXYZ?

From the dissection, we can see that

XW = length of the diagonal AC, and
WZ = half the length of the other diagonal BD.

Thus, we have

$$\begin{aligned}\text{Area of rhombus ABCD} &= \text{Area of rectangle WXYZ}\\ &= XW \times WZ\\ &= AC \times \frac{BD}{2}\\ &= \frac{1}{2} \times AC \times BD\end{aligned}$$

Therefore,

Area of a rhombus = $\frac{1}{2}$ × *product of diagonals.*

? Area of rhombus ABCD can also be determined by finding the areas of ΔADB and ΔCDB. What formula does this give us?

Since the diagonals are perpendicular to each other, we have



$$\text{Area } (\Delta ADB) = \frac{1}{2} \times AO \times BD, \text{ and}$$

$$\text{Area } (\Delta CDB) = \frac{1}{2} \times CO \times BD, \text{ and}$$

Area of rhombus ABCD = Area (ΔADB) + Area (ΔCDB).

© NCERT not to be republished

? Simplify the expression to show that we get the same formula for the area of a rhombus in terms of its diagonals.

Trapezium

? Find the areas of the following trapeziums by breaking them into figures whose areas can be computed.



One way of finding the area of a trapezium is by breaking it into a rectangle and triangles.

? Consider a trapezium WXYZ with WX ∥ ZY. Find its area.



Construct $WM \perp ZY$, and $XN \perp ZY$ (WM and XN perpendicular to ZY).

? Is WXNM a rectangle?

∠MWX = ∠NXW = 90°, since WX∥ZY and the interior angles on the same side of a transversal (WM and XN) add up to 180°. Therefore, WXNM is a rectangle.

We have

$$\text{Area WXYZ} = \text{Area } (\Delta WMZ) + \text{Area WXNM} + \text{Area } (\Delta XNY)$$

$$= \frac{1}{2} \times MZ \times WM + WX \times WM + \frac{1}{2} \times NY \times XN$$

Let us assign letter numbers to the lengths that we need to find the area of the trapezium. Let MZ = x, WM = XN = h, WX = a, NY = y.

So we get

$$\text{Area WXYZ} = \frac{1}{2} hx + ha + \frac{1}{2} hy$$

$$= h\left(\frac{1}{2} x + a + \frac{1}{2} y\right)$$

$$= h\left(\frac{x + y + 2a}{2}\right)$$

$$= \frac{1}{2} h(x + y + 2a).$$



© NCERT not to be republished

We have taken the length of one of the parallel sides as a. Let b be the length of the other parallel side.

Can the area of the trapezium be expressed in terms of a, b and h?

To replace $x + y$ in the area expression with a and b, observe that $b = x + y + a$. Subtracting a from both sides, we get

$$x + y = b - a.$$

Using this, we get

$$\text{Area WXYZ} = \frac{1}{2} h(b - a + 2a)$$

$$= \frac{1}{2} h(a + b).$$

Therefore,

Area of a trapezium $= \frac{1}{2} \times$ *height* $\times$ *sum of the parallel sides.*

? Will this formula hold for a trapezium that looks like this?



There are different ways of approaching this, which are sketched below. Complete the arguments.

Approach 1: Rectangle and Triangles



Area ABCD = Area ABED + Area ΔBEC

Area ABED = Area ABEF – Area ΔAFD

Approach 2: Parallelogram and Triangle



Draw BG ∥ AD

? Will Approach 2 work for any type of trapezium?

Math Talk

© NCERT not to be republished

Finding the Area Using Two Copies of the Trapezium

There is another interesting way of finding the area of a trapezium. Consider two copies of the given trapezium in which AB∥CD. Rotate the second copy as shown.



? What figure will we get when the two trapeziums are joined along BC?

The possibilities are either a 6-sided figure or a 4-sided figure (quadrilateral).

Possibilities



6-sided figure



Quadrilateral

We can rule out the first possibility by looking at the sum of angles x and y.

Since AB ∥ CD, we have $x + y = 180$, since they are internal angles along the same side of the transversal (BC). So AB́ and A´CD are straight lines. Therefore, the resulting figure is a quadrilateral.

? What type of a quadrilateral is this?

Let us look at the other two angles of the trapezium.



We have $u + v = 180$. Therefore, AD∥Ď A´, since the sum of the internal angles along the same side of the transversal A´D is 180°. Since we already have AĎ ∥ A´D, the quadrilateral AĎ A´D is actually a parallelogram.



© NCERT not to be republished

$$\text{Area of the trapezium} = \frac{1}{2} \times \text{Area of the parallelogram}$$

$$= \frac{1}{2} h(a + b).$$

Figure it Out

1. Find the area of a rhombus whose diagonals are 20 cm and 15 cm.
2. Give a method to convert a rectangle into a rhombus of equal area using dissection.
3. Find the areas of the following figures:



(i)



(ii)



(iii)



(iv)

4. [*Śulba-Sūtras*] Give a method to convert an isosceles trapezium to a rectangle using dissection.
5. Here is one of the ways to convert trapezium ABCD into a rectangle EFGH of equal area —



Given the trapezium ABCD, how do we find the vertices of the rectangle EFGH?

[**Hint:** If $\Delta AHI \cong \Delta DGI$ and $\Delta BEJ \cong \Delta CFJ$, then the trapezium and rectangle have equal areas.]

Math Talk

© NCERT not to be republished

6. Using the idea of converting a trapezium into a rectangle of equal area, and vice versa, construct a trapezium of area 144 cm^2.

Math Talk

7. A regular hexagon is divided into a trapezium, an equilateral triangle, and a rhombus, as shown. Find the ratio of their areas.



8. ZYXW is a trapezium with ZY ∥ WX. A is the midpoint of XY. Show that the area of the trapezium ZYXW is equal to the area of ΔZWB.



Areas in Real Life

? What do you think is the area of an A4 sheet?
Its sidelengths are 21 cm and 29.7 cm. Now find its area.

? What do you think is the area of the tabletop that you use at school or at home? You could perhaps try to visualise how many A4 sheets can fit on your table.

The dimensions of furniture like tables and chairs are sometimes measured in inches (in) and feet (ft).

1 in = 2.54 cm
1 ft = 12 in

? Express the following lengths in centimeters:
(i) 5 in (ii) 7.4 in

? Express the following lengths in inches:
(i) 5.08 cm (ii) 11.43 cm

? How many cm^2 is 1 in^2?



So, 1 in^2 = 2.54^2 cm^2 = 6.4516 cm^2.

© NCERT not to be republished

? How many cm^2 is 10 in^2?

$$10\ in^2 = 10 \times 6.4516\ cm^2 = 64.516\ cm^2.$$

? Convert 161.29 cm^2 to in^2.

Every 6.4516 cm^2 gives an in^2. Hence,

$$161.29\ cm^2 = \frac{161.29}{6.4516}\ in^2.$$

? Evaluate the quotient.

? What do you think is the area of your classroom?

Areas of classroom, house, etc., are generally measured in ft^2 or m^2.

? How many in^2 is 1 ft^2?

? What do you think is the area of your school? Make an estimate and compare it with the actual data.

Larger areas of land are also measured in acres.

$$1\ acre = 43{,}560\ ft^2.$$

Besides these units, different parts of India use different local units for measuring area, such as *bigha*, *gaj*, *katha*, *dhur*, *cent*, *ankanam*, etc.

? Find out the local unit of area measurement in your region.

? What do you think is the area of your village/town/city? Make an estimate and compare it with the actual data.

Larger areas are measured in km^2.

? How many m^2 is a km^2?

? How many times is your village/town/city bigger than your school?

? Find the city with the largest area in (i) India, and (ii) the world.

? Find the city with the smallest area in (i) India, and (ii) the world.

SUMMARY

- *Area of a triangle* = $\frac{1}{2}$ × *base* × *height.*
- *The area of any polygon can be evaluated by breaking it into triangles.*
- *Area of a parallelogram = base × height.*
- *Area of a rhombus* = $\frac{1}{2}$ × *product of its diagonals.*
- *Area of a trapezium* = $\frac{1}{2}$ × *height* × *sum of parallel sides.*

© NCERT not to be republished

LEARNING MATERIAL SHEETS

© NCERT not to be republished

1	
2	
3	
4	
5	
6	
7	
8	
9	
10	
11	
12	
13	
14	
15	
16	
17	
18	
19	
20	
21	
22	
23	
24	

1	
2	
3	
4	
5	
6	
7	
8	
9	
10	
11	
12	
13	
14	
15	
16	
17	
18	
19	
20	
21	
22	
23	
24	

1	
2	
3	
4	
5	
6	
7	
8	
9	
10	
11	
12	
13	
14	
15	
16	
17	
18	
19	
20	
21	
22	
23	
24	

© NCERT not to be republished

© NCERT
not to be republished

Isometric Grid



© NCERT not to be republished

© NCERT
not to be republished